

WINDOW ELEVATIONS		
STORY	1ST FLR	
ID	W11	W12
QTY	1	1
NOMINAL SIZE	2'-9" x 8'-0 1/2"	10'-0" x 7'-11 1/2"
ELEVATION VIEW		
WINDOW TYPE	FIXED	FIXED, 2 PANEL

2ND FLR										
STORY	2ND FLR									
ID	W21	W21a	W22	W23	W24	W24a	W28	W28a	W29	W29a
QTY	4	1	3	2	1	1	1	1	1	2
NOMINAL SIZE	2'-6" x 9'-0"	4'-0" x 9'-0"	2'-6" x 9'-0"	2'-6" x 9'-0"	2'-6" x 6'-0"	2'-6" x 6'-11 1/2"	5'-0" x 9'-0"	2'-6" x 9'-0"	7'-0" x 9'-0"	2'-5" x 9'-0"
ELEVATION VIEW										
WINDOW TYPE	FIXED	FIXED	FIXED/AWNING	CASEMENT	AWNING	AWNING	FIXED	FIXED/AWNING	FIXED	FIXED/AWNING

3RD FLR										
STORY	3RD FLR									
ID	W31	W31a	W32	W33	W34	W38	W38a	W39	W39a	W41
QTY	2	1	6	2	2	1	1	1	2	1
NOMINAL SIZE	2'-6" x 9'-6"	4'-0" x 9'-6"	2'-6" x 9'-6"	2'-6" x 9'-6"	2'-6" x 6'-6"	5'-0" x 9'-6"	2'-6" x 9'-6"	7'-0" x 9'-6"	2'-6" x 9'-6"	2'-6" x 9'-8"
ELEVATION VIEW										
WINDOW TYPE	FIXED	FIXED	FIXED/AWNING	CASEMENT	AWNING	FIXED	FIXED/AWNING	FIXED	FIXED/AWNING	FIXED

4TH FLR										
STORY	4TH FLR									
ID	W41a	W41b	W41c	W41d	W42	W48	W48a	W49	W49a	
QTY	1	1	1	1	1	1	1	1	2	
NOMINAL SIZE	2'-6" x 9'-0"	5'-0" x 9'-0"	4'-0" x 9'-8"	3'-6" x 9'-0"	2'-6" x 9'-0"	5'-0" x 9'-0"	2'-6" x 9'-0"	7'-0" x 9'-0"	2'-8" x 9'-0"	
ELEVATION VIEW										
WINDOW TYPE	FIXED	FIXED	FIXED	FIXED	FIXED/AWNING	FIXED	FIXED/AWNING	FIXED	FIXED	

WINDOW SCHEDULE										
STORY	ID	WINDOW TYPE	QTY	MANUF.	NOMINAL WINDOW SIZE		AREA OF GLAZING	SILL (Above Floor Ref)	NOTES	
					W	H				
1ST FLR	W11	FIXED	1	See Notes	2'-9"	8'-0 1/2"	23	0'-7"		
	W12	FIXED, 2 PANEL	1		10'-0"	7'-11 1/2"	80	0'-0"		
			2			103 sq ft				
2ND FLR	W21	FIXED	4		2'-6"	9'-0"	23	0'-2"		
	W21a	FIXED	1		4'-0"	9'-0"	36	0'-2"		
	W22	FIXED/AWNING	3		2'-6"	9'-0"	23	0'-2"		
	W23	CASEMENT	2		2'-6"	9'-0"	23	0'-2"		
	W24	AWNING	1		2'-6"	6'-0"	15	3'-2"		
	W24a	AWNING	1		2'-6"	6'-11 1/2"	18	2'-3"		
	W28	FIXED	1		5'-0"	9'-0"	44	0'-2"	Mulled with W28 series	
	W28a	FIXED/AWNING	1		2'-6"	9'-0"	23	0'-2"	Mulled with W28 series	
	W29	FIXED	1		7'-0"	9'-0"	64	0'-2"	Mulled with W29 series	
	W29a	FIXED/AWNING	2		2'-5"	9'-0"	22	0'-2"	Mulled with W29 series	
			17			449 sq ft				
3RD FLR	W31	FIXED	2		2'-6"	9'-6"	24	0'-2"		
	W31a	FIXED	1		4'-0"	9'-6"	38	0'-2"		
	W32	FIXED/AWNING	6		2'-6"	9'-6"	24	0'-2"		
	W33	CASEMENT	2		2'-6"	9'-6"	24	0'-2"		
	W34	AWNING	2		2'-6"	6'-6"	17	3'-2"		
	W38	FIXED	1		5'-0"	9'-6"	48	0'-2"	Mulled with W38 series	
	W38a	FIXED/AWNING	1		2'-6"	9'-6"	24	0'-2"	Mulled with W38 series	
	W39	FIXED	1		7'-0"	9'-6"	67	0'-2"	Mulled with W39 series	
	W39a	FIXED/AWNING	2		2'-6"	9'-6"	24	0'-2"	Mulled with W39 series	
			18			499 sq ft				
4TH FLR	W41	FIXED	1		2'-6"	9'-8"	25	0'-2"		
	W41a	FIXED	1		2'-6"	9'-0"	23	0'-10"		
	W41b	FIXED	1		5'-0"	9'-0"	46	0'-10"		
	W41c	FIXED	1		4'-0"	9'-8"	39	0'-2"		
	W41d	FIXED	1		3'-6"	9'-0"	32	0'-10"		
	W42	FIXED/AWNING	1		2'-6"	9'-0"	23	0'-10"		
	W48	FIXED	1		5'-0"	9'-0"	46	0'-10"	Mulled with W48 series	
	W48a	FIXED/AWNING	1		2'-6"	9'-0"	23	0'-10"	Mulled with W48 series	
	W49	FIXED	1		7'-0"	9'-0"	64	0'-10"	Mulled with W49 series	
	W49a	FIXED	2		2'-8"	9'-0"	24	0'-10"	Mulled with W49 series	
			11			369 sq ft				
			48			1,420 sq ft				

WINDOW GENERAL NOTES:

- Windows Basis of Design is Loewen Wood Clad Triple Glazed in sizes and configurations as shown in the window schedule. Basis of Design exterior color is "Clear Anodized" and interior finish to be primed wood. Hardware Basis of Design to be satin nickel "contemporary" style in satin nickel color. Loewen Exterior doors hardware to be also satin nickel and contemporary "Dallas" type. Preferred supplier: Pinnacle Window Solutions. Contact Chris Bailey chris@pinnaclewindowsolutions.net 207-588-6590 x12. See Project Specifications for additional information.
At the time of this submission, the Owner is also interested in other triple glazed options in similar quality and color. Contractor to provide options and samples for Owner and Architect review as requested.
- U-Value of windows to be maximum of 0.35 per IECC 2009 requirements, refer to specifications.
- Safety Glazing to be provided in windows and doors at hazardous locations in accordance with IBC 2009 Section 2406.4. This would include fixed or operable glass lites that are within 18" of the floor per IBC 2406.7 Item 7.1. Also, any single lite greater than 9sf requires safety glazing per item 7.2. As a result, it appears all windows and lite in this project requires safety glazing. Window manufacturer to verify.
- 4. Submittal requirements:** Contractor and/or window supplier is to provide corner sample of window with hardware for verification from Architect and Owner. Afterwards, but before procurement, Contractor to provide shop drawings for Architect's review.