130 EASTEREN PROMENADE

PORTLAND, MAINE

PROJECT DIRECTORY

OWNER
130 EASTERN PROMENADE LLC
110 MARGINAL WAY
PORTLAND, MAINE 04112

ARCHITECT
MARK MUELLER ARCHITECTS
100 COMMERCIAL STREET
SUITE #207
PORTLAND, MAINE 04101
P: 207.774.9057
F: 207.773.3851
E-MAIL: rfi@muellerarchitects.com

LANDSCAPE ARCHITECT
CARROLL ASSOCIATES
217 COMMERCIAL STREET
PORTLAND, MAINE 04101
P: 207.772.1552
E-MAIL: pcarroll@carroll-assoc.com

SURVEYOR
BACK BAY BOUNDARY, INC.
643 FOREST AVE.
PORTLAND, MAINE 04101
P: 207.774.2855

STRUCTURAL ENGINEER
SHELLEY ENGINEERING, INC.
P.O. BOX 1030
GRAY, MAINE 04039
P: 207.657.8031
M: 207.756.2296

CIVIL ENGINEER
BLAIS CIVIL ENGINEERS
780 BROADWAY
SOUTH PORTLAND, MAINE 04106
P: 207767.7300

SYMBOLS

- ROOM NUMBER
- DOOR NUMBER
- WINDOW TYPE
- BUILDING SECTION
- WALL SECTION
- DETAIL SECTION
- CASEWORK ELEVATION
- INTERIOR ELEVATION
- VERTICAL ELEVATION
- PARTITION TYPE
- COLUMN CENTER LINE

MATERIALS

- CONCRETE
- CONCRETE MASONRY UNIT
- GRAVEL
- SOIL
- STEEL
- WOOD FRAMING
- WOOD BLOCKING
- PLYWOOD
- GYPSUM BOARD
- SAT
- BATT INSULATION
- RIGID INSULATION
- EXPANSION MATERIAL
- FINISH WOOD

DRAWING INDEX

T-1.0 GENERAL ARCHITECTURAL INFORMATION, ABBREVIATIONS, SYMBOL LEGEND

CIVIL & LANDSCAPE DRAWINGS

- EXISTING CONDITIONS PLAN
L-1.0 SITE PREPARATION PLAN
L-2.0 SITE LAYOUT & MATERIALS PLAN
L-3.0 SITE GRADING PLAN
L-4.0 LANDSCAPE PLAN
L-5.0 SITE DETAILS
L-6.0 SITE DETAILS

ARCHITECTURAL DRAWINGS

EC-1.0 EXISTING/ DEMO FLOOR PLANS
EC-2.0 EXISTING/ DEMO ELEVATIONS
A-1.0 FIRST FLOOR PLAN
A-1.1 SECOND FLOOR PLAN
A-1.2 THIRD FLOOR PLAN
A-1.3 BASEMENT FLOOR PLAN
A-1.4 ROOF PLAN
A-1.5 SCHEDULES & WALL DETAILS
A-2.0 ELEVATIONS
A-2.1 ELEVATIONS
A-3.0 BUILDING SECTIONS
A-3.1 BUILDING SECTIONS
A-3.2 BUILDING SECTIONS
A-3.3 BUILDING SECTIONS
A-3.4 WALL SECTIONS
A-3.5 WALL SECTIONS
A-3.6 DETAILS
A-3.7 DETAILS

STRUCTURAL DRAWINGS

S1.0 -
S1.1 -
S1.2 -
S1.3 -
S1.4 -
S2.1 -
S2.2 -

ELECTRICAL DRAWINGS

E1 -

MECHANICAL DRAWINGS

P1 -

ABBREVIATIONS

AB	ANCHOR BOLT
AFF	ABOVE FINISH FLOOR
ALUM OR AL	ALUMINUM
BIT	BITUMINOUS
BM	BENCH MARK
BOT	BOTTOM
BRG	BEARING
BRK	BRICK
C	CARPET
CAB	CABINET
CC	CENTER TO CENTER
CL	CENTER LINE
CLG	CEILING
CONC	CONCRETE
CONT	CONTINUOUS
DBL	DOUBLE
DIA	DIAMETER
DIM	DIMENSION
DNA	DOES NOT APPLY
DTL	DETAIL
DWG	DRAWING
E	EAST
EA	EACH
EF	EACH FACE
EL	ELEVATION
ELEC	ELECTRICAL
ELEV	ELEVATOR
EHO	ELECTRO-MAGNETIC HOLD OPEN
ETR	EXISTING TO REMAIN
EQ	EQUAL
EW	EACH WAY
EXT	EXTERIOR
FDKB	FIRE DEPARTMENT KEY BOX
FDN	FOUNDATION
FX	FIRE EXTINGUISHER
FFE	FINISH FLOOR ELEVATION
FIN	FINISH
FIN FL OR FF	FINISH FLOOR
FIN GR	FINISH GRADE
FL	FLOOR
FR	FIRE RATING
FRMG	FRAMING
FT	FEET (FOOT)
FV	FIELD VERIFY
GA	GAUGE
GALV	GALVANIZED
GB	GRAB BARS
GC	GENERAL CONTRACTOR
GWB	GYPSUM WALL BOARD
HC	HANDICAP
HM	HOLLOW METAL
HORZ	HORIZONTAL
HT	HEIGHT
IF	INSIDE FACE
IN	INCHES
INSUL	INSULATION
INT	INTERIOR
JNT OR JT	JOINT
LOC	LOCATION
MAX	MAXIMUM
MECH	MECHANICAL
MFGR	MANUFACTURER
MIN	MINIMUM
MISC	MISCELLANEOUS
MRGB	MOISTURE RESISTANT GYPSUM BOARD
MTL	METAL
N	NORTH
NA	NOT APPLICABLE
NIC	NOT IN CONTACT
NO	NUMBER
NOM	NOMINAL
NTS	NOT TO SCALE
OA	OVERALL
OC	ON CENTER
OD	OUTSIDE DIAMETER
OPNG	OPENING
OPP	OPPOSITE
P	PAINT
PTD	PAINTED
PL	PLATE
PLY WD	PLYWOOD
PNL	PANEL
P.T.	PRESSURE TREATED
PTN	PARTITION
RE	REFER
REF	REFRIGERATOR
REINF	REINFORCED
REQD	REQUIRED
RM	ROOM
RO	ROUGH OPENING
S	SOUTH
SAT	SUSPENDED ACOUSTICAL TILE CEILING
SC	SHOWER CURTAIN
SD	SOAP DISPENSER
SCHED	SCHEDULE
SECT	SECTION
SHT	SHEET
SIM	SIMILAR
SND	SANITARY NAPKIN DISPOSAL
SQ	SQUARE
STD	STANDARD
STL	STEEL
STRUCT	STRUCTURAL
SV	SHEET VINYL
T	TEMPERED (GLASS)
THK	THICKNESS
TO	TOP OF
TOB	TOP OF BEAM
TOM	TOP OF MASONRY
TOW	TOP OF WALL
TP	TOILET PAPER DISPENSER
TUON	TYPICAL UNLESS OTHERWISE NOTED
TYP	TYPICAL
VB	VAPOR BARRIER
VCT	VINYL COMPOSITION TILE
VERT	VERTICAL
W	WEST
W/	WITH
WC	WATER CLOSET
WD	WOOD

GENERAL NOTES

1. THE BUILDING SHALL BE CONSTRUCTED TO CONFORM WITH ALL CURRENT APPLICABLE CODES INCLUDING, BUT NOT LIMITED TO, THE LATEST EDITIONS OF IBC, IECC, NFPA 101, ANSI, UFAS, HUD/AG, ADA/AG, MPS.

2. ALL WOOD IN CONTACT WITH CONCRETE SHALL BE PRESSURE PRESERVATIVE TREATED.

3. CONTRACTOR SHALL WORK FROM GIVEN DIMENSIONS AND LARGE SCALE DETAILS ONLY. DO NOT SCALE THE DRAWINGS.

4. INSTALL BLOCKING FOR SURFACE APPLIED FIXTURES, TRIM, CABINETS, COUNTER TOPS, AND GRAB BARS WHEN MOUNTED ON STUD WALLS, INCLUDING ALL FUTURE INSTALLATIONS.

5. ALL GRAB BARS SHALL BE ABLE TO SUPPORT A DEAD WEIGHT OF 250 LBS AT ANY POINT.

6. INSTALL MOISTURE RESISTANT GYPSUM BOARD IN RECYCLE/TRASH, JANITOR CLOSETS, AND ALL OTHER HIGH HUMIDITY AREAS, INCLUDING UNIT BATHROOMS.

7. ALL CAULKING AROUND WINDOWS SHALL BE NON-HARDENING TYPE SEALANT.

8. INSTALL U.L. FIRE-STOPPING SEALANT/SYSTEM EQUAL TO THE FIRE RATED FLOOR, CEILING AND WALL ASSEMBLY.

9. FIRESTOP VERTICAL MECHANICAL CHASES @ FLOOR & CEILING PENETRATIONS. CAULK JOINTS. COORDINATE AND FLASH ALL ROOF/WALL PENETRATIONS WITH THE SUB-TRADES.

10. CONTINUE SEPARATION WALLS TO UNDERSIDE OF FLOOR/CEILING ABOVE. UNIT TO UNIT, UNIT TO CORRIDOR, CORRIDOR WALLS, STORAGE WALLS, ELEVATOR, STAIRWELL WALLS, ETC.

11. REPORT ANY AND ALL DISCREPANCIES TO THE ARCHITECT PRIOR TO PROCEEDING WITH WORK.

12. PROJECT ASSUMES ALL EXISTING HAZARDOUS MATERIALS HAVE BEEN REMOVED PRIOR TO THE COMMENCEMENT OF WORK. ALL HAZARDOUS MATERIAL REMOVAL IS THE RESPONSIBILITY OF THE OWNER.

13. ALL WINDOWS IN SLEEPING ROOMS SHALL BE EGRESS WINDOWS MEETING THE FOLLOWING MINIMUM CLEAR OPENING REQUIREMENTS: 22" WIDE - 24" HIGH - 5.7 S.F.

14. ALL WINDOWS WITHIN 60" HORIZ. & VERT. DIMENSION OF STAIRS MUST BE TEMPERED.
ALL WINDOWS WITHIN 24" OF A DOOR SWING MUST BE TEMPERED.
ALL WINDOWS WITHIN A SHOWER ENCLOSURE MUST BE TEMPERED.

15. BUILDING INSULATION SHALL BE PROVIDED AS INDICATED & NOTED IF NOT SHOWN IN ITS ENTIRETY THROUGHOUT THE DRAWING SET. INSULATE ALL BATHROOM, LAUNDRY & MECH. ROOM WALLS & VENT PIPES.

16. BEAM, JOIST OR OTHER STRUCTURAL MEMBER PENETRATIONS NOT SHOWN OR INDICATED ON DRAWINGS MUST BE CONSULTED WITH THE ARCHITECT &/OR ENGINEER PRIOR TO WORK.

17. ANY CHANGE DURING CONSTRUCITON OF USE, OCCUPANCY OR CONSTRUCTION TYPE MUST BE DISCUSSED WITH ARCHITECT PRIOR TO ANY WORK PERFORMED AND SUBSTANTIAL TIME ALLOWED FOR REQUIRED CODE RESEARCH AND DRAWING MODIFICATIONS OR ADDITIONS.

PERMIT SET:
MAY 23, 2014

CITY OF PORTLAND, MAINE · RESURGAM
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 07/21/14

MARK MUELLER ARCHITECTS
A.I.A.
100 Commercial Street
Suite 205
Portland, Maine 04101
Phone: 207.774.9057
Email:
rfi@muellerarchitects.com

© COPYRIGHT 2013
MARK MUELLER ARCHITECTS

PROPOSED RENOVATIONS @:
130 EASTERN PROMENADE
FOR: 130 EASTERN PROMENADE LLC
110 MARGINAL WAY
PORTLAND, MAINE 04101

TITLE SHEET

REVISIONS

DATE
02.24.2011

PROJECT
130 E. PROM

DRAWN BY
MRP

CHECK BY
MLM

T-1.1