

Portland, Maine



Yes. Life's good here.

Danielle P. West-Chuhta
Corporation Counsel

Anne M. Torregrossa
Associate Counsel

Michael I. Goldman
Associate Counsel

July 15, 2016

NOTICE OF INTENT TO PROSECUTE

Lucille P. Tanner, Trustee of the Lucille P.
Tanner Rev. Trust
23 Oakmont Drive
Falmouth, Maine 04105

RE: 126 Eastern Promenade
CBL003 C003001

To Whom it May Concern,

Please see the attached Inspection Violations. The City of Portland Fire Department has referred this matter to me for prosecution. In order to avoid prosecution, you must submit to Fire Prevention Bureau a plan of action to remedy the violations no later than **July 29, 2016**.

**YOUR FAILURE TO SUBMIT A PLAN OF ACTION
WITHIN THE TIMEFRAME PROVIDED WILL RESULT IN
LEGAL ACTION AND THE IMPOSITION OF CIVIL PENALTIES.**

Please feel free to contact Tori Ross of the Fire Prevention Bureau at (207)874-8400 with any questions. I look forward to your anticipated cooperation and appreciate your efforts to help keep the citizens of Portland safe.

Sincerely,

Anne M. Torregrossa
Associate Corporation Counsel
City of Portland

**CITY OF PORTLAND
PORTLAND FIRE DEPARTMENT**

380 Congress Street
Portland, Maine 04101

353901

Inspection Violations

Owner/Manager Tanner Lucille P Trustee		Inspector Daniel Small	Inspection Date 6/22/2016
Location 0126 EASTERN PROM	CBL 003 C003001	Status Failed	Inspection Type Fire Company-FP Routine Inspec

Code	Int/Ext	Floor	Unit No.	Area	Compliance Date
------	---------	-------	----------	------	-----------------

1) 80.16

Violation: NFPA 101-7.9.3 EMERGENCY LIGHTS REQUIRE MAINTENANCE; 7.9.3 Periodic Testing of Emergency Equipment

7.9.3.1 Required emergency lighting systems shall be tested in accordance with one of the three options offered by 7.9.3.1.1, 7.9.3.1.2, or 7.9.3.1.3.

7.9.3.1.1 Testing of required emergency lighting systems shall be permitted to be conducted as follows:

(1) Functional testing shall be conducted monthly with a minimum of 3 weeks and a maximum of 5 weeks between tests, for not less than 30 seconds, except as otherwise permitted by 7.9.3.1.1(2).

(2) The test interval shall be permitted to be extended beyond 30 days with the approval of the authority having jurisdiction.

(3) Functional testing shall be conducted annually for a minimum 1-1/2 hours if the emergency lighting system is battery powered.

(4) The emergency lighting equipment shall be fully operational for the duration of the test required by 7.9.3.1.1(1) and (3).

(5) Written records of visual inspections and tests shall be kept by the owner for inspection by the authority having jurisdiction.

Notes: EMERGENCY LIGHT-REAR-SECOND FLOOR IS INOPERATIVE

2) 80.28

Violation: NFPA 101- 7.5.1.1 EXIT OBSTRUCTED; Where exits are not immediately accessible from an open floor area, continuous passageways, aisles, or corridors leading directly to every exit shall be maintained and shall be arranged to provide access for each occupant to not less than two exits by separate ways of travel, unless otherwise provided in 7.5.1.1.3 and 7.5.1.1.4.

Notes: 3RD FLOOR FRONT EMERGENCY EXIT IS BLOCKED

3) 91.25

Violation: NFPA 70 MISSING BOX COVERS; REFER TO NFPA 70, NATIONAL ELECTRICAL CODE, ON STANDARDS FOR MISSING BOX COVERS.

Notes: BASEMENT

4) 80.37

Violation: NFPA 101- 8.3.4.2 60 MINUTE FIRE DOOR REQUIRED; REFER TO NFPA 101- TABLE 8.3.4.2 THAT STATES FIRE DOOR ASSEMBLIES FOR VERTICAL SHAFTS (INCLUDING STAIRWAYS, EXITS, AND REFUSE CHUTES) ARE RATED AND REQUIRED FOR 1 HOUR.

Notes: APARTMENT DOORS ARE NOT RATED