PLAN NORTH

NOTES:

1. NEW WINDOW HEADERS SHALL BE (2)2x8's, U.N.O. SEE DETAIL 3/S3.0. CONTRACTOR TO VERIFY INTEGRITY OF EXISTING WINDOW HEADERS AND NOTIFY ENGINEER OF ANY CONCERNS.
2. PROVIDE (3)2x4 COLUMNS, U.N.O.
3. ALL EXTERIOR WALLS AND BEARING WALLS SHALL BE SHEATHED ON MIN. ONE SIDE WITH ½" APA RATED SHEATHING. NAIL EXTERIOR SHEATHING PANEL EDGES @ 4"o.c. BLOCK AND STAGGER ALL PANEL EDGES. SPACE NAILS AT 12" o.c. AT INTERMEDIATE PANEL EDGES.
4. (*) CONTRACTOR TO VERIFY CONDITION OF EXISTING ROOF RAFTERS AND NOTIFY ENGINEER OF ANY STRUCTURAL CONCERNS. SISTER EXISTING DAMAGED RAFTERS WITH NEW MEMBERS AS NOTED ON PLANS.

PLAN LEGEND

- BEARING WALL
- SHEAR WALL
- BEAM
- HSS COLUMN
- COLUMN FROM ABOVE
- COLUMN BELOW
- COLUMN ABOVE AND BELOW
- HOLD-DOWN

ROOF FRAMING PLAN

SCALE: 1/4"=1'-0"

PRINTED: Oct 03, 2017


CASCO BAY ENGINEERING
424 Fore Street
Portland, ME 04101
Phone 207.842.2800
Fax 207.842.2828
www.cascobayengineering.com


CLIENT:
DAVID MATERO ARCHITECTURE
100 FRONT STREET, SUITE 40
BATH, MAINE 04530

STATE OF MAINE
ERIC DUBE
No. 12630
LICENSED
PROFESSIONAL ENGINEER

MCMANN CONDO
26 MOODY STREET, PORTLAND MAINE

RESIDENTIAL RENNOVATION

ISSUED

| No. | DESCRIPTION | DR. BY | CKD. BY | DATE |
|---|---|---|---|---|
| A | ISSUE FOR REVIEW | SD | ED | 7-31-17 |
| B | FOR PERMIT ONLY | SD | TD | 8-1-17 |
| 0 | ISSUE FOR CONSTRUCTION | SD | ED | 10-3-17 |

SHEET TITLE:

ROOF FRAMING PLAN

| | |
|---|---|
| DESIGNED: | SD |
| DRAWN: | SD |
| DATE: | 10-3-2017 |
| PROJECT NUMBER: | 17-090 |

S1.4