Elevation Legend

01. Existing asphalt shingles, typ.
02. Smartside painted eave and rake trim w/crown
03. Smartside clapboard siding on WRB
04. Repair existing bracket,
05. High efficiency New window. typ.
06. Repoint, patch and infill brick to match existing
07. Smartside 5/4 x 6 Corner board
08. Smartside 5/4 x 8 Water table
09 5/4 x 4 Smartside window/door casing, refer to detail C/A9.1
10 Refurbish existing dentil moulding replace as needed
11 Deck w/ Pre-primed railings and supports, pntd. (Baird Brothers LJ5004 Balusters or similar)
12 Craftsman 8x8 no taper paneled column, pntd
13 Pre primed MDO panels w/ Smartside trim
14 PT Deck columns, joists, and supports
15 1x6 PT Lattice, pntd.
16 Not Used
17 New door
18 Repair existing dormer, New windows
19 Remove existing window, infill to match existing

1a Existing North Elevation

Scale: 1/4" 1'-0"

1 Proposed North Elevation

Scale: 1/4" 1'-0"

David Matero
Architecture

100 Front Street
Suite 40
Bath, Maine 04530
207.389.4278
info@davidmatero.com

Reviewed for Code Compliance
Inspections Division
Date: 10/05/17

Consultants

Casco Bay Engineering
Structural Engineer

Revisions

.

26 Moody Street Condominium

Portland, Maine

Job Number: 17.011
Date: 09.28.17
Scale: 1/4" = 1'-0"

Drawing Title:

Proposed & Existing North Elevation

A2.1

Issued for Permit

Copyright 2017 David Matero Architecture, LLC