1 SISTER TO EXIST. BEAM SECTION

3/4" = 1'-0"

2 DECK ATTACHMENT SECTION

3/4" = 1'-0"

NOTE:
1. PROVIDE (2) FULL HEIGHT KING STUDS ON EACH SIDE OF OPENING TO MATCH ½ OF INTERRUPTED STUDS @ WALL OPENING. MINIMUM (2) FULL HEIGHT KING STUDS @ EACH SIDE OF OPENING.
2. ALL HEADERS SUPPORTED BY MINIMUM OF (1) JACK STUD.
3. WINDOW SILL PLATES MINIMUM (2)-2x6 ON THE FLAT.

3 TYPICAL WINDOW HEADER DETAIL

N.T.S.

PRINTED: Aug 01, 2017

CASCO BAY ENGINEERING
424 Fore Street
Portland, ME 04101
Phone 207.842.2800
Fax 207.842.2828
www.cascobayengineering.com

CLIENT:
DAVID MATERO ARCHITECTURE
100 FRONT STREET, SUITE 40
BATH, MAINE 04530

STATE OF MAINE
ERIC DUBE
No. 12630
LICENSED
PROFESSIONAL ENGINEER

MCMANN CONDO
26 MOODY STREET, PORTLAND MAINE

RESIDENTIAL RENNOVATION

ISSUED

No.	DESCRIPTION	DR. BY	CKD. BY	DATE
A	ISSUE FOR REVIEW	SD	ED	7-31-17
B	FOR PERMIT ONLY	SD	TD	8-1-17

SHEET TITLE:

FRAMING DETAILS

DESIGNED:	SD
DRAWN:	SD
DATE:	7-31-2017
PROJECT NUMBER:	17-090

S3.0