PRINTED: Aug 01, 2017

PLAN NORTH

NOTES:

1. PROVIDE SIMPSON HANGERS AT ALL JOIST ENDS, TYP.
2. NEW WINDOW HEADERS SHALL BE (2)2x8's, U.N.O. SEE DETAIL 3/S3.0. CONTRACTOR TO VERIFY INTEGRITY OF EXISTING WINDOW HEADERS AND NOTIFY ENGINEER OF ANY CONCERNS.
3. PROVIDE (3)2x4 COLUMNS, U.N.O.
4. ALL EXTERIOR WALLS AND BEARING WALLS SHALL BE SHEATHED ON MIN. ONE SIDE WITH ½" APA RATED SHEATHING. NAIL EXTERIOR SHEATHING PANEL EDGES @ 4"o.c. BLOCK AND STAGGER ALL PANEL EDGES. SPACE NAILS AT 12" o.c. AT INTERMEDIATE PANEL EDGES.
5. (*) CONTRACTOR TO VERIFY CONDITION OF EXISTING FLOOR JOIST AND NOTIFY ENGINEER OF ANY STRUCTURAL CONCERNS. SISTER EXISTING DAMAGED JOISTS WITH NEW MEMBERS AS NOTED ON PLANS. SISTERED MEMBERS SHALL BE CONTINUOUS BETWEEN SUPPORTS.

PLAN LEGEND

- BEARING WALL
- SHEAR WALL
- BEAM
- HSS COLUMN
- COLUMN FROM ABOVE
- COLUMN BELOW
- COLUMN ABOVE AND BELOW
- HOLD-DOWN

THIRD FLOOR FRAMING PLAN

SCALE: 1/4"=1'-0" | -

CASCO BAY ENGINEERING
424 Fore Street
Portland, ME 04101
Phone 207.842.2800
Fax 207.842.2828
www.cascobayengineering.com

CLIENT:
DAVID MATERO ARCHITECTURE
100 FRONT STREET, SUITE 40
BATH, MAINE 04530

STATE OF MAINE
ERIC DUBE
No. 12630
LICENSED
PROFESSIONAL ENGINEER

MCMANN CONDO
26 MOODY STREET, PORTLAND MAINE

RESIDENTIAL RENNOVATION

ISSUED

No.	DESCRIPTION	DR. BY	CKD. BY	DATE
A	ISSUE FOR REVIEW	SD	ED	7-31-17
B	FOR PERMIT ONLY	SD	TD	8-1-17

SHEET TITLE:

THIRD FLOOR FRAMING PLAN

DESIGNED:	SD
DRAWN:	SD
DATE:	7–31–2017
PROJECT NUMBER:	17–090

S1.3