



REBAR LAP SPLICE TABLE

BAR SIZE	LAP LENGTH		
	3,000 PSI	3,500 PSI	4,000+ PSI
#3	30"	28"	24"
#4	36"	34"	32"
#5	48"	45"	42"
#6	56"	52"	48"
#7	81"	78"	72"
#8	93"	88"	80"

