Approved
Approved as Amended
Denied
Date: 07/06/17

NOTE: EXT. WALL ASSEMBLY @ WALL ON LOT LINE
PAINTED WOOD CLAPBOARDS TO MATCH
PAPER HOUSE WRAP
1/2" PLYWOOD SHEATHING
2X6 WOOD STUDS @ 16" O.C.
R 20 INSULATION TO CODE
6 MIL. PLASTIC VAPOR BARRIER
(2) LAYERS 5/8" FIRE RATED GYPSUM BOARD BOTH SIDES OF STUDS, PAINTED
SEE DETAIL ON THIS SHEET (A5)

ROOF ASSEMBLY
30 YR ASPHALT SHINGLES
WEATHER PROOFING
5/8" ADVANTEC SHEATHING
2X12 RAFTERS @ 16" O.C.
R 49 INSULATION TO CODE
1/2" BLOCKING
1/2" GYPSUM BOARD, PAINTED

EXT. WALL ASSEMBLY
PAINTED WOOD CLAPBOARDS TO MATCH
PAPER HOUSE WRAP
1/2" PLYWOOD SHEATHING
2X6 WOOD STUDS @ 16" O.C.
R 20 INSULATION TO CODE
6 MIL. PLASTIC VAPOR BARRIER
1/2" GYPSUM BOARD, PAINTED

FLOOR ASSEMBLY
3/4" WOOD FLOOR TO MATCH EXISTING
3/4" ADVANTEC SUB-FLOOR
BATT INSULATION
2X8 JOISTS @ 12" or 16" O.C.
1/2" BLOCKING
1/2" GYPSUM BOARD (NOT IN BASEMENT)

NOTE: SEE STRUCTURAL PLANS FOR ALL FRAMING AND FOUNDATION SPECIFICATIONS AND DETAILS

A BUILDING SECTION
SCALE: 1/4" = 1'-0"

B BUILDING SECTION
SCALE: 1/4" = 1'-0"

1 EAVE & WALL DETAIL @ 1 HR FIRE RATED WALL
SCALE: 3/4" = 1'-0"

STAIR DETAIL
SCALE: 1/4" = 1'-0"

C BUILDING SECTION
SCALE: 1/4" = 1'-0"

© 2008 RANDALL DESIGN

RANDALL DESIGN
architectural drafting & design
150 morrells mill rd. * n. berwick, me. 03906
207-651-6844 drandall@randalldesignme.com

CAVANAUGH RESIDENCE ADDITION
39 MUNJOY STREET PORTLAND, MAINE

Revisions:

Date: JULY 1, 2017
Drawn By: DGR
Scale: as shown
File: ----

Drawing Title:
BUILDING SECTIONS

Drawing Number:
A5