

WALL TYPES

<p>1 HR RATED WHERE INDICATED ON PLANS</p> <p>Ex1 R-Value=29 STC=58+/- Exterior Wood Clad Wall <small>1 Along West Side of Structure provide 5/8" Type "X" GWB and 5 1/2" mineral wool insulation for 1 hour protection prescriptively per Table 720.1(2) Item 1a-1.3</small></p>	<p>1 HOUR RATED WHERE INDICATED ON PLANS</p> <p>Ex2 R-Value=29 STC=58+/- Exterior Brick Wall <small>1 Along West Side of Structure provide 5/8" Type "X" GWB and 5 1/2" mineral wool insulation for 1 hour protection prescriptively per Table 720.1(2) Item 1a-1.3</small></p>	<p>Ex3 R-Value=29 STC=58+/- Exterior Metal Clad Wall</p>

					<p>OTHER WALL / AIR SPACE AS INDICATED ON PLANS</p> <p>WOOD FURRING OR FRAMING AS REQUIRED. SEE PLANS FOR LOCATIONS</p> <p>(1) LAYER OF 5/8" GYP</p>
<p>A1 NON RATED INTERIOR WALL 2x4 <small>SIM. TO A1 W/ SOUND ATTENUATION BATTS</small></p>	<p>A2 NON RATED INTERIOR WALL 2x6 <small>SIM. TO B2 W/ SOUND ATTENUATION BATTS</small></p>	<p>D1 TYP UNIT DEMISING WALL AT STAIRWELL 1-HOUR RATED PARTITION WALL, UL-U327 STC-54</p>	<p>D2 ELEVATOR HOISTWAY WALL 2 HOUR RATED WALL, UL-U305</p>	<p>F1 INTERIOR FURRING AS REQUIRED</p>	

General Notes:
 1. Refer to Project Specifications for Material Selections and Requirements

<p>FLOOR ASSEMBLIES</p> <p>Z1 TYPICAL 2ND, 3RD, 4TH FLOOR ASSEMBLY Wood Construction 1-HR Rated Horizontal Dwelling Unit Separation Assembly UL-1570 STC-64; IIC 62</p> <p>Z1a 2ND FLOOR ASSEMBLY - MIN. R-30 INSULATION IN CAVITY</p> <p>Z1b 4TH FLOOR ASSEMBLY - (1) LAYER OF 5/8" GYP BOARD OVER 1/2" RESILIENT CHANNELS AT 24" O.C.</p>	<p>Z2 TYPICAL FLOOR ASSEMBLY AT EXTERIOR DECKS Wood Construction 1-HR Rated Horizontal Dwelling Unit Separation Assembly American Wood Council Report No: WHI-651-031.1 STC-60 est; IIC 60 est.</p>	<p>Z3 TYPICAL ROOF STRUCTURE ASSEMBLY Wood Construction Non-Rated STC-52 est; IIC 52 est.</p>	<p>Z5 TYPICAL SLAB-ON-GRADE ASSEMBLY R-Value = 11</p>	<p>ROOF COVERING ASSEMBLIES</p> <p>RF-1 TYPICAL ROOF COVERING ASSEMBLY R-Value = 27 Minimum Class C</p>	<p>RF-2 TYPICAL GREEN ROOF R-Value = 27 Minimum Class C</p>
--	--	--	---	---	--

PARTITION TYPES
 SCALE: 1" = 1'-0"



FOR CITY REVIEW
 NOT FOR CONSTRUCTION

CALEB JOHNSON STUDIO
 110 EXCHANGE ST. 2ND FLOOR, PORTLAND, ME 04101
 1-207-263-9777

ARCHITECT
 DRAFTSPERSON:
 PJ/J/J/C/K
 DATE: 12/01/2017
 PROJECT STATUS: Site Plan Review

CONSULTANT:
 SUBMISSIONS:
 ISSUE: 001
 DATE: 12/01/2017
 DESCRIPTION: CITY REVIEW

CHANGES THIS ISSUE:
 ID DESCRIPTION

BRADY RESIDENCE
 Jim and Julia Brady
 9 Moody Street Portland ME 04101

A-601

BIM Server: bimservr.cjpb.me - BIM Server 21/9 Moody Street/9 Moody Street_10052017