

- 1. ALL DIMENSIONAL LUMBER SHALL BE No.1 / No. 2 SPRUCE PINE FIR UNLESS OTHERWISE NOTED.
- 2. DIMENSIONAL LUMBER NOTED AS P.T. SHALL BE No. 1 SOUTHERN PINE, PRESSURE TREATED.
- 3. ALL MATERIALS IN CONTACT WITH THE EXISTING ROOFING SHALL BE COMPATIBLE WITH THE EXISTING ROOFING. CONTRACTOR TO COORDINATE.
- 4. SPACE HANDRAILS AT MANUFACTURERS RECOMMENDED SPACING. HANDRAIL SPACING SHALL NOT EXCEED 5 FEET ON CENTER.
- 5. HANDRAIL SYSTEM MAY DIFFER FROM SHOWN. CONTRACTOR TO COORDINATE AND NOTIFY ENGINEER IF OTHER THAN SHOWN.
- 6. SEALING, FLASHING AND PROVIDING A WATERTIGHT ROOF SYSTEM IS THE RESPONSIBILITY OF THE CONTRACTOR.




424 Fore Street Portland, ME 04101 Phone 207.842.2800 Fax 207.842.2828 www.cascobayengineering.com

CLIENT:

## RYAN FITZGERALD

51 MORNING STREET PORTLAND, MAINE 04101

ST 51 MORNING ROOF DECK



SHEET TITLE:

## HANDRAIL CONN. **DETAIL**

DESIGNED:	PDR
DRAWN:	PDR
DATE:	06-16-14
PROJECT No:	14-069