

G-D-1

2000-0027

349 Park Ave.

High Bay Cooler Expansion

H.P. Hood

on Spreadsheet

**CITY OF PORTLAND, MAINE
DEVELOPMENT REVIEW APPLICATION
PLANNING DEPARTMENT PROCESSING FORM**

20000027

I. D. Number

H.P. Hood Inc.
Applicant
349 Park Ave, Portland, ME 04101
Applicant's Mailing Address
Phillip Dooughy Associates
Consultant/Agent
781-5346 781-2908
Applicant or Agent Daytime Telephone, Fax

3/8/00
Application Date
High Bay Cooler Expansion
Project Name/Description
349 Park Ave, Portland, Maine 04101
Address of Proposed Site
006-D-001
Assessor's Reference: Chart-Block-Lot

Proposed Development (check all that apply): New Building Building Addition Change Of Use Residential
 Office Retail Manufacturing Warehouse/Distribution Parking Lot Other (specify) _____
7,110 sf 1.7393
Proposed Building square Feet or # of Units Acreage of Site Zoning

Check Review Required:

Site Plan (major/minor) Subdivision # of lots _____ PAD Review 14-403 Streets Review
 Flood Hazard Shoreland Historic Preservation DEP Local Certification
 Zoning Conditional Use (ZBA/PB) Zoning Variance Other _____

Fees Paid: Site Plan \$400.00 Subdivisio _____ Engineer Review _____ Date 3/8/00

Planning Approval Status:

Reviewer sarah

Approved Approved w/Conditions See Attached Denied

Approval Date 5/3/00 Approval Expiration 5/3/01 Extension to _____ Additional Sheets Attached
 OK to Issue Building Permi sarah 5/4/00
signature date

Performance Guarantee Required* Not Required

* No building permit may be issued until a performance guarantee has been submitted as indicated below

<input type="checkbox"/> Performance Guarantee Accepted	_____	_____	_____
	date	amount	expiration date
<input checked="" type="checkbox"/> Inspection Fee Paid	_____	<u>\$300.00</u>	
	date	amount	
<input type="checkbox"/> Building Permit Issue	_____		
	date		
<input type="checkbox"/> Performance Guarantee Reduced	_____	_____	_____
	date	remaining balance	signature
<input type="checkbox"/> Temporary Certificate of Occupancy	_____	<input type="checkbox"/> Conditions (See Attached)	
	date		
<input type="checkbox"/> Final Inspection	_____	_____	
	date	signature	
Certificate Of Occupancy	_____		
	date		
Performance Guarantee Released	_____	_____	
	date	signature	
Performance Guarantee Submitted	_____	_____	
	submitted date	amount	expiration date
Performance Guarantee Released	_____	_____	
	date	signature	

**CITY OF PORTLAND, MAINE
DEVELOPMENT REVIEW APPLICATION
PLANNING DEPARTMENT PROCESSING FORM**

20000027

I. D. Number

H.P. Hood Inc.

Applicant

349 Park Ave, Portland, ME 04101

Applicant's Mailing Address

Phillip Dooughty Associates

Consultant/Agent

781-5346 **781-2908**

Applicant or Agent Daytime Telephone, Fax

3/8/00

Application Date

High Bay Cooler Expansion

Project Name/Description

349 Park Ave, Portland, Maine 04101

Address of Proposed Site

006-D-001

Assessor's Reference: Chart-Block-Lot

Proposed Development (check all that apply):
 New Building Building Addition Change Of Use Residential
 Office Retail Manufacturing Warehouse/Distribution Parking Lot Other (specify) _____

7,110 sf **1.7393**
Proposed Building square Feet or # of Units Acreage of Site Zoning

Check Review Required:

- | | | | |
|--|---|--|--|
| <input checked="" type="checkbox"/> Site Plan
(major/minor) | <input type="checkbox"/> Subdivision
of lots _____ | <input type="checkbox"/> PAD Review | <input type="checkbox"/> 14-403 Streets Review |
| <input type="checkbox"/> Flood Hazard | <input type="checkbox"/> Shoreland | <input type="checkbox"/> Historic Preservation | <input type="checkbox"/> DEP Local Certification |
| <input type="checkbox"/> Zoning Conditional
Use (ZBA/PB) | <input type="checkbox"/> Zoning Variance | <input type="checkbox"/> Other _____ | |

Fees Paid: Site Plan **\$400.00** Subdivision _____ Engineer Review _____ Date: **3/8/00**

Planning Approval Status:

Reviewer _____

- Approved Approved w/Conditions
See Attached Denied

Approval Date _____ Approval Expiration _____ Extension to _____ Additional Sheets
Attached

OK to Issue Building Permit _____ _____
signature date

Performance Guarantee Required* Not Required

* No building permit may be issued until a performance guarantee has been submitted as indicated below

- | | | | |
|---|----------------|--|-----------------|
| <input type="checkbox"/> Performance Guarantee Accepted | _____ | _____ | _____ |
| | date | amount | expiration date |
| <input type="checkbox"/> Inspection Fee Paid | _____ | _____ | |
| | date | amount | |
| <input type="checkbox"/> Building Permit Issued | _____ | | |
| | date | | |
| <input type="checkbox"/> Performance Guarantee Reduced | _____ | _____ | _____ |
| | date | remaining balance | signature |
| <input type="checkbox"/> Temporary Certificate of Occupancy | _____ | <input type="checkbox"/> Conditions (See Attached) | |
| | date | | |
| <input type="checkbox"/> Final Inspection | _____ | _____ | |
| | date | signature | |
| <input type="checkbox"/> Certificate Of Occupancy | _____ | | |
| | date | | |
| <input type="checkbox"/> Performance Guarantee Released | _____ | _____ | |
| | date | signature | |
| <input type="checkbox"/> Defect Guarantee Submitted | _____ | _____ | _____ |
| | submitted date | amount | expiration date |


STORMWATER MANAGEMENT REPORT

for the

**H.P. HOOD, INC.
BUILDING EXPANSION PROJECT**

**Completed By
Dufresne-Henry, Inc.**

**Completed For
Phillip J. Doughty Associates - Architects**



March 2000



BACKGROUND SUMMARY

PROJECT DESCRIPTION

H.P. Hood, Inc. is proposing an expansion to its principal facility located at 340 Park Avenue in Portland, Maine. The expansion includes the construction of a high bay cooler building located adjacent to the existing main building and will encompass a total area of approximately 7,100 square feet.

The existing H.P. Hood, Inc. site is approximately 2 acres and contains the main building facility, loading docks, trailer storage area, and parking lot. The entire area is paved and includes an existing stormwater drainage system consisting of catchbasins that convey stormwater runoff to the City combined sewer system on Park Avenue.

This drainage analysis was prepared to determine the stormwater runoff effects of the H.P. Hood, Inc. expansion project. Drainage calculations for pre-development conditions and post-development conditions have been developed to determine the difference between existing drainage conditions and those resulting from the proposed building expansion.

DRAINAGE ANALYSIS SUMMARY

INTRODUCTION

There is one distinct drainage area at the project site in the pre and post-development conditions and includes the existing H.P. Hood, Inc. facility and bituminous pavement parking lot to the property boundary. Stormwater management on the site will not be significantly affected by the proposed expansion. Proposed regrading will include slight modifications to existing grades in the vicinity of the proposed building to promote drainage to existing and proposed catchbasins. The proposed project will be designed such that no negative impacts to adjacent properties, or the City sewer system are anticipated.

METHODOLOGY

In order to compare the stormwater characteristics of today with the future stormwater characteristics of the site, computer modeling using HydroCad software was employed which incorporates the methodology outlined in the U.S. Natural Resources Conservation Service's (NRCS) Technical Release Number 20 (TR-20). Runoff was calculated for the 2, 10 and 25-year, 24 hour storm events. The one day precipitation values for the Portland, ME and the project site are as follows:

2-Year, 24 Hour Precipitation - 3.0 inches
10-Year, 24 Hour Precipitation - 4.7 inches
25-Year, 24 Hour Precipitation - 5.5 inches

Since the H.P. Hood, Inc. facility is located in southeast Maine, a Type III distribution was utilized throughout this study. Also, the project site has been designated as impervious in the pre and post-development conditions for this study. All curve number and time of concentration calculations may be found along with computer generated documentation following this narrative.

STORMWATER RUNOFF ANALYSIS

Subcatchments 1, Pre-Development and Post-Development Conditions

The drainage area encompassing the expansion project to the H.P. Hood facility is approximately 2 acres. A majority of the stormwater runoff generated adjacent to the project site is conveyed to the City sewer system through drainage structures not considered in this report, and therefore was not included in the stormwater runoff calculations. This area has been analyzed as one subcatchment for the entire drainage area for the pre-development conditions and for the post-development conditions (See Dwg. A, Pre-Development Conditions and Dwg B, Post-Development Conditions). Subcatchment 1 represents the area which drains to DMH 1 prior to being discharged through a 20-inch vitrified clay pipe from the project site. Generally, stormwater runoff generated on the project site sheet flows in a southwesterly direction to an existing catchbasin that conveys the collected stormwater runoff to DMH 1 through an existing 12-inch RCP pipe.

In the post-development condition, Subcatchment 1 is essentially unchanged. The building expansion results in less bituminous pavement on the site but the amount of impervious area at the site is unchanged. Also, as part of the proposed expansion, stormwater runoff is conveyed through 12-inch RCP pipes around the proposed expansion due to existing CB 2 being removed and existing CB 1 being removed and replaced with a new catchbasin to the east of the new building. Relocated CB 1 will tie-into two proposed structures installed along the north side of the building (DMH-2 and CB-3). As in the pre-development condition, a majority of the stormwater runoff generated on the site is conveyed to DMH 1 prior to being discharged from the project site.

The estimated peak rates of runoff in cubic feet per second (CFS) in the pre-development and post-development conditions for Subcatchments 1, with the projected differences in parenthesis are as follows:

<u>Pre-Development, 2 year storm</u>		<u>Post-Development, 2 year storm</u>	
Subcatchment 1	6.07 CFS	Subcatchment 1	6.07 CFS (0 CFS)
<u>Pre-Development, 10 year storm</u>		<u>Post-Development, 10 year storm</u>	
Subcatchment 1	9.58 CFS	Subcatchment 1	9.58 CFS (0 CFS)
<u>Pre-Development, 25 year storm</u>		<u>Post-Development, 25 year storm</u>	
Subcatchment 1	11.23 CFS	Subcatchment 1	11.23 CFS (0 CFS)

CONCLUSIONS

The existing 12-inch RCP pipe conveying stormwater runoff to DMH 1 was analyzed in the post-development conditions using the Field's Hydraulic Calculator based on Manning's Equation. The results of this analysis demonstrated that sufficient capacity exists in the 12-inch RCP pipe to convey stormwater runoff for the 10-year storm event. During the 25-year storm event, the 12-inch RCP pipe is flowing at capacity producing 1.5 feet of headwater in the existing catchbasin. Lastly, the existing 18-inch RCP pipe draining DMH 1 has sufficient capacity to convey stormwater runoff for the 25-year storm event in the post-development conditions.

Therefore, the proposed development will have no adverse impact on Subcatchment 1. Projected post-development peak runoff quantities and the quality of stormwater runoff will not change from pre-development conditions.

Data for HP HOOD COOLER EXPANSION


TYPE III 24-HOUR RAINFALL= 3.00 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

WATERSHED ROUTING =====



SUBCATCHMENT 1 = DRAINAGE AREA TO CATCH BASIN (RIM-11.43') -> REACH 1

REACH 1 = ->

Data for HP HOOD COOLER EXPANSION

TYPE III 24-HOUR RAINFALL= 3.00 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

SUBCATCHMENT 1

DRAINAGE AREA TO CATCH BASIN (RIM-11.43')

PEAK= 6.07 CFS @ 11.99 HRS, VOLUME= .39 AF

ACRES	CN	
2.07	98	IMPERVIOUS

SCS TR-20 METHOD
 TYPE III 24-HOUR
 RAINFALL= 3.00 IN
 SPAN= 10-20 HRS, dt=.1 HRS

Method	Comment	Tc (min)
TR-55 SHEET FLOW	Segment ID:	1.6
Smooth surfaces n=.011 L=205'	P2=5.5 in s=.022 '/'	
CIRCULAR CHANNEL	Segment ID:	.3
12" Diameter a=.79 sq-ft Pw=3.1' r=.25'		
s=.0066 '/' n=.011 V=4.36 fps L=85' Capacity=3.4 cfs		
Total Length= 290 ft		Total Tc= 1.9

Data for HP HOOD COOLER EXPANSION

TYPE III 24-HOUR RAINFALL= 3.00 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

REACH 1

Qin = 6.07 CFS @ 11.99 HRS, VOLUME= .39 AF

Qout= 6.00 CFS @ 11.99 HRS, VOLUME= .39 AF, ATTEN= 1%, LAG= 0.0 MIN

DEPTH (FT)	END AREA (SQ-FT)	DISCH (CFS)
0.00	0.00	0.00
.15	.09	.26
.30	.25	1.09
.45	.45	2.43
1.05	1.32	10.39
1.20	1.52	12.13
1.35	1.68	13.23
1.41	1.72	13.35
1.46	1.75	13.23
1.50	1.77	12.41

18" PIPE

n= .011

LENGTH= 55 FT

SLOPE= .01 FT/FT

STOR-IND+TRANS METHOD

PEAK DEPTH= .72 FT

PEAK VELOCITY= 7.2 FPS

TRAVEL TIME = .1 MIN

SPAN= 10-20 HRS, dt=.1 HRS

2 x FINER ROUTING

Data for HP HOOD COOLER EXPANSION POST-DEVELOPMENT


TYPE III 24-HOUR RAINFALL= 3.00 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

WATERSHED ROUTING =====



SUBCATCHMENT 1 = DRAINAGE AREA TO CATCH BASIN (RIM-11.43') -> REACH 1

REACH 1 = ->

Data for HP HOOD COOLER EXPANSION POST-DEVELOPMENT

TYPE III 24-HOUR RAINFALL= 3.00 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

SUBCATCHMENT 1

DRAINAGE AREA TO CATCH BASIN (RIM-11.43')

PEAK= 6.07 CFS @ 11.99 HRS, VOLUME= .39 AF

ACRES	CN	
2.07	98	IMPERVIOUS

SCS TR-20 METHOD
 TYPE III 24-HOUR
 RAINFALL= 3.00 IN
 SPAN= 10-20 HRS, dt=.1 HRS

Method	Comment	Tc (min)
TR-55 SHEET FLOW	Segment ID:	1.6
Smooth surfaces n=.011 L=205'	P2=5.5 in s=.022 '/'	
CIRCULAR CHANNEL	Segment ID:	.3
12" Diameter a=.79 sq-ft Pw=3.1' r=.25'		
s=.0066 '/ n=.011 V=4.36 fps L=85' Capacity=3.4 cfs		
Total Length= 290 ft		Total Tc= 1.9

Data for HP HOOD COOLER EXPANSION POST-DEVELOPMENT

TYPE III 24-HOUR RAINFALL= 3.00 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

REACH 1

Qin = 6.07 CFS @ 11.99 HRS, VOLUME= .39 AF
Qout= 6.00 CFS @ 11.99 HRS, VOLUME= .39 AF, ATTEN= 1%, LAG= 0.0 MIN

DEPTH (FT)	END AREA (SQ-FT)	DISCH (CFS)	18" PIPE	STOR-IND+TRANS METHOD
0.00	0.00	0.00		PEAK DEPTH= .72 FT
.15	.09	.26	n= .011	PEAK VELOCITY= 7.2 FPS
.30	.25	1.09	LENGTH= 55 FT	TRAVEL TIME = .1 MIN
.45	.45	2.43	SLOPE= .01 FT/FT	SPAN= 10-20 HRS, dt=.1 HRS
1.05	1.32	10.39		2 x FINER ROUTING
1.20	1.52	12.13		
1.35	1.68	13.23		
1.41	1.72	13.35		
1.46	1.75	13.23		
1.50	1.77	12.41		

Data for HP HOOD COOLER EXPANSION

TYPE III 24-HOUR RAINFALL= 4.70 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

SUBCATCHMENT 1

DRAINAGE AREA TO CATCH BASIN (RIM-11.43')

PEAK= 9.58 CFS @ 11.99 HRS, VOLUME= .62 AF

ACRES	CN	
2.07	98	IMPERVIOUS

SCS TR-20 METHOD
 TYPE III 24-HOUR
 RAINFALL= 4.70 IN
 SPAN= 10-20 HRS, dt=.1 HRS

Method	Comment	Tc (min)
TR-55 SHEET FLOW	Segment ID:	1.6
Smooth surfaces n=.011 L=205'	P2=5.5 in s=.022 '/'	
CIRCULAR CHANNEL	Segment ID:	.3
12" Diameter a=.79 sq-ft Pw=3.1' r=.25'		
s=.0066 '/' n=.011 V=4.36 fps L=85' Capacity=3.4 cfs		
Total Length= 290 ft		Total Tc= 1.9

Data for HP HOOD COOLER EXPANSION

TYPE III 24-HOUR RAINFALL= 4.70 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

REACH 1

Qin = 9.58 CFS @ 11.99 HRS, VOLUME= .62 AF

Qout= 9.49 CFS @ 11.99 HRS, VOLUME= .62 AF, ATTEN= 1%, LAG= 0.0 MIN

DEPTH (FT)	END AREA (SQ-FT)	DISCH (CFS)	18" PIPE	STOR-IND+TRANS METHOD
0.00	0.00	0.00		PEAK DEPTH= .98 FT
.15	.09	.26	n= .011	PEAK VELOCITY= 7.8 FPS
.30	.25	1.09	LENGTH= 55 FT	TRAVEL TIME = .1 MIN
.45	.45	2.43	SLOPE= .01 FT/FT	SPAN= 10-20 HRS, dt=.1 HRS
1.05	1.32	10.39		2 x FINER ROUTING
1.20	1.52	12.13		
1.35	1.68	13.23		
1.41	1.72	13.35		
1.46	1.75	13.23		
1.50	1.77	12.41		

Data for HP HOOD COOLER EXPANSION POST-DEVELOPMENT

TYPE III 24-HOUR RAINFALL= 4.70 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

SUBCATCHMENT 1

DRAINAGE AREA TO CATCH BASIN (RIM-11.43')

PEAK= 9.58 CFS @ 11.99 HRS, VOLUME= .62 AF

ACRES	CN	
2.07	98	IMPERVIOUS

SCS TR-20 METHOD
 TYPE III 24-HOUR
 RAINFALL= 4.70 IN
 SPAN= 10-20 HRS, dt=.1 HRS

Method	Comment	Tc (min)
TR-55 SHEET FLOW	Segment ID:	1.6
Smooth surfaces n=.011 L=205'	P2=5.5 in s=.022 '/'	
CIRCULAR CHANNEL	Segment ID:	.3
12" Diameter a=.79 sq-ft Pw=3.1' r=.25'		
s=.0066 '/' n=.011 V=4.36 fps L=85' Capacity=3.4 cfs		
Total Length= 290 ft		Total Tc= 1.9

Data for HP HOOD COOLER EXPANSION POST-DEVELOPMENT

TYPE III 24-HOUR RAINFALL= 4.70 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

REACH 1

Qin = 9.58 CFS @ 11.99 HRS, VOLUME= .62 AF
Qout= 9.49 CFS @ 11.99 HRS, VOLUME= .62 AF, ATTEN= 1%, LAG= 0.0 MIN

DEPTH (FT)	END AREA (SQ-FT)	DISCH (CFS)	18" PIPE	STOR-IND+TRANS METHOD
0.00	0.00	0.00		PEAK DEPTH= .98 FT
.15	.09	.26	n= .011	PEAK VELOCITY= 7.8 FPS
.30	.25	1.09	LENGTH= 55 FT	TRAVEL TIME = .1 MIN
.45	.45	2.43	SLOPE= .01 FT/FT	SPAN= 10-20 HRS, dt=.1 HRS
1.05	1.32	10.39		2 x FINER ROUTING
1.20	1.52	12.13		
1.35	1.68	13.23		
1.41	1.72	13.35		
1.46	1.75	13.23		
1.50	1.77	12.41		

Data for HP HOOD COOLER EXPANSION

TYPE III 24-HOUR RAINFALL= 5.50 IN

Prepared by DUFRESNE-HENRY, INC.

9 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

SUBCATCHMENT 1

DRAINAGE AREA TO CATCH BASIN (RIM-11.43')

PEAK= 11.23 CFS @ 11.99 HRS, VOLUME= .73 AF

ACRES	CN
2.07	98

IMPERVIOUS

SCS TR-20 METHOD
TYPE III 24-HOUR
RAINFALL= 5.50 IN
SPAN= 10-20 HRS, dt=.1 HRS

Method	Comment	Tc (min)
TR-55 SHEET FLOW	Segment ID:	1.6
Smooth surfaces n=.011 L=205'	P2=5.5 in s=.022 '/'	
CIRCULAR CHANNEL	Segment ID:	.3
12" Diameter a=.79 sq-ft Pw=3.1' r=.25'		
s=.0066 '/' n=.011 V=4.36 fps L=85' Capacity=3.4 cfs		
	Total Length= 290 ft	Total Tc= 1.9

Data for HP HOOD COOLER EXPANSION

TYPE III 24-HOUR RAINFALL= 5.50 IN

Prepared by DUFRESNE-HENRY, INC.

9 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

REACH 1

Qin = 11.23 CFS @ 11.99 HRS, VOLUME= .73 AF

Qout= 11.12 CFS @ 11.99 HRS, VOLUME= .72 AF, ATTEN= 1%, LAG= 0.0 MIN

DEPTH (FT)	END AREA (SQ-FT)	DISCH (CFS)	18" PIPE	STOR-IND+TRANS METHOD
0.00	0.00	0.00		PEAK DEPTH= 1.12 FT
.15	.09	.26	n= .011	PEAK VELOCITY= 7.9 FPS
.30	.25	1.09	LENGTH= 55 FT	TRAVEL TIME = .1 MIN
.45	.45	2.43	SLOPE= .01 FT/FT	SPAN= 10-20 HRS, dt=.1 HRS
1.05	1.32	10.39		2 x FINER ROUTING
1.20	1.52	12.13		
1.35	1.68	13.23		
1.41	1.72	13.35		
1.46	1.75	13.23		
1.50	1.77	12.41		

Data for HP HOOD COOLER EXPANSION POST-DEVELOPMENT

TYPE III 24-HOUR RAINFALL= 5.50 IN

Prepared by DUFRESNE-HENRY, INC.

9 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

SUBCATCHMENT 1

DRAINAGE AREA TO CATCH BASIN (RIM-11.43')

PEAK= 11.23 CFS @ 11.99 HRS, VOLUME= .73 AF

ACRES	CN	
2.07	98	IMPERVIOUS

SCS TR-20 METHOD
 TYPE III 24-HOUR
 RAINFALL= 5.50 IN
 SPAN= 10-20 HRS, dt=.1 HRS

Method	Comment	Tc (min)
TR-55 SHEET FLOW	Segment ID:	1.6
Smooth surfaces n=.011 L=205'	P2=5.5 in s=.022 '/'	
CIRCULAR CHANNEL	Segment ID:	.3
12" Diameter a=.79 sq-ft Pw=3.1' r=.25'		
s=.0066 '/' n=.011 V=4.36 fps L=85' Capacity=3.4 cfs		
Total Length= 290 ft		Total Tc= 1.9

Data for HP HOOD COOLER EXPANSION POST-DEVELOPMENT

TYPE III 24-HOUR RAINFALL= 5.50 IN

Prepared by DUFRESNE-HENRY, INC.

9 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

REACH 1

Qin = 11.23 CFS @ 11.99 HRS, VOLUME= .73 AF
Qout= 11.12 CFS @ 11.99 HRS, VOLUME= .72 AF, ATTEN= 1%, LAG= 0.0 MIN

DEPTH (FT)	END AREA (SQ-FT)	DISCH (CFS)	18" PIPE	STOR-IND+TRANS METHOD
0.00	0.00	0.00		PEAK DEPTH= 1.12 FT
.15	.09	.26	n= .011	PEAK VELOCITY= 7.9 FPS
.30	.25	1.09	LENGTH= 55 FT	TRAVEL TIME = .1 MIN
.45	.45	2.43	SLOPE= .01 FT/FT	SPAN= 10-20 HRS, dt=.1 HRS
1.05	1.32	10.39		2 x FINER ROUTING
1.20	1.52	12.13		
1.35	1.68	13.23		
1.41	1.72	13.35		
1.46	1.75	13.23		
1.50	1.77	12.41		

**CITY OF PORTLAND, MAINE
DEVELOPMENT REVIEW APPLICATION
PLANNING DEPARTMENT PROCESSING FORM**

20000027

I. D. Number

H.P. Hood Inc.

Applicant

349 Park Ave, Portland, ME 04101

Applicant's Mailing Address

Phillip Dooughy Associates

Consultant/Agent

781-5346 781-2908

Applicant or Agent Daytime Telephone, Fax

3/8/00

Application Date

High Bay Cooler Expansion

Project Name/Description

349 Park Ave, Portland, Maine 04101

Address of Proposed Site

006-D-001

Assessor's Reference: Chart-Block-Lot

Proposed Development (check all that apply): New Building Building Addition Change Of Use Residential
 Office Retail Manufacturing Warehouse/Distribution Parking Lot Other (specify)

7,110 sf 1.7393

Proposed Building square Feet or # of Units

Acreage of Site

Zoning

Check Review Required:

- Site Plan (major/minor)
- Subdivision # of lots
- PAD Review
- 14-403 Streets Review
- Flood Hazard
- Shoreland
- Historic Preservation
- DEP Local Certification
- Zoning Conditional Use (ZBA/PB)
- Zoning Variance
- Other

Fees Paid: Site Plan \$400.00 Subdivision _____ Engineer Review _____ Date: 3/8/00

DRC Approval Status:

Approved Approved w/Conditions see attache Denied

Approval Date 5/3/00 Approval Expiration 5/3/01 Extension to _____

Condition Compliance sarah signature 5/4/00 date Additional Sheets Attached

Performance Guarantee

Required* Not Required

* No building permit may be issued until a performance guarantee has been submitted as indicated below

<input type="checkbox"/> Performance Guarantee Accepted	_____	_____	_____
	date	amount	expiration date
<input checked="" type="checkbox"/> Inspection Fee Paid	_____	\$300.00	
	date	amount	
<input type="checkbox"/> Building Permit	_____		
	date		
<input type="checkbox"/> Performance Guarantee Reduced	_____	_____	_____
	date	remaining balance	signature
<input type="checkbox"/> Temporary Certificate Of Occupancy	_____	<input type="checkbox"/> Conditions (See Attached)	
	date		
<input type="checkbox"/> Final Inspection	_____	_____	
	date	signature	
<input type="checkbox"/> Certificate Of Occupancy	_____	_____	
	date	signature	
<input type="checkbox"/> Performance Guarantee Released	_____	_____	
	date	signature	
<input type="checkbox"/> Defect Guarantee Submitted	_____	_____	
	submitted date	amount	expiration date
<input type="checkbox"/> Defect Guarantee Released	_____	_____	
	date	signature	

RENTAL AGREEMENT

TELAHC PROPERTIES, L.P. with a principal place of business at Chalet Drive, Wilton, NH 03086 (hereinafter referred to as TELAHC) agrees to rent to H. P. HOOD, INC. certain parking spaces on TELAHC's property located at 340 Park Avenue, Portland, Maine, known as the Susse Chalet.

Similarly, H. P. HOOD, INC. with a principal place of business at 349 Park Avenue, Portland, ME 04102 (hereinafter referred to as HOOD) agrees to rent such parking spaces from TELAHC.

TERMS:


1. HOOD agrees that it will:
 - (a) Pay TWENTY DOLLARS (\$20.00) per space per month for thirty (30) parking spaces or SIX HUNDRED DOLLARS (\$600.00) per month. Rental payments for SIX HUNDRED DOLLARS (\$600.00) per month are to be made in advance by the 1st day of each month and without regard as to number of spaces used, commencing on the 1st day of July, 1999 and running for a period of two (2) years ending June 30, 2001, and to be re-negotiated at that time.
 - (b) Parking spaces will only be used between the hours of 7:30 a.m. and 5:00 p.m. HOOD will hold TELAHC harmless for any damage done to cars parked on the property.

2. TELAHC agrees that it will:
 - (a) Properly stripe and identify the appropriate parking spaces.
 - (b) Clear the parking lot of snow and ice.
 - (c) Make available such parking spaces between the hours of 7:30 a.m. and 5:00 p.m.

Each party recognizes that this Rental Agreement may be terminated with a ninety (90) days written notice of either party due to business reasons or other changes.

Each party also recognizes that this Rental Agreement shall terminate due to any change of ordinances or requirements of the City of Portland.

Dated: 10/26/99
TELAHC PROPERTIES, L.P.
By: 
Title: Alan G. Retter, VP of CSI, Property Mgr.
Duly Authorized

Dated: _____
H. P. HOOD, INC.
By: 
Title: Scott Blake, Operations Manager
Duly Authorized



April 3, 2000

Via Facsimile (207) 773-2913

HP Hood, Inc.
Northern Region
Attention: Janet Dow

Dear Ms Dow:

Please be advised that Paramount Management Associates, LLC is presently managing agent for Oly Realty One, LLC and Paramount Hotel Group, LLC, joint owners of the Portland/Intown property.

We have assumed the existing contract between your organization and Telahc Properties, L.P. All correspondence and rental payments should be forwarded to my attention at the following address:

Paramount Management Associates, LLC
710 Route 46 East, Suite 102
Fairfield, New Jersey 07004
Attention: Peter Marino

This letter shall also confirm that HP Hood's rental payment is \$600.00. Should you have any questions, please do not hesitate to contact me.

Sincerely,

A handwritten signature in black ink, appearing to read "Peter Marino", written over a horizontal line.

Peter Marino
Senior Vice President/Operations

PM:mm

PDA Phillip Doughty Associates — Architects

364 U.S. Route One, Falmouth, ME 04105
Telephone: 207-781-5346

e-mail: pjd1108@aol.com
Fax: 207-781-2908

ADDENDUM #1

PROJECT: H.P. Hood High Bay Cooler Expansion and Renovation
PDA #990-028
DATE: April 12, 2000

The following represents a compilation of data resulting from drawing/specification changes or clarifications, calls from bidders, and issues generated by the owner. These issues are in writing or in the form of drawings, and comprise this Addendum #1. This addendum is a part of the contract bid documents and shall be referenced on the proposal form.

Please acknowledge receipt of this addendum by faxing a copy (stamped "Received" and dated) to our office at 207-781-2908. Thank you.

1. Prebid meeting minutes attached.
2. Bid documents state that full sets of documents (plans and specs) will be available for subcontractors at \$75.00 per full set. Make checks payable to Phillip Doughty Associates — Architects.
 - a. Partial sets are available from Am-At-Uer at the risk of each sub. Subs are responsible for reviewing a complete set of plans and specifications prior to requesting separate sheets of plans or specifications.
3. Architectural Specifications:
 - a. Section 08410.1.02.B.4 Aluminum Entrances & Storefronts: Change Kawneer 1600 Series 2½" x 6" Section profiles to Kawneer Encore Series 1¾" x 6" aluminum frame profiles.
 - b. Section 08710.4.04.B Finish Hardware: Add Door #108A.
4. Site Drawings:
 - a. Dwg. C-2: Site Plan – The rim elevation for catch basin CB-3 is 12.8 rather than 13.1 shown.
 - b. Site miscellaneous: Foundation drain notes have been deleted from Structural Dwg. S-1, #8. We are awaiting the results on further borings, which will be taken on April 14th. If results are not available prior to the bid date and time, delete all reference to foundation drains.
5. Architectural Drawing:
 - a. Dwg. A-12: Added Reflected Ceiling Plans, Stair Section Scale & Ref. Tags
6. Structural Drawings:
 - a. Dwg. S-1: **Foundation Note #8** – Delete.
 - b. Dwg. S-10: Stair Tower foundation and framing plans (added sheet).
 - c. Dwg. S-11: Entrance Sections and Details (added sheet).
7. Electrical Drawings:
 - a. Dwg. E-2: Revise site lighting. Add notes 14, 15, 16. Add power for docks, hooks, and seal fans.
 - b. Dwg. E-3: Remove overhead drops shown on bid drawings.
 - c. Dwg. E-4: Service entrance re-design per CMP. Stair tower lighting re-design.
 - d. Dwg. E-5: Revise power distribution block diagram and feeder. Add LP-3-11.
 - e. Dwg. E-6: Revise panel LP1-A-2 and 4. Material schedule O, P, and Q.

Attachments:

1. Prebid Meeting Minutes
2. Architectural Drawings A-12
3. Structural Drawings S-1, S-10, S-11
4. Electrical Drawings E-2, E-3, E-4, E-5, E-6

End of Addendum

ADDENDUM 1— 1
Project #990-028

PDA Phillip Doughty Associates — Architects

364 U.S. Route One, Falmouth, ME 04105
Telephone: 207-781-5346

e-mail: pjd1108@aol.com
Fax: 207-781-2908

MEETING MINUTES

PROJECT: H.P. Hood High Bay Cooler Expansion and Renovation
PDA #990-028
DATE: April 7, 2000
PRESENT: Chris Gill AAA Energy Service
George Liming Allied/Cook
Tom Anuszewski Brown Construction
Jim Ellsworth Langford & Low
John Walker H.P. Hood
Joe Romano H.P. Hood
Scott Sawyer H.P. Hood
Dane Ramsay H.P. Hood
Bob Bryant H.P. Hood
Scott Blake H.P. Hood
Brian B. H.P. Hood
Phil Doughty Phillip Doughty Associates
CC: File

-
1. Sign-in Attendance List passed around the group.
 2. Division 1 and Site Issues discussion:
 - a. Site is extremely tight. Most trailers, though, which are seen on this day around the north and east sides of the yard, will not be on site during construction.
 - b. H.P. Hood will provide two locations for trailer boxes in the northwest corner of the yard. These will be for use by mechanical and electrical contractors.
 - c. General contractor's office space will be provided in the adjacent Carvel building. This will include bathroom facilities power and heat. Telephone will be the responsibility of the general contractor. Disregard Section 01500, 1.02.C.1 & .2; D.1, .2, .3, and further subsequent written requirements regarding these specific issues in that section.
 - d. H.P. Hood will designate five people to facilitate and coordinate H.P. Hood's and the general contractor's use of the site.
 - e. Parking for the general contractor's employees will be curbside along St. James street.
 - f. Yard activity: the site will be the least busy between 6:30 and 7:00 a.m. Wednesday is the day of least activity over the course of a day.
 - g. The City of Portland has required that the area catch basins, existing and new, be kept clear of all sediment and debris during the construction time period. A final cleaning is required at project closeout.
 - h. The existing concrete hard stands at grade will need to be broken up and removed from the site in the area north of the existing structure.
 - i. H.P. Hood is requiring the general contractor to comply fully with OSHA regulations as they relate to all construction on the site.
 - j. Lay down area: once the site is excavated along the new westerly cooler and foundations are in, lay down will be along this wall. There will also be space along the rear property line.
 3. **Drawing PH-I - Phasing High bay cooler area:**
 - a. Phase One is to be constructed first. The area of low roof represented on this drawing as Phase 3, currently a loading dock area, must remain in operation until the westerly loading bays shown in the high bay area are operational and refrigerated. The Phase One Penthouse cannot be closed in until all refrigeration equipment is in place.

PDA Phillip Doughty Associates — Architects

364 U.S. Route One, Falmouth, ME 04105
Telephone: 207-781-5346

e-mail: pjd1108@aol.com
Fax: 207-781-2908

ADDENDUM #1

PROJECT: H.P. Hood High Bay Cooler Expansion and Renovation
PDA #990-028
DATE: April 12, 2000

The following represents a compilation of data resulting from drawing/specification changes or clarifications, calls from bidders, and issues generated by the owner. These issues are in writing or in the form of drawings, and comprise this Addendum #1. This addendum is a part of the contract bid documents and shall be referenced on the proposal form.

Please acknowledge receipt of this addendum by faxing a copy (stamped "Received" and dated) to our office at 207-781-2908. Thank you.

1. Prebid meeting minutes attached.
2. Bid documents state that full sets of documents (plans and specs) will be available for subcontractors at \$75.00 per full set. Make checks payable to Phillip Doughty Associates — Architects.
 - a. Partial sets are available from Am-At-Uer at the risk of each sub. Subs are responsible for reviewing a complete set of plans and specifications prior to requesting separate sheets of plans or specifications.
3. Architectural Specifications:
 - a. Section 08410.1.02.B.4 Aluminum Entrances & Storefronts: Change Kawneer 1600 Series 2½" x 6" Section profiles to Kawneer Encore Series 1¾" x 6" aluminum frame profiles.
 - b. Section 08710.4.04.B Finish Hardware: Add Door #108A.
4. Site Drawings:
 - a. Dwg. C-2: Site Plan – The rim elevation for catch basin CB-3 is 12.8 rather than 13.1 shown.
 - b. Site miscellaneous: Foundation drain notes have been deleted from Structural Dwg. S-1, #8. We are awaiting the results on further borings, which will be taken on April 14th. If results are not available prior to the bid date and time, delete all reference to foundation drains.
5. Architectural Drawing:
 - a. Dwg. A-12: Added Reflected Ceiling Plans, Stair Section Scale & Ref. Tags
6. Structural Drawings:
 - a. Dwg. S-1: **Foundation Note #8** – Delete.
 - b. Dwg. S-10: Stair Tower foundation and framing plans (added sheet).
 - c. Dwg. S-11: Entrance Sections and Details (added sheet).
7. Electrical Drawings:
 - a. Dwg. E-2: Revise site lighting. Add notes 14, 15, 16. Add power for docks, hooks, and seal fans.
 - b. Dwg. E-3: Remove overhead drops shown on bid drawings.
 - c. Dwg. E-4: Service entrance re-design per CMP. Stair tower lighting re-design.
 - d. Dwg. E-5: Revise power distribution block diagram and feeder. Add LP-3-11.
 - e. Dwg. E-6: Revise panel LP1-A-2 and 4. Material schedule O, P, and Q.

Attachments:

1. Prebid Meeting Minutes
2. Architectural Drawings A-12
3. Structural Drawings S-1, S-10, S-11
4. Electrical Drawings E-2, E-3, E-4, E-5, E-6

End of Addendum

ADDENDUM 1— 1
Project #990-028

PDA Phillip Doughty Associates — Architects

364 U.S. Route One, Falmouth, ME 04105
Telephone: 207.781.5346

e-mail: pjd1108@aol.com
Fax: 207.781.2908

MEETING MINUTES

PROJECT: H.P. Hood High Bay Cooler Expansion and Renovation
PDA #990-028
DATE: April 7, 2000
PRESENT: Chris Gill AAA Energy Service
George Liming Allied/Cook
Tom Anuszewski Brown Construction
Jim Ellsworth Langford & Low
John Walker H.P. Hood
Joe Romano H.P. Hood
Scott Sawyer H.P. Hood
Dane Ramsay H.P. Hood
Bob Bryant H.P. Hood
Scott Blake H.P. Hood
Brian B. H.P. Hood
Phil Doughty Phillip Doughty Associates
CC: File

1. Sign-in Attendance List passed around the group.
2. Division 1 and Site Issues discussion:
 - a. Site is extremely tight. Most trailers, though, which are seen on this day around the north and east sides of the yard, will not be on site during construction.
 - b. H.P. Hood will provide two locations for trailer boxes in the northwest corner of the yard. These will be for use by mechanical and electrical contractors.
 - c. General contractor's office space will be provided in the adjacent Carvel building. This will include bathroom facilities power and heat. Telephone will be the responsibility of the general contractor. Disregard Section 01500, 1.02.C.1 & .2; D.1, .2, .3, and further subsequent written requirements regarding these specific issues in that section.
 - d. H.P. Hood will designate five people to facilitate and coordinate H.P. Hood's and the general contractor's use of the site.
 - e. Parking for the general contractor's employees will be curbside along St. James street.
 - f. Yard activity: the site will be the least busy between 6:30 and 7:00 a.m. Wednesday is the day of least activity over the course of a day.
 - g. The City of Portland has required that the area catch basins, existing and new, be kept clear of all sediment and debris during the construction time period. A final cleaning is required at project closeout.
 - h. The existing concrete hard stands at grade will need to be broken up and removed from the site in the area north of the existing structure.
 - i. H.P. Hood is requiring the general contractor to comply fully with OSHA regulations as they relate to all construction on the site.
 - j. Lay down area: once the site is excavated along the new westerly cooler and foundations are in, lay down will be along this wall. There will also be space along the rear property line.
3. **Drawing PH-I - Phasing High bay cooler area:**
 - a. Phase One is to be constructed first. The area of low roof represented on this drawing as Phase 3, currently a loading dock area, must remain in operation until the westerly loading bays shown in the high bay area are operational and refrigerated. The Phase One Penthouse cannot be closed in until all refrigeration equipment is in place.

PDA Phillip Doughty Associates — Architects

364 U.S. Route One, Falmouth, ME 04105
Telephone: 207-781-5346

e-mail: pjd1108@aol.com
Fax: 207-781-2908

ADDENDUM #1

PROJECT: H.P. Hood High Bay Cooler Expansion and Renovation
PDA #990-028
DATE: April 12, 2000

The following represents a compilation of data resulting from drawing/specification changes or clarifications, calls from bidders, and issues generated by the owner. These issues are in writing or in the form of drawings, and comprise this Addendum #1. This addendum is a part of the contract bid documents and shall be referenced on the proposal form.

Please acknowledge receipt of this addendum by faxing a copy (stamped "Received" and dated) to our office at 207-781-2908. Thank you.

1. Prebid meeting minutes attached.
2. Bid documents state that full sets of documents (plans and specs) will be available for subcontractors at \$75.00 per full set. Make checks payable to Phillip Doughty Associates — Architects.
 - a. Partial sets are available from Am-At-Uer at the risk of each sub. Subs are responsible for reviewing a complete set of plans and specifications prior to requesting separate sheets of plans or specifications.
3. Architectural Specifications:
 - a. Section 08410.1.02.B.4 Aluminum Entrances & Storefronts: Change Kawneer 1600 Series 2½" x 6" Section profiles to Kawneer Encore Series 1¾" x 6" aluminum frame profiles.
 - b. Section 08710.4.04.B Finish Hardware: Add Door #108A.
4. Site Drawings:
 - a. Dwg. C-2: Site Plan – The rim elevation for catch basin CB-3 is 12.8 rather than 13.1 shown.
 - b. Site miscellaneous: Foundation drain notes have been deleted from Structural Dwg. S-1, #8. We are awaiting the results on further borings, which will be taken on April 14th. If results are not available prior to the bid date and time, delete all reference to foundation drains.
5. Architectural Drawing:
 - a. Dwg. A-12: Added Reflected Ceiling Plans, Stair Section Scale & Ref. Tags
6. Structural Drawings:
 - a. Dwg. S-1: **Foundation Note #8** – Delete.
 - b. Dwg. S-10: Stair Tower foundation and framing plans (added sheet).
 - c. Dwg. S-11: Entrance Sections and Details (added sheet).
7. Electrical Drawings:
 - a. Dwg. E-2: Revise site lighting. Add notes 14, 15, 16. Add power for docks, hooks, and seal fans.
 - b. Dwg. E-3: Remove overhead drops shown on bid drawings.
 - c. Dwg. E-4: Service entrance re-design per CMP. Stair tower lighting re-design.
 - d. Dwg. E-5: Revise power distribution block diagram and feeder. Add LP-3-11.
 - e. Dwg. E-6: Revise panel LP1-A-2 and 4. Material schedule O, P, and Q.

Attachments:

1. Prebid Meeting Minutes
2. Architectural Drawings A-12
3. Structural Drawings S-1, S-10, S-11
4. Electrical Drawings E-2, E-3, E-4, E-5, E-6

End of Addendum

ADDENDUM 1— 1
Project #990-028

PDA Phillip Doughty Associates — Architects

364 U.S. Route One, Falmouth, ME 04105
Telephone: 207-781-5346

e-mail: pjd1108@aol.com
Fax: 207-781-2908

MEETING MINUTES

PROJECT: H.P. Hood High Bay Cooler Expansion and Renovation
PDA #990-028
DATE: April 7, 2000
PRESENT: Chris Gill AAA Energy Service
George Liming Allied/Cook
Tom Anuszewski Brown Construction
Jim Ellsworth Langford & Low
John Walker H.P. Hood
Joe Romano H.P. Hood
Scott Sawyer H.P. Hood
Dane Ramsay H.P. Hood
Bob Bryant H.P. Hood
Scott Blake H.P. Hood
Brian B. H.P. Hood
Phil Doughty Phillip Doughty Associates
CC: File

1. Sign-in Attendance List passed around the group.
2. Division 1 and Site Issues discussion:
 - a. Site is extremely tight. Most trailers, though, which are seen on this day around the north and east sides of the yard, will not be on site during construction.
 - b. H.P. Hood will provide two locations for trailer boxes in the northwest corner of the yard. These will be for use by mechanical and electrical contractors.
 - c. General contractor's office space will be provided in the adjacent Carvel building. This will include bathroom facilities power and heat. Telephone will be the responsibility of the general contractor. Disregard Section 01500, 1.02.C.1 & .2; D.1, .2, .3, and further subsequent written requirements regarding these specific issues in that section.
 - d. H.P. Hood will designate five people to facilitate and coordinate H.P. Hood's and the general contractor's use of the site.
 - e. Parking for the general contractor's employees will be curbside along St. James street.
 - f. Yard activity: the site will be the least busy between 6:30 and 7:00 a.m. Wednesday is the day of least activity over the course of a day.
 - g. The City of Portland has required that the area catch basins, existing and new, be kept clear of all sediment and debris during the construction time period. A final cleaning is required at project closeout.
 - h. The existing concrete hard stands at grade will need to be broken up and removed from the site in the area north of the existing structure.
 - i. H.P. Hood is requiring the general contractor to comply fully with OSHA regulations as they relate to all construction on the site.
 - j. Lay down area: once the site is excavated along the new westerly cooler and foundations are in, lay down will be along this wall. There will also be space along the rear property line.
3. **Drawing PH-I – Phasing High bay cooler area:**
 - a. Phase One is to be constructed first. The area of low roof represented on this drawing as Phase 3, currently a loading dock area, must remain in operation until the westerly loading bays shown in the high bay area are operational and refrigerated. The Phase One Penthouse cannot be closed in until all refrigeration equipment is in place.

PDA *Phillip Doughty Associates — Architects*

364 U.S. Route One, Falmouth, ME 04105
Telephone: 207-781-5346

e-mail: pjd1108@aol.com
Fax: 207-781-2908

ADDENDUM #1

PROJECT: H.P. Hood High Bay Cooler Expansion and Renovation
PDA #990-028
DATE: April 12, 2000

The following represents a compilation of data resulting from drawing/specification changes or clarifications, calls from bidders, and issues generated by the owner. These issues are in writing or in the form of drawings, and comprise this Addendum #1. This addendum is a part of the contract bid documents and shall be referenced on the proposal form.

Please acknowledge receipt of this addendum by faxing a copy (stamped "Received" and dated) to our office at 207-781-2908. Thank you.

1. Prebid meeting minutes attached.
2. Bid documents state that full sets of documents (plans and specs) will be available for subcontractors at \$75.00 per full set. Make checks payable to Phillip Doughty Associates — Architects.
 - a. Partial sets are available from Am-At-Uer at the risk of each sub. Subs are responsible for reviewing a complete set of plans and specifications prior to requesting separate sheets of plans or specifications.
3. Architectural Specifications:
 - a. Section 08410.1.02.B.4 Aluminum Entrances & Storefronts: Change Kawneer 1600 Series 2½" x 6" Section profiles to Kawneer Encore Series 1¾" x 6" aluminum frame profiles.
 - b. Section 08710.4.04.B Finish Hardware: Add Door #108A.
4. Site Drawings:
 - a. Dwg. C-2: Site Plan – The rim elevation for catch basin CB-3 is 12.8 rather than 13.1 shown.
 - b. Site miscellaneous: Foundation drain notes have been deleted from Structural Dwg. S-1, #8. We are awaiting the results on further borings, which will be taken on April 14th. If results are not available prior to the bid date and time, delete all reference to foundation drains.
5. Architectural Drawing:
 - a. Dwg. A-12: Added Reflected Ceiling Plans, Stair Section Scale & Ref. Tags
6. Structural Drawings:
 - a. Dwg. S-1: **Foundation Note #8** - Delete.
 - b. Dwg. S-10: Stair Tower foundation and framing plans (added sheet).
 - c. Dwg. S-11: Entrance Sections and Details (added sheet).
7. Electrical Drawings:
 - a. Dwg. E-2: Revise site lighting. Add notes 14, 15, 16. Add power for docks, hooks, and seal fans.
 - b. Dwg. E-3: Remove overhead drops shown on bid drawings.
 - c. Dwg. E-4: Service entrance re-design per CMP. Stair tower lighting re-design.
 - d. Dwg. E-5: Revise power distribution block diagram and feeder. Add LP-3-11.
 - e. Dwg. E-6: Revise panel LP1-A-2 and 4. Material schedule O, P, and Q.

Attachments:

1. Prebid Meeting Minutes
2. Architectural Drawings A-12
3. Structural Drawings S-1, S-10, S-11
4. Electrical Drawings E-2, E-3, E-4, E-5, E-6

End of Addendum

ADDENDUM 1— 1
Project #990-028

PDA Phillip Doughty Associates — Architects

364 U.S. Route One, Falmouth, ME 04105
Telephone: 207.781.5346

e-mail: pjd1108@aol.com
Fax: 207.781.2908

MEETING MINUTES

PROJECT: H.P. Hood High Bay Cooler Expansion and Renovation
PDA #990-028
DATE: April 7, 2000
PRESENT: Chris Gill AAA Energy Service
George Liming Allied/Cook
Tom Anuszewski Brown Construction
Jim Ellsworth Langford & Low
John Walker H.P. Hood
Joe Romano H.P. Hood
Scott Sawyer H.P. Hood
Dane Ramsay H.P. Hood
Bob Bryant H.P. Hood
Scott Blake H.P. Hood
Brian B. H.P. Hood
Phil Doughty Phillip Doughty Associates
CC: File

-
1. Sign-in Attendance List passed around the group.
 2. Division 1 and Site Issues discussion:
 - a. Site is extremely tight. Most trailers, though, which are seen on this day around the north and east sides of the yard, will not be on site during construction.
 - b. H.P. Hood will provide two locations for trailer boxes in the northwest corner of the yard. These will be for use by mechanical and electrical contractors.
 - c. General contractor's office space will be provided in the adjacent Carvel building. This will include bathroom facilities power and heat. Telephone will be the responsibility of the general contractor. Disregard Section 01500, 1.02.C.1 & .2; D.1, .2, .3, and further subsequent written requirements regarding these specific issues in that section.
 - d. H.P. Hood will designate five people to facilitate and coordinate H.P. Hood's and the general contractor's use of the site.
 - e. Parking for the general contractor's employees will be curbside along St. James street.
 - f. Yard activity: the site will be the least busy between 6:30 and 7:00 a.m. Wednesday is the day of least activity over the course of a day.
 - g. The City of Portland has required that the area catch basins, existing and new, be kept clear of all sediment and debris during the construction time period. A final cleaning is required at project closeout.
 - h. The existing concrete hard stands at grade will need to be broken up and removed from the site in the area north of the existing structure.
 - i. H.P. Hood is requiring the general contractor to comply fully with OSHA regulations as they relate to all construction on the site.
 - j. Lay down area: once the site is excavated along the new westerly cooler and foundations are in, lay down will be along this wall. There will also be space along the rear property line.
 3. **Drawing PH-I – Phasing High bay cooler area:**
 - a. Phase One is to be constructed first. The area of low roof represented on this drawing as Phase 3, currently a loading dock area, must remain in operation until the westerly loading bays shown in the high bay area are operational and refrigerated. The Phase One Penthouse cannot be closed in until all refrigeration equipment is in place.

PDA Phillip Doughty Associates — Architects

364 U.S. Route One, Falmouth, ME 04105
Telephone: 207-781-5346

e-mail: pjd1108@aol.com
Fax: 207-781-2908

ADDENDUM #1

PROJECT: H.P. Hood High Bay Cooler Expansion and Renovation
PDA #990-028
DATE: April 12, 2000

The following represents a compilation of data resulting from drawing/specification changes or clarifications, calls from bidders, and issues generated by the owner. These issues are in writing or in the form of drawings, and comprise this Addendum #1. This addendum is a part of the contract bid documents and shall be referenced on the proposal form.

Please acknowledge receipt of this addendum by faxing a copy (stamped "Received" and dated) to our office at 207-781-2908. Thank you.

1. Prebid meeting minutes attached.
2. Bid documents state that full sets of documents (plans and specs) will be available for subcontractors at \$75.00 per full set. Make checks payable to Phillip Doughty Associates — Architects.
 - a. Partial sets are available from Am-At-Uer at the risk of each sub. Subs are responsible for reviewing a complete set of plans and specifications prior to requesting separate sheets of plans or specifications.
3. Architectural Specifications:
 - a. Section 08410.1.02.B.4 Aluminum Entrances & Storefronts: Change Kawneer 1600 Series 2½" x 6" Section profiles to Kawneer Encore Series 1¾" x 6" aluminum frame profiles.
 - b. Section 08710.4.04.B Finish Hardware: Add Door #108A.
4. Site Drawings:
 - a. Dwg. C-2: Site Plan – The rim elevation for catch basin CB-3 is 12.8 rather than 13.1 shown.
 - b. Site miscellaneous: Foundation drain notes have been deleted from Structural Dwg. S-1, #8. We are awaiting the results on further borings, which will be taken on April 14th. If results are not available prior to the bid date and time, delete all reference to foundation drains.
5. Architectural Drawing:
 - a. Dwg. A-12: Added Reflected Ceiling Plans, Stair Section Scale & Ref. Tags
6. Structural Drawings:
 - a. Dwg. S-1: **Foundation Note #8** – Delete.
 - b. Dwg. S-10: Stair Tower foundation and framing plans (added sheet).
 - c. Dwg. S-11: Entrance Sections and Details (added sheet).
7. Electrical Drawings:
 - a. Dwg. E-2: Revise site lighting. Add notes 14, 15, 16. Add power for docks, hooks, and seal fans.
 - b. Dwg. E-3: Remove overhead drops shown on bid drawings.
 - c. Dwg. E-4: Service entrance re-design per CMP. Stair tower lighting re-design.
 - d. Dwg. E-5: Revise power distribution block diagram and feeder. Add LP-3-11.
 - e. Dwg. E-6: Revise panel LP1-A-2 and 4. Material schedule O, P, and Q.

Attachments:

1. Prebid Meeting Minutes
2. Architectural Drawings A-12
3. Structural Drawings S-1, S-10, S-11
4. Electrical Drawings E-2, E-3, E-4, E-5, E-6

End of Addendum

ADDENDUM 1— 1
Project #990-028

PDA Phillip Doughty Associates — Architects

364 U.S. Route One, Falmouth, ME 04105
Telephone: 207.781.5346

e-mail: pjd1108@aol.com
Fax: 207.781.2908

MEETING MINUTES

PROJECT: H.P. Hood High Bay Cooler Expansion and Renovation
PDA #990-028
DATE: April 7, 2000
PRESENT: Chris Gill AAA Energy Service
George Liming Allied/Cook
Tom Anuszewski Brown Construction
Jim Ellsworth Langford & Low
John Walker H.P. Hood
Joe Romano H.P. Hood
Scott Sawyer H.P. Hood
Dane Ramsay H.P. Hood
Bob Bryant H.P. Hood
Scott Blake H.P. Hood
Brian B. H.P. Hood
Phil Doughty Phillip Doughty Associates
CC: File

1. Sign-in Attendance List passed around the group.
2. Division 1 and Site Issues discussion:
 - a. Site is extremely tight. Most trailers, though, which are seen on this day around the north and east sides of the yard, will not be on site during construction.
 - b. H.P. Hood will provide two locations for trailer boxes in the northwest corner of the yard. These will be for use by mechanical and electrical contractors.
 - c. General contractor's office space will be provided in the adjacent Carvel building. This will include bathroom facilities power and heat. Telephone will be the responsibility of the general contractor. Disregard Section 01500, 1.02.C.1 & .2; D.1, .2, .3, and further subsequent written requirements regarding these specific issues in that section.
 - d. H.P. Hood will designate five people to facilitate and coordinate H.P. Hood's and the general contractor's use of the site.
 - e. Parking for the general contractor's employees will be curbside along St. James street.
 - f. Yard activity: the site will be the least busy between 6:30 and 7:00 a.m. Wednesday is the day of least activity over the course of a day.
 - g. The City of Portland has required that the area catch basins, existing and new, be kept clear of all sediment and debris during the construction time period. A final cleaning is required at project closeout.
 - h. The existing concrete hard stands at grade will need to be broken up and removed from the site in the area north of the existing structure.
 - i. H.P. Hood is requiring the general contractor to comply fully with OSHA regulations as they relate to all construction on the site.
 - j. Lay down area: once the site is excavated along the new westerly cooler and foundations are in, lay down will be along this wall. There will also be space along the rear property line.
3. **Drawing PH-I – Phasing High bay cooler area:**
 - a. Phase One is to be constructed first. The area of low roof represented on this drawing as Phase 3, currently a loading dock area, must remain in operation until the westerly loading bays shown in the high bay area are operational and refrigerated. The Phase One Penthouse cannot be closed in until all refrigeration equipment is in place.


STORMWATER MANAGEMENT REPORT

for the

**H.P. HOOD, INC.
BUILDING EXPANSION PROJECT**

**Completed By
Dufresne-Henry, Inc.**

**Completed For
Phillip J. Doughty Associates - Architects**



March 2000



BACKGROUND SUMMARY

PROJECT DESCRIPTION

H.P. Hood, Inc. is proposing an expansion to its principal facility located at 340⁹ Park Avenue in Portland, Maine. The expansion includes the construction of a high bay cooler building located adjacent to the existing main building and will encompass a total area of approximately 7,100 square feet.

The existing H.P. Hood, Inc. site is approximately 2 acres and contains the main building facility, loading docks, trailer storage area, and parking lot. The entire area is paved and includes an existing stormwater drainage system consisting of catchbasins that convey stormwater runoff to the City combined sewer system on Park Avenue.

This drainage analysis was prepared to determine the stormwater runoff effects of the H.P. Hood, Inc. expansion project. Drainage calculations for pre-development conditions and post-development conditions have been developed to determine the difference between existing drainage conditions and those resulting from the proposed building expansion.

DRAINAGE ANALYSIS SUMMARY

INTRODUCTION

There is one distinct drainage area at the project site in the pre and post-development conditions and includes the existing H.P. Hood, Inc. facility and bituminous pavement parking lot to the property boundary. Stormwater management on the site will not be significantly affected by the proposed expansion. Proposed regrading will include slight modifications to existing grades in the vicinity of the proposed building to promote drainage to existing and proposed catchbasins. The proposed project will be designed such that no negative impacts to adjacent properties, or the City sewer system are anticipated.

METHODOLOGY

In order to compare the stormwater characteristics of today with the future stormwater characteristics of the site, computer modeling using HydroCad software was employed which incorporates the methodology outlined in the U.S. Natural Resources Conservation Service's (NRCS) Technical Release Number 20 (TR-20). Runoff was calculated for the 2, 10 and 25-year, 24 hour storm events. The one day precipitation values for the Portland, ME and the project site are as follows:

2-Year, 24 Hour Precipitation - 3.0 inches
10-Year, 24 Hour Precipitation - 4.7 inches
25-Year, 24 Hour Precipitation - 5.5 inches

Since the H.P. Hood, Inc. facility is located in southeast Maine, a Type III distribution was utilized throughout this study. Also, the project site has been designated as impervious in the pre and post-development conditions for this study. All curve number and time of concentration calculations may be found along with computer generated documentation following this narrative.

STORMWATER RUNOFF ANALYSIS

Subcatchments 1, Pre-Development and Post-Development Conditions

The drainage area encompassing the expansion project to the H.P. Hood facility is approximately 2 acres. A majority of the stormwater runoff generated adjacent to the project site is conveyed to the City sewer system through drainage structures not considered in this report, and therefore was not included in the stormwater runoff calculations. This area has been analyzed as one subcatchment for the entire drainage area for the pre-development conditions and for the post-development conditions (See Dwg. A, Pre-Development Conditions and Dwg B, Post-Development Conditions). Subcatchment 1 represents the area which drains to DMH 1 prior to being discharged through a 20-inch vitrified clay pipe from the project site. Generally, stormwater runoff generated on the project site sheet flows in a southwesterly direction to an existing catchbasin that conveys the collected stormwater runoff to DMH 1 through an existing 12-inch RCP pipe.

In the post-development condition, Subcatchment 1 is essentially unchanged. The building expansion results in less bituminous pavement on the site but the amount of impervious area at the site is unchanged. Also, as part of the proposed expansion, stormwater runoff is conveyed through 12-inch RCP pipes around the proposed expansion due to existing CB 2 being removed and existing CB 1 being removed and replaced with a new catchbasin to the east of the new building. Relocated CB 1 will tie-into two proposed structures installed along the north side of the building (DMH-2 and CB-3). As in the pre-development condition, a majority of the stormwater runoff generated on the site is conveyed to DMH 1 prior to being discharged from the project site.

The estimated peak rates of runoff in cubic feet per second (CFS) in the pre-development and post-development conditions for Subcatchments 1, with the projected differences in parenthesis are as follows:

<u>Pre-Development, 2 year storm</u>		<u>Post-Development, 2 year storm</u>	
Subcatchment 1	6.07 CFS	Subcatchment 1	6.07 CFS (0 CFS)
<u>Pre-Development, 10 year storm</u>		<u>Post-Development, 10 year storm</u>	
Subcatchment 1	9.58 CFS	Subcatchment 1	9.58 CFS (0 CFS)
<u>Pre-Development, 25 year storm</u>		<u>Post-Development, 25 year storm</u>	
Subcatchment 1	11.23 CFS	Subcatchment 1	11.23 CFS (0 CFS)

CONCLUSIONS

The existing 12-inch RCP pipe conveying stormwater runoff to DMH 1 was analyzed in the post-development conditions using the Field's Hydraulic Calculator based on Manning's Equation. The results of this analysis demonstrated that sufficient capacity exists in the 12-inch RCP pipe to convey stormwater runoff for the 10-year storm event. During the 25-year storm event, the 12-inch RCP pipe is flowing at capacity producing 1.5 feet of headwater in the existing catchbasin. Lastly, the existing 18-inch RCP pipe draining DMH 1 has sufficient capacity to convey stormwater runoff for the 25-year storm event in the post-development conditions.

Therefore, the proposed development will have no adverse impact on Subcatchment 1. Projected post-development peak runoff quantities and the quality of stormwater runoff will not change from pre-development conditions.

Data for HP HOOD COOLER EXPANSION


TYPE III 24-HOUR RAINFALL= 3.00 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

WATERSHED ROUTING =====



SUBCATCHMENT 1 = DRAINAGE AREA TO CATCH BASIN (RIM-11.43') -> REACH 1

REACH 1 = ->

Data for HP HOOD COOLER EXPANSION

TYPE III 24-HOUR RAINFALL= 3.00 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

SUBCATCHMENT 1

DRAINAGE AREA TO CATCH BASIN (RIM-11.43')

PEAK= 6.07 CFS @ 11.99 HRS, VOLUME= .39 AF

ACRES	CN	
2.07	98	IMPERVIOUS

SCS TR-20 METHOD
 TYPE III 24-HOUR
 RAINFALL= 3.00 IN
 SPAN= 10-20 HRS, dt=.1 HRS

Method	Comment	Tc (min)
TR-55 SHEET FLOW	Segment ID:	1.6
Smooth surfaces n=.011 L=205'	P2=5.5 in s=.022 '/'	
CIRCULAR CHANNEL	Segment ID:	.3
12" Diameter a=.79 sq-ft Pw=3.1' r=.25'		
s=.0066 '/' n=.011 V=4.36 fps L=85' Capacity=3.4 cfs		
	Total Length= 290 ft	Total Tc= 1.9

Data for HP HOOD COOLER EXPANSION

TYPE III 24-HOUR RAINFALL= 3.00 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

REACH 1

Qin = 6.07 CFS @ 11.99 HRS, VOLUME= .39 AF
Qout= 6.00 CFS @ 11.99 HRS, VOLUME= .39 AF, ATTEN= 1%, LAG= 0.0 MIN

DEPTH (FT)	END AREA (SQ-FT)	DISCH (CFS)	18" PIPE	STOR-IND+TRANS METHOD
0.00	0.00	0.00		PEAK DEPTH= .72 FT
.15	.09	.26	n= .011	PEAK VELOCITY= 7.2 FPS
.30	.25	1.09	LENGTH= 55 FT	TRAVEL TIME = .1 MIN
.45	.45	2.43	SLOPE= .01 FT/FT	SPAN= 10-20 HRS, dt=.1 HRS
1.05	1.32	10.39		2 x FINER ROUTING
1.20	1.52	12.13		
1.35	1.68	13.23		
1.41	1.72	13.35		
1.46	1.75	13.23		
1.50	1.77	12.41		

Data for HP HOOD COOLER EXPANSION POST-DEVELOPMENT



TYPE III 24-HOUR RAINFALL= 3.00 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

WATERSHED ROUTING =====



SUBCATCHMENT 1 = DRAINAGE AREA TO CATCH BASIN (RIM-11.43') -> REACH 1

REACH 1 = ->

Data for HP HOOD COOLER EXPANSION POST-DEVELOPMENT

TYPE III 24-HOUR RAINFALL= 3.00 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

SUBCATCHMENT 1

DRAINAGE AREA TO CATCH BASIN (RIM-11.43')

PEAK= 6.07 CFS @ 11.99 HRS, VOLUME= .39 AF

ACRES	CN	
2.07	98	IMPERVIOUS

SCS TR-20 METHOD
 TYPE III 24-HOUR
 RAINFALL= 3.00 IN
 SPAN= 10-20 HRS, dt=.1 HRS

Method	Comment	Tc (min)
TR-55 SHEET FLOW	Segment ID:	1.6
Smooth surfaces n=.011 L=205'	P2=5.5 in s=.022 '/'	
CIRCULAR CHANNEL	Segment ID:	.3
12" Diameter a=.79 sq-ft Pw=3.1' r=.25'		
s=.0066 '/' n=.011 V=4.36 fps L=85' Capacity=3.4 cfs		
Total Length= 290 ft		Total Tc= 1.9

Data for HP HOOD COOLER EXPANSION POST-DEVELOPMENT

TYPE III 24-HOUR RAINFALL= 3.00 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

REACH 1

Qin = 6.07 CFS @ 11.99 HRS, VOLUME= .39 AF
 Qout= 6.00 CFS @ 11.99 HRS, VOLUME= .39 AF, ATTEN= 1%, LAG= 0.0 MIN

DEPTH (FT)	END AREA (SQ-FT)	DISCH (CFS)	18" PIPE	STOR-IND+TRANS METHOD
0.00	0.00	0.00		PEAK DEPTH= .72 FT
.15	.09	.26	n= .011	PEAK VELOCITY= 7.2 FPS
.30	.25	1.09	LENGTH= 55 FT	TRAVEL TIME = .1 MIN
.45	.45	2.43	SLOPE= .01 FT/FT	SPAN= 10-20 HRS, dt=.1 HRS
1.05	1.32	10.39		2 x FINER ROUTING
1.20	1.52	12.13		
1.35	1.68	13.23		
1.41	1.72	13.35		
1.46	1.75	13.23		
1.50	1.77	12.41		

Data for HP HOOD COOLER EXPANSION

TYPE III 24-HOUR RAINFALL= 4.70 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

SUBCATCHMENT 1

DRAINAGE AREA TO CATCH BASIN (RIM-11.43')

PEAK= 9.58 CFS @ 11.99 HRS, VOLUME= .62 AF

ACRES	CN	
2.07	98	IMPERVIOUS

SCS TR-20 METHOD
 TYPE III 24-HOUR
 RAINFALL= 4.70 IN
 SPAN= 10-20 HRS, dt=.1 HRS

Method	Comment	Tc (min)
TR-55 SHEET FLOW	Segment ID:	1.6
Smooth surfaces n=.011 L=205'	P2=5.5 in s=.022 '/'	
CIRCULAR CHANNEL	Segment ID:	.3
12" Diameter a=.79 sq-ft Pw=3.1' r=.25'		
s=.0066 '/' n=.011 V=4.36 fps L=85' Capacity=3.4 cfs		
Total Length= 290 ft		Total Tc= 1.9

Data for HP HOOD COOLER EXPANSION

TYPE III 24-HOUR RAINFALL= 4.70 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

REACH 1

Qin = 9.58 CFS @ 11.99 HRS, VOLUME= .62 AF
Qout= 9.49 CFS @ 11.99 HRS, VOLUME= .62 AF, ATTEN= 1%, LAG= 0.0 MIN

DEPTH (FT)	END AREA (SQ-FT)	DISCH (CFS)	18" PIPE	STOR-IND+TRANS METHOD
0.00	0.00	0.00		PEAK DEPTH= .98 FT
.15	.09	.26	n= .011	PEAK VELOCITY= 7.8 FPS
.30	.25	1.09	LENGTH= 55 FT	TRAVEL TIME = .1 MIN
.45	.45	2.43	SLOPE= .01 FT/FT	SPAN= 10-20 HRS, dt=.1 HRS
1.05	1.32	10.39		2 x FINER ROUTING
1.20	1.52	12.13		
1.35	1.68	13.23		
1.41	1.72	13.35		
1.46	1.75	13.23		
1.50	1.77	12.41		

Data for HP HOOD COOLER EXPANSION POST-DEVELOPMENT

TYPE III 24-HOUR RAINFALL= 4.70 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

SUBCATCHMENT 1

DRAINAGE AREA TO CATCH BASIN (RIM-11.43')

PEAK= 9.58 CFS @ 11.99 HRS, VOLUME= .62 AF

ACRES	CN	
2.07	98	IMPERVIOUS

SCS TR-20 METHOD
 TYPE III 24-HOUR
 RAINFALL= 4.70 IN
 SPAN= 10-20 HRS, dt=.1 HRS

Method	Comment	Tc (min)
TR-55 SHEET FLOW	Segment ID:	1.6
Smooth surfaces n=.011 L=205'	P2=5.5 in s=.022 '/'	
CIRCULAR CHANNEL	Segment ID:	.3
12" Diameter a=.79 sq-ft Pw=3.1' r=.25'		
s=.0066 '/' n=.011 V=4.36 fps L=85' Capacity=3.4 cfs		
Total Length= 290 ft		Total Tc= 1.9

Data for HP HOOD COOLER EXPANSION POST-DEVELOPMENT

TYPE III 24-HOUR RAINFALL= 4.70 IN

Prepared by DUFRESNE-HENRY, INC.

11 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

REACH 1

Qin = 9.58 CFS @ 11.99 HRS, VOLUME= .62 AF
Qout= 9.49 CFS @ 11.99 HRS, VOLUME= .62 AF, ATTEN= 1%, LAG= 0.0 MIN

DEPTH (FT)	END AREA (SQ-FT)	DISCH (CFS)	18" PIPE	STOR-IND+TRANS METHOD
0.00	0.00	0.00		PEAK DEPTH= .98 FT
.15	.09	.26	n= .011	PEAK VELOCITY= 7.8 FPS
.30	.25	1.09	LENGTH= 55 FT	TRAVEL TIME = .1 MIN
.45	.45	2.43	SLOPE= .01 FT/FT	SPAN= 10-20 HRS, dt=.1 HRS
1.05	1.32	10.39		2 x FINER ROUTING
1.20	1.52	12.13		
1.35	1.68	13.23		
1.41	1.72	13.35		
1.46	1.75	13.23		
1.50	1.77	12.41		

Data for HP HOOD COOLER EXPANSION

TYPE III 24-HOUR RAINFALL= 5.50 IN

Prepared by DUFRESNE-HENRY, INC.

9 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

SUBCATCHMENT 1

DRAINAGE AREA TO CATCH BASIN (RIM-11.43')

PEAK= 11.23 CFS @ 11.99 HRS, VOLUME= .73 AF

ACRES	CN	
2.07	98	IMPERVIOUS

SCS TR-20 METHOD
 TYPE III 24-HOUR
 RAINFALL= 5.50 IN
 SPAN= 10-20 HRS, dt=.1 HRS

Method	Comment	Tc (min)
TR-55 SHEET FLOW	Segment ID:	1.6
Smooth surfaces n=.011 L=205'	P2=5.5 in s=.022 '/'	
CIRCULAR CHANNEL	Segment ID:	.3
12" Diameter a=.79 sq-ft Pw=3.1' r=.25'		
s=.0066 '/' n=.011 V=4.36 fps L=85' Capacity=3.4 cfs		
Total Length= 290 ft		Total Tc= 1.9

Data for HP HOOD COOLER EXPANSION

TYPE III 24-HOUR RAINFALL= 5.50 IN

Prepared by DUFRESNE-HENRY, INC.

9 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

REACH 1

Qin = 11.23 CFS @ 11.99 HRS, VOLUME= .73 AF

Qout= 11.12 CFS @ 11.99 HRS, VOLUME= .72 AF, ATTEN= 1%, LAG= 0.0 MIN

DEPTH (FT)	END AREA (SQ-FT)	DISCH (CFS)	18" PIPE	STOR-IND+TRANS METHOD
0.00	0.00	0.00		PEAK DEPTH= 1.12 FT
.15	.09	.26	n= .011	PEAK VELOCITY= 7.9 FPS
.30	.25	1.09	LENGTH= 55 FT	TRAVEL TIME = .1 MIN
.45	.45	2.43	SLOPE= .01 FT/FT	SPAN= 10-20 HRS, dt=.1 HRS
1.05	1.32	10.39		2 x FINER ROUTING
1.20	1.52	12.13		
1.35	1.68	13.23		
1.41	1.72	13.35		
1.46	1.75	13.23		
1.50	1.77	12.41		

Data for HP HOOD COOLER EXPANSION POST-DEVELOPMENT

TYPE III 24-HOUR RAINFALL= 5.50 IN

Prepared by DUFRESNE-HENRY, INC.

9 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

SUBCATCHMENT 1

DRAINAGE AREA TO CATCH BASIN (RIM-11.43')

PEAK= 11.23 CFS @ 11.99 HRS, VOLUME= .73 AF

ACRES	CN	
2.07	98	IMPERVIOUS

SCS TR-20 METHOD
 TYPE III 24-HOUR
 RAINFALL= 5.50 IN
 SPAN= 10-20 HRS, dt=.1 HRS

Method	Comment	Tc (min)
TR-55 SHEET FLOW	Segment ID:	1.6
Smooth surfaces n=.011 L=205'	P2=5.5 in s=.022 '/'	
CIRCULAR CHANNEL	Segment ID:	.3
12" Diameter a=.79 sq-ft Pw=3.1' r=.25'		
s=.0066 '/' n=.011 V=4.36 fps L=85' Capacity=3.4 cfs		
Total Length= 290 ft		Total Tc= 1.9

Data for HP HOOD COOLER EXPANSION POST-DEVELOPMENT

TYPE III 24-HOUR RAINFALL= 5.50 IN

Prepared by DUFRESNE-HENRY, INC.

9 Feb 00

HydroCAD 5.11 001123 (c) 1986-1999 Applied Microcomputer Systems

REACH 1

Qin = 11.23 CFS @ 11.99 HRS, VOLUME= .73 AF
Qout= 11.12 CFS @ 11.99 HRS, VOLUME= .72 AF, ATTEN= 1%, LAG= 0.0 MIN

DEPTH (FT)	END AREA (SQ-FT)	DISCH (CFS)	18" PIPE	STOR-IND+TRANS METHOD
0.00	0.00	0.00		PEAK DEPTH= 1.12 FT
.15	.09	.26	n= .011	PEAK VELOCITY= 7.9 FPS
.30	.25	1.09	LENGTH= 55 FT	TRAVEL TIME = .1 MIN
.45	.45	2.43	SLOPE= .01 FT/FT	SPAN= 10-20 HRS, dt=.1 HRS
1.05	1.32	10.39		2 x FINER ROUTING
1.20	1.52	12.13		
1.35	1.68	13.23		
1.41	1.72	13.35		
1.46	1.75	13.23		
1.50	1.77	12.41		

**CITY OF PORTLAND, MAINE
DEVELOPMENT REVIEW APPLICATION
PLANNING DEPARTMENT PROCESSING FORM**

I. D. Number _____

H.P. Hood
Applicant
500 Rutherford Ave, Boston, MA 02129
Applicant's Mailing Address
Center Line Const/Dick Miller
Consultant/Agent
846-0042
Applicant or Agent Daytime Telephone, Fax

9/16/97
Application Date
Park Ave 349
Project Name/Description

349 Park Ave, Great Diamond Island
Address of Proposed Site
066-D-001
Assessor's Reference: Chart-Block-Lot

Proposed Development (check all that apply):
 New Building Building Addition Change Of Use Residential
 Office Retail Manufacturing Warehouse/Distribution Parking Lot Other (specify) **2 Milk Storage Tanks**

Proposed Building square Feet or # of Units: **66,890 Sq Ft** Acreage of Site _____ Zoning _____

Check Review Required:

Site Plan (major/minor) Subdivision # of lots _____ PAD Review 14-403 Streets Review
 Flood Hazard Shoreland Historic Preservation DEP Local Certification
 Zoning Conditional Use (ZBA/PB) Zoning Variance Other _____

Fees Paid: Site Plan **\$300.00** Subdivision _____ Engineer Review _____ Date: **9/16/97**

Planning Approval Status:

Approved Approved w/Conditions See Attached Denied

Reviewer *Sandra H.*

Approval Date **7/18/97** Approval Expiration *Salt* Extension to _____ Additional Sheets Attached
 OK to Issue Building Permit signature date

Performance Guarantee Required* Not Required

* No building permit may be issued until a performance guarantee has been submitted as indicated below

<input type="checkbox"/> Performance Guarantee Accepted	_____	_____	_____
	date	amount	expiration date
<input type="checkbox"/> Inspection Fee Paid	_____	_____	
	date	amount	
<input type="checkbox"/> Building Permit Issued	_____		
	date		
<input type="checkbox"/> Performance Guarantee Reduced	_____	_____	_____
	date	remaining balance	signature
<input type="checkbox"/> Temporary Certificate of Occupancy	_____	<input type="checkbox"/> Conditions (See Attached)	
	date		
<input type="checkbox"/> Final Inspection	_____	_____	
	date	signature	
<input type="checkbox"/> Certificate Of Occupancy	_____		
	date		
<input type="checkbox"/> Performance Guarantee Released	_____	_____	
	date	signature	
<input type="checkbox"/> Defect Guarantee Submitted	_____	_____	_____
	submitted date	amount	expiration date
<input type="checkbox"/> Defect Guarantee Released	_____	_____	
	date	signature	

**CITY OF PORTLAND, MAINE
DEVELOPMENT REVIEW APPLICATION
PLANNING DEPARTMENT PROCESSING FORM**

I. D. Number _____

H.P. Hood
Applicant
500 Rutherford Ave, Boston, MA 02129
Applicant's Mailing Address
Center Line Const/Dick Miller
Consultant/Agent
846-0042
Applicant or Agent Daytime Telephone, Fax

9/16/97
Application Date
Park Ave 349
Project Name/Description

349 Park Ave, Great Diamond Island
Address of Proposed Site
066-D-001
Assessor's Reference: Chart-Block-Lot

Proposed Development (check all that apply):
 Office Retail Manufacturing Warehouse/Distribution Parking Lot Other (specify) **2 Milk Storage Tanks**

Proposed Building square Feet or # of Units: **66,890 Sq Ft** Acreage of Site _____ Zoning _____

Check Review Required:

Site Plan (major/minor) Subdivision # of lots _____ PAD Review 14-403 Streets Review
 Flood Hazard Shoreland Historic Preservation DEP Local Certification
 Zoning Conditional Use (ZBA/PB) Zoning Variance Other _____

Fees Paid: Site Plan **\$300.00** Subdivision _____ Engineer Review _____ Date: **9/16/97**

DRC Approval Status:

Approved Approved w/Conditions see attached Denied
 Reviewer: *Sarah Hylle*
 Approval Date: *9/18/97* Approval Expiration _____ Extension to _____ Additional Sheets Attached
 Condition Compliance *Sarah Hylle* signature _____ date

Performance Guarantee Required* Not Required

* No building permit may be issued until a performance guarantee has been submitted as indicated below

<input type="checkbox"/> Performance Guarantee Accepted	_____ date	_____ amount	_____ expiration date
<input type="checkbox"/> Inspection Fee Paid	_____ date	_____ amount	
<input type="checkbox"/> Building Permit	_____ date		
<input type="checkbox"/> Performance Guarantee Reduced	_____ date	_____ remaining balance	_____ signature
<input type="checkbox"/> Temporary Certificate Of Occupancy	_____ date	<input type="checkbox"/> Conditions (See Attached)	
<input type="checkbox"/> Final Inspection	_____ date	_____ signature	
<input type="checkbox"/> Certificate Of Occupancy	_____ date		
<input type="checkbox"/> Performance Guarantee Released	_____ date	_____ signature	
<input type="checkbox"/> Defect Guarantee Submitted	_____ submitted date	_____ amount	_____ expiration date
<input type="checkbox"/> Defect Guarantee Released	_____ date	_____ signature	

CENTER LINE CONSTRUCTION, INC.

P.O. Box 1264
PORTLAND, ME 04104
(207) 767-5609 8460042

Sept. 15, 1997

Site Plan Review Statement

Project: Installation of two 25,000 Gal. Milk Tanks


Owner: H.P. Hood & Sons, Inc. Mr. John Kneb, Pres./C.E.O.
349 Park Avenue Catamount Dairy Holdings
Portland, Me. 04101 90 Everett Ave., Suite 200
Chelsea, MA 02150

Cost of Project:


Foundation work \$47,800.
New Tanks 125,000. (by owner)

1. Proposed Use: Install two new 25,000 gal milk tanks next to existing milk tanks.
2. Area of Site: 64,910 sq.ft. New tanks will set on a 15' x 30' concrete foundation/slab.
3. Easements: No new easements.
4. Solid Waste: No solid waste to be generated.
5. Off-site facilities; No change
6. Surface Drainage: The existing site is almost completely paved and served by a system of existing storm drains. The new tanks should have little or no impact on this system.
7. Construction plan: Install new foundation, set new tanks, & build "hall" to tie in system.
8. Regulatory Approvals - After new tanks are completely finished the FDA will inspect for final approval.
9. Evidence of Financial & Technical Capacity:
The project is being funded from Hoods Corp. assets.
Hood has been a going concern for many years.
10. Evidence of Title: Cumberland Co. Registry of Deeds 12272/84
11. Unusual Characteristics of Site: None

Center Line Construction, Inc.



Richard L. Miller, President



CITY OF PORTLAND

June 16, 2000

Phillip Doughty
364 US Route 1
Falmouth, ME 04105

re: HP Hood at 349 Park Ave.

Dear Mr. Doughty:

On May 3, 2000, the Portland Planning Authority approved the site plan application for the high bay cooler expansion at the HP Hood facility at 349 Park Avenue.

The proposed site plan was found to be in conformance with the Site Plan Ordinance of the Land Use Code.


Please note the following provisions and requirements for all site plan approvals:

1. A performance guarantee covering the site improvements as well as an inspection fee payment of 1.7% of the guarantee amount must be submitted to and approved by the Planning Division and Public works prior to the recording of the subdivision plat. The subdivision approval is valid for three (3) years.
2. The site plan approval will be deemed to have expired unless work in the development has commenced within one (1) year of the approval or within a time period agreed upon in writing by the City and the applicant. Requests to extend approvals must be received before the expiration date.
3. A defect guarantee, consisting of 10% of the performance guarantee, must be posted before the performance guarantee will be released.
4. Prior to construction, a preconstruction meeting shall be held at the project site with the contractor, development review coordinator, Public Work's representative and owner to review the construction schedule and critical aspects of the site work. At that time, the site/building contractor shall provide three (3) copies of a detailed construction schedule to the attending City representatives. It shall be the contractor's responsibility to arrange a mutually agreeable time for the preconstruction meeting.
5. If work will occur within the public right-of-way such as utilities, curb, sidewalk and driveway construction, a street opening permit(s) is required for your site. Please contact Carol Merritt at 874-8300, ext. 8828. (Only excavators licensed by the City of Portland are eligible.)

The Development Review Coordinator (who is located at DeLuca Hoffman at 775-1121) must be notified five (5) working days prior to date required for final site inspection. Please make allowances for completion of site plan requirements determined to be incomplete or defective during the inspection. This is essential as all site plan requirements must be completed and approved by the Development Review Coordinator prior to issuance of a Certificate of Occupancy. Please schedule any property closing with these requirements in mind.

If there are any questions, please contact the Planning Staff.

Sincerely,



Joseph E. Gray, Jr.
Director of Planning and Urban Development

cc: ✓ Alexander Jaegerman, Chief Planner
✓ Sarah Hopkins, Senior Planner
P. Samuel Hoffses, Building Inspector
Marge Schmuckal, Zoning Administrator
Tony Lombardo, Project Engineer
Development Review Coordinator
William Bray, Director of Public Works
Nancy Knauber, Associate Engineer
Jeff Tarling, City Arborist
Penny Littell, Associate Corporation Counsel
Lt. Gaylen McDougall, Fire Prevention
Inspection Department
Lee Urban, Director of Economic Development
Don Hall, Appraiser, Assessor's Office
Susan Doughty, Assessor's Office
Approval Letter File

City of Portland Planning Department

389 Congress Street, 4th Floor
Portland, ME 04101
207-874-8721 or 207-874-8719
Fax: 207-756-8258

FAX TRANSMISSION COVER SHEET

Date: _____

To: Phil Dougherty

Company: _____

Fax #: 781-2908

From: Sarah Hopkins

RE: _____

Phil -

I spoke too soon.

Here are comments from Public Works.

Note #1 can be addressed with a note on the
plan.

Note #2 can be addressed w/ a detail.

Sarah

YOU SHOULD RECEIVE 2 PAGE(S),
INCLUDING THIS COVER SHEET.
IF YOU DO NOT RECEIVE ALL THE PAGES,
PLEASE CALL 207-874-8721 OR 207-874-8719.

From: Anthony Lombardo
To: Sarah Hopkins
Date: Thu, Mar 23, 2000 9:50 AM
Subject: HP Hood Addition.....3/23/00

Sarah,

I have reviewed the submittal package and offer the following comments:

1. Public Works did a recent inspection of the storm drain system into which HP Hood currently discharges. The structures and piping have a large amount of sediment collected. As a result, Public Works is requesting the applicant thoroughly clean the structures and pipes, both existing and proposed, at an appropriate time near the completion of this development.
2. Public Works is also requesting that all proposed and existing catch basin structures be fitted with "Casco Traps" or an approved equivalent.

BK 12272PG084

66822

QUITCLAIM DEED WITH COVENANT

H.P. HOOD INC., a Massachusetts corporation, having a place of business at 500 Rutherford Avenue, Boston, Massachusetts 02129, for full value and consideration paid, hereby grants to H.P. HOOD & SONS, INC., a Massachusetts corporation, having a place of business and a mailing address at 500 Rutherford Avenue, Boston, Massachusetts 02129, with QUITCLAIM COVENANT, those parcels of land located at or near 349 Park Avenue in the City of Portland, County of Cumberland and State of Maine, as more particularly described in Exhibit A attached hereto and made a part hereof, together with all buildings, structures and improvements located thereon, and together with all rights and appurtenances pertaining to such land.

Being the same premises conveyed to H.P. Hood Inc. by deed of Agri-Mark, Inc., dated May 9, 1991, and recorded in the Cumberland County Registry of Deeds in Book 9555, page 137.

The premises are conveyed subject to and with the benefit of all easements, restrictions, rights of way and other matters of record, if any, insofar as the same are now in force and applicable.

IN WITNESS WHEREOF, H.P. Hood Inc. has caused this deed to be executed and sealed by Robert L. Keller, its duly authorized President, this 15th day of December, 1995.

WITNESS: H.P. HOOD INC.

Robert L. Keller

By: *Robert L. Keller*
Robert L. Keller
President

COMMONWEALTH OF MASSACHUSETTS

County of Suffolk, ss.

December 15, 1995

Personally appeared the above-named Robert L. Keller, President of H.P. Hood Inc., and acknowledged the foregoing instrument to be the free act and deed of H.P. Hood Inc.

Before me,

Mack S. Kinnihan
Notary Public/Attorney-at-Law
Print Name: *Mack S. Kinnihan*
My Commission Expires: *7/27/96*

SEAL

F:\MXN\JKB74\FED.POR

RECEIVED
SEP 15 1997
RECEIVE

BK 12272PG085

EXHIBIT A

A certain lot or parcel of land situated in the City of Portland, in the County of Cumberland and State of Maine, bounded and described as follows:

Beginning at a point on the northerly side of Park Avenue, said point being twenty (20) feet northwesterly measured along said Park Avenue from the point of intersection of a line extended southwesterly one hundred eighteen (118) feet from and measured normal to the center or base line of location of said Portland Terminal Company as established by the Federal Valuation Plans dated June 30, 1916:

Thence northwesterly along said Park Avenue fifty-four (54) feet, more or less, to the southeasterly corner of land now or formerly of H.P. Hood & Sons, Inc.; Thence N 19° 27' 30" W along the northeasterly line of said Hood land and continuing on a straight prolongation of said northeasterly line a distance of five hundred forty and nine-tenths (540.9) feet, more or less, to a point which is one hundred eighteen (118) feet southwesterly of and measured normal to said base line;

Thence southeasterly on a straight line a distance of five hundred sixty-one and three tenths (561.3) feet, more or less, to the point of beginning. Containing 13,760 square feet, more or less.

A certain lot or parcel of land situated in Portland, in the County of Cumberland, and State of Maine, and bounded and described as follows:

Beginning at a point in the northerly side line of Park Avenue, formerly called Portland Street in said City of Portland, which point is seventy-four feet (74') westerly along said northerly side line of said Park Avenue, from the southwesterly corner of a strip of land conveyed to the Maine Central Railroad Company by trustees of the J.B. Brown Estate; thence from said point northerly by the westerly side line of the triangular lot of land sold by the J.B. Brown & Sons to the Maine Central Railroad Company three hundred eighteen and fifty-five hundredths (318.55) feet to a stake; thence westerly on a line parallel to said Park Avenue two hundred (200) feet to a stake, thence southerly, parallel to the westerly side line of the triangular lot of land above referred to, three hundred eighteen and fifty-five hundredths (318.55) feet to a stake in the northerly side line of said Park Avenue, thence easterly along side line of said Park Avenue, to the point of beginning containing sixty thousand (60,000) square feet of land northerly of the present line of Park Avenue.

Excepting so much of the premises as was conveyed by H.P. Hood & Sons, Inc. to the State of Maine by deed dated July 28, 1971 and recorded with the Cumberland County Registry of Deeds in Book 3186, Page 109.

Together with all of Grantor's right, title and interest in the land abutting the above-described premises formerly known as St. James Street which was the subject of the Order of

Discontinuance adopted by the Portland City Council on July 3, 1989 recorded in the Cumberland County Registry of Deeds in Book 8882, Page 11.

RECEIVED
RECORDED REGISTRY OF DEEDS

95 DEC 20 PM 2:25

CUMBERLAND COUNTY

John B. Brown

Haley & Aldrich, Inc.

10/18/89

REPORT ON

SUBSURFACE AND FOUNDATION INVESTIGATION
PROPOSED SILO AND ADDITION
PORTLAND, MAINE

Consulting

Geotechnical Engineers,

Geologists and

Hydrogeologists

10/18/89

REPORT ON

SUBSURFACE AND FOUNDATION INVESTIGATION
PROPOSED SILO AND ADDITION
PORTLAND, MAINE


by

Haley & Aldrich, Inc.
Portland, Maine

for

HP Hood, Inc.
Portland, Maine

File No. 80154-00



October 1989



16 October 1989
File No. 80154-00

HP Hood, Inc.
349 Park Avenue
Portland, ME 04101

Attention: Mr. Scott Sawyer

Subject: Subsurface and Foundation Investigation
Proposed Silo and Addition
Portland, Maine

Gentlemen:

This report presents the results of our evaluation of the subsurface conditions and foundation requirements for the proposed silo and building addition at your facility in Portland, Maine. This evaluation was performed in accordance with our proposal dated 19 September 1989.

In summary, it is our opinion that the silo and addition can be supported on spread footings bearing on undisturbed, naturally deposited clay or on compacted structural fill placed after removal of unsuitable soil. In addition, an earth supported slab-on-grade may be used for the ground floor. Specific recommendations for foundation design and construction considerations are presented below.

INTRODUCTION

The silo and addition will be constructed at your facility on Park Avenue. The silo will be built adjacent to an existing silo located along Park Avenue. The addition will be built on the north and east sides of the existing building. The site of the proposed silo and portions of the building addition are presently paved roadways and parking areas.

Consulting
Geotechnical Engineers,
Geologists and
Hydrogeologists

622 Congress Street
P.O. Box 4076
Portland, ME 04101
207/772-7869
FAX 207/772-2698

Offices
Cambridge, Massachusetts
Glastonbury, Connecticut
Bedford, New Hampshire

Affiliate
H&A of New York
Rochester, New York

HP Hood, Inc.
16 October 1989
Page 2

Portions of the existing building consist of a two-story brick structure with a basement in the area near the proposed silo. The basement floor is approximately 8 ft. below ground surface. The remainder of the building consists of a one-story masonry block structure with loading docks and no basement.

PROPOSED CONSTRUCTION

It is understood that the silo will be approximately 60 ft. high and 12 ft. in diameter. It is anticipated that the silo will require a pad approximately 15 ft. square. Total load of the silo is on the order of 400 kips.

It is further understood that the addition will consist of a two-story building having a plan area of approximately 2,100 sq. ft. A portion of the addition will consist of a second story built over the masonry block building with loading docks. It is anticipated that the addition will be supported independently from the existing building. Construction will require relocation of some existing fuel pumps and buried tanks.

SUBSURFACE CONDITIONS

Subsurface Explorations

A total of four test pits, TP1 to TP4, were excavated at the site on 20 September 1989 by W.H. Lavigne Excavating at locations shown on Figure 2, Test Pit Plan. The test pits were excavated to depths varying from 7 ft. to 10 ft. below ground surface using a Ford 555A backhoe. All test pits terminated in naturally deposited soil and were backfilled with the excavated material.

Haley & Aldrich, Inc. (H&A) monitored the test pits and prepared the logs which are included in Appendix A. Test pit locations were determined by H&A by taping from existing buildings and site features.

During excavation of test pits, the working space was monitored for volatile organic vapors using a photoionization detector. No significantly elevated levels above background were noted, however, a strong fuel oil odor was noted in TP1 and TP2 and an oily sheen was noted on the water in TP2 during excavation. A sample of the material from 4.5 ft. to 7 ft. in TP2 was monitored and a level of 30 parts per million was recorded.

The test pit logs depict subsurface conditions and groundwater levels only at the specific locations and times indicated on the logs. Soil conditions at other locations may vary from conditions observed in the test pits, and the passage of time may result in differing groundwater conditions.



Subsurface Conditions

The test pits disclose the following subsurface conditions from ground surface:

<u>Thickness (Ft.)</u>	<u>Description</u>
1.4 to 5.4	Light brown, gravelly, coarse to fine SAND; to dark brown, silty CLAY, with various amounts of brick, ash and scrap metal - FILL -
1.5 to 6.4	Gray to brown, mottled, silty CLAY, trace fine sand
Greater than 6.4	Gray, silty, fine SAND; to brown, silty medium to fine SAND, little to trace gravel, coarse sand and cobbles and boulders.

Water was measured in TP1 and TP3 at depths of 8 ft. and 5 ft., respectively, below ground surface. No water was encountered in the other test pits. However, observations were over a short period of time and do not represent the actual groundwater conditions. Water levels at the site will fluctuate with precipitation, temperature, season and construction activity in the area. Thus, water levels during and following construction may vary from conditions observed in the test pits.

RECOMMENDATIONS FOR FOUNDATION DESIGN AND CONSTRUCTION

Recommended Foundation Type and Design Criteria

The fill is not considered suitable for support of the silo or building and floor slab. All fill should be removed from within the silo and building limits.

It is recommended that the silo and building be supported on spread footings bearing on undisturbed, naturally deposited clay or sand or on compacted structural fill placed after removal of unsuitable soil.

Footings may be proportioned for an allowable bearing pressure of 2,000 lbs per sq. ft. All footings should be at least 2 ft. wide.

Exterior footings should be founded at least 4.5 ft. below the lowest adjacent ground surface exposed to freezing. Interior footings should be founded a minimum of 1.5 ft. below the ground floor.



The proposed silo will be located adjacent to the existing silo and a portion of the existing building with a basement approximately 8 ft. below ground surface. Normally, the foundation for the silo should bear at approximately the same elevation as the basement so as not to add lateral load to the basement wall. However, the existing silo, which is adjacent to the basement wall, bears at approximately 4.5 ft. below ground surface and the new silo should bear at approximately the same depth in order not to undermine the existing foundation. Because the new silo will be adjacent to a relatively small portion of the basement wall, it is anticipated that the silo bearing at approximately 4.5 ft. below ground surface will not apply excessive lateral loads to the basement wall. However, this loading condition should be reviewed by the structural engineer.

Footings for the new addition, where they abut the existing building, should bear at approximately the same elevation.

Compacted structural fill supporting footings should extend laterally from the footings to at least the limits defined by 1 horizontal to 1 vertical lines sloped outward and downward from points located at least 2 ft. horizontally beyond the bottom edges of the footings.

The ground floor slab may be a slab-on-grade bearing on compacted structural fill. For consistency, it is recommended that the floor slab bear on a minimum of 12 in. of compacted structural fill.

Lateral Foundation Loads

It is recommended that lateral loads be resisted by bottom friction on footings. It is recommended that a coefficient of friction equal to 0.35 be used for footings.

Fill Materials

Structural fill below footings and floor slab and backfill should consist of sandy gravel to gravelly sand. It should be free of organic material, loam, trash, snow, ice, frozen soil and other objectionable material, and should conform to the following gradation:

<u>Sieve Size</u>	<u>Percent Finer by Weight</u>
6 in.	100
No. 4	30 to 90
No. 40	10 to 50
No. 200	0 to 8



In open areas, compacted structural fill should be placed in layers not exceeding eight in. in loose measure and compacted by self-propelled compaction equipment at approximately optimum moisture content to a dry density of at least 95 percent of the maximum dry density, as determined in accordance with ASTM Test Designation D1557. In confined areas, the maximum particle size should be reduced to three in. and the loose layer thickness to six in. and compaction performed by hand-guided equipment.

Construction Considerations

It is anticipated that all foundation excavation can be accomplished with open excavation. The subgrade soil is susceptible to disturbance due to construction traffic (personnel and equipment). Equipment and personnel should not be permitted to travel across footing bearing surfaces. Subgrades should be protected against freezing if exposed to freezing temperatures during construction. The final excavation to grade should be performed using equipment with smooth-edge buckets.

Groundwater may be encountered during construction. It is anticipated that groundwater can be controlled by trenching and open pumping from sumps. All groundwater and surface runoff should be controlled in such a manner as to prevent disturbance to the subgrade and to permit construction in-the-dry.

It is recommended that excavation for foundations be monitored using a photoionization detector to check for the presence of volatile organic compounds. If elevated readings are encountered, provisions should be made for evaluating the source of the vapors and potential corrective action.

It is recommended that all aspects of earthwork and foundation construction be monitored by personnel qualified by training and experience.

LIMITATIONS OF RECOMMENDATIONS

This report has been prepared for specific application to the subject project in accordance with generally accepted geotechnical engineering practices. No other warranty, expressed or implied, is made. In the event that any changes in the nature, design or location of the building are planned, the conclusions and recommendations contained in this report should not be considered valid, unless the changes are reviewed and the conclusions of this report modified or verified in writing.




The recommendations presented herein are based in part upon the data obtained from the referenced test pits. The nature and extent of variations between the explorations may not become evident until construction. If variations then appear evident, it will be necessary to reevaluate the recommendations of this report.

We request that we be provided the opportunity for a general review of final design and specifications in order to determine that our earthwork and foundation recommendations have been interpreted and implemented in the design and specifications as they were intended.

It has been a pleasure to work with you on this project. Please do not hesitate to contact us if you have any questions or require additional information.


Sincerely yours,
HALEY & ALDRICH, INC.


Kenneth L. Recker
Vice President

KLR:ljw/1.05

Enclosures: Figure 1 - Project Locus
Figure 2 - Test Pit Plan
Appendix A - Logs of Test Pits





LEGEND:

TP1 NUMBER AND APPROXIMATE LOCATION OF TEST PITS EXCAVATED BY W.H. LAVIGNE EXCAVATING ON 20 SEPTEMBER 1989.

NOTES:

1. BASE PLAN PREPARED FROM 40 SCALE PLAN PROVIDED BY STRUCTURAL DESIGN CONSULTANTS.
2. TEST PITS MONITORED BY HALEY & ALDRICH, INC.
3. LOCATIONS OF TEST PITS DETERMINED BY HALEY & ALDRICH, INC. BY TAPING FROM EXISTING BUILDINGS.




FILE NO. 80154-00

CHARRETTE

	Haley & Aldrich, Inc. <small>Consulting Geotechnical Engineers, Geologists and Hydrogeologists</small>
	PROPOSED SILO AND ADDITION HP HOOD, INC. PORTLAND, MAINE TEST PIT PLAN
<small>SCALE: AS SHOWN</small>	<small>OCTOBER 1989</small>


FIGURE 2

HALEY & ALDRICH, INC., PORTLAND, MAINE Consulting Geotechnical Engineers, Geologists and Hydrogeologists		TEST PIT REPORT	TEST PIT NO. TP1 FILE NO. 80154-00
PROJECT: PROPOSED SILO AND BUILDING ADDITION LOCATION: PORTLAND, MAINE CLIENT: H.P. HOOD, INC. CONTRACTOR: W.H. LAVIGNE EXCAVATING EQUIPMENT USED: FORD 555A BACKHOE		LOCATION: SEE PLAN ELEVATION: EXPLORATION DATE: 20 SEPT 89 H&A REP.: S. DIXON	



WATER LEVEL			APPROXIMATE PIT DIMENSIONS AT SURFACE		SUMMARY
DATE	TIME*	DEPTH (FT)	LENGTH	WIDTH	DEPTH:
9-20-89	0.25	8.0	8.0 feet	4.0 feet	10.0 FT.
--	--	--	BOULDERS		JAR SAMPLES: --
--	--	--	8" to 18" DIAMETER: No.	-- = Vol.	BAG SAMPLES: --
* Hrs after completed			Over 18" DIAMETER: No.	-- = Vol.	WATER LEVEL: 8.0 FT.
					TEST PIT NO. TP1


HALEY & ALDRICH, INC., PORTLAND, MAINE Consulting Geotechnical Engineers, Geologists and Hydrogeologists		TEST PIT REPORT	TEST PIT NO. TP3 FILE NO. 80154-00
PROJECT: PROPOSED SILO AND BUILDING ADDITION LOCATION: PORTLAND, MAINE CLIENT: H.P. HOOD, INC. CONTRACTOR: W.H. LAVIGNE EXCAVATING EQUIPMENT USED: FORD 555A BACKHOE		LOCATION: SEE PLAN ELEVATION: EXPLORATION DATE: 20 SEPT 89 H&A REP.: S. DIXON	



WATER LEVEL			APPROXIMATE PIT DIMENSIONS AT SURFACE		SUMMARY
DATE	TIME*	DEPTH (FT)	LENGTH	WIDTH	DEPTH:
			8.0 feet	5.0 feet	9.8 FT.
					JAR SAMPLES: --
					BAG SAMPLES: --
					WATER LEVEL: 5.0 FT.
					TEST PIT NO. TP3

HALEY & ALDRICH, INC., PORTLAND, MAINE Consulting Geotechnical Engineers, Geologists and Hydrogeologists				TEST PIT REPORT		TEST PIT NO. TP3 FILE NO. 80154-00	
PROJECT: PROPOSED SILO AND BUILDING ADDITION LOCATION: PORTLAND, MAINE CLIENT: H.P. HOOD, INC. CONTRACTOR: W.H. LAVIGNE EXCAVATING EQUIPMENT USED: FORD 555A BACKHOE				LOCATION: SEE PLAN ELEVATION: EXPLORATION DATE: 20 SEPT 89 H&A REP.: S. DIXON			
SCALE IN FEET	SAMPLE NUMBER	SAMPLE DEPTH RANGE	STRATA CHANGE	DESCRIPTION OF MATERIALS	REMARKS		
2		0.4		Dark brown, coarse to fine SAND, little silt, trace gravel	Encountered former utility pole buried from 0.5 ft. to 5.0 ft. below ground surface. Gray clay deposit may represent the sediment that filled in a channel-like erosional feature cut into the underlying brown clay. Slight seepage at depth of 5.0 ft. within the gray clay suggests preferred ground water flow within the channel feature. FIELD VANE TESTS Undrained Shear Strength (tsf) Depth (ft.) (tests in brown clay) 3.0 .58 3.0 .56 (tests in gray clay) 3.0 .48 3.0 .64		
		0.8		Brown, gravelly, coarse to fine SAND, trace silt			
				Dark brown, coarse to fine SAND, to sandy GRAVEL, some fragments of brick and particles of ash, trace scrap metal pieces			
				-FILL-			
4		2.8		Gray, mottled, silty CLAY, trace organics			
				-MARINE DEPOSITS-			
6				Brown, mottled, silty CLAY, trace fine sand			
				-MARINE DEPOSITS-			
8							
10		9.2		Light brown, silty, fine SAND, trace clay			
				Bottom of Test Pit at 9.8 ft. No Refusal			
12							
WATER LEVEL			APPROXIMATE PIT DIMENSIONS AT SURFACE		SUMMARY		
DATE	TIME*	DEPTH (FT)	LENGTH 8.0 feet	WIDTH 5.0 feet	DEPTH: 9.8 FT.		
			BOULDERS		JAR SAMPLES: --		
			8" to 18" DIAMETER: No. -- = Vol. -- cu ft		BAG SAMPLES: --		
			Over 18" DIAMETER: No. -- = Vol. -- cu ft		WATER LEVEL: NE		
* Hrs after completed					TEST PIT NO. TP3		

HALEY & ALDRICH, INC., PORTLAND, MAINE Consulting Geotechnical Engineers, Geologists and Hydrogeologists				TEST PIT REPORT		TEST PIT NO. TP4 FILE NO. 80154-00	
PROJECT: PROPOSED SILO AND BUILDING ADDITION LOCATION: PORTLAND, MAINE CLIENT: H.P. HOOD, INC. CONTRACTOR: W.H. LAVIGNE EXCAVATING EQUIPMENT USED: FORD 555A BACKHOE				LOCATION: SEE PLAN ELEVATION: EXPLORATION DATE: 20 SEPT 89 H&A REP.: S. DIXON			
SCALE IN FEET	SAMPLE NUMBER	SAMPLE DEPTH RANGE	STRATA CHANGE	DESCRIPTION OF MATERIALS	REMARKS		
2		0.3		Bituminous concrete -PAVEMENT-	FIELD VANE TESTS Undrained Shear Strength (tsf) Depth (ft.) 2.0 1.56 2.0 1.80 2.0 1.84		
		0.6		Light brown, gravelly, coarse to fine SAND, trace silt -FILL-			
		0.8		Bituminous concrete -PAVEMENT-			
		1.4		Light brown, gravelly, coarse to fine SAND, trace silt -FILL-			
4		2.9		Olive-brown, mottled, silty CLAY, trace fine sand, trace organics, with pockets of dark gray, fine sandy SILT and partings of fine SAND			
				Brown, mottled, silty fine SAND, interbedded with fine SAND, little silt			
6				-MARINE DEPOSITS-			
				Brown, silty medium to fine SAND, little gravel, coarse sand and clay, few cobbles and boulders			
8				-GLACIAL TILL-			
10		9.3		Gray, silty, fine SAND, little coarse to medium sand, trace gravel and clay			
				Bottom of Test Pit at 9.8 ft. No Refusal			
12							
WATER LEVEL			APPROXIMATE PIT DIMENSIONS AT SURFACE		SUMMARY		
DATE	TIME*	DEPTH (FT)	LENGTH 8.0 feet	WIDTH 3.0 feet	DEPTH: 9.8 FT.		
			BOULDERS		JAR SAMPLES: --		
			8" to 18" DIAMETER: No. 3 = Vol. 5 cu ft		BAG SAMPLES: --		
			Over 18" DIAMETER: No. -- = Vol. -- cu ft		WATER LEVEL: NE		
* Hrs after completed					TEST PIT NO. TP4		




PARK AVENUE

H.P. HOOD & SON
PORTLAND, MAINE
SCALE: 1" = 40'

NEW HOOD YARD DRAIN
ENTRANCE TO SEWER
IN STREET.

H.P. HOOD & SON
ENGINEERS
100 STATE ST. PORTLAND, ME.



PARCEL NO. 715-2
 NORTHERN UTILITIES, INC.
 LAND TAKEN = 3.69 ± AC.
 (ENTIRE LOT)

PARCEL NO. 715-3
 NORTHERN UTILITIES, INC.
 LAND TAKEN = 1.28 ± AC.
 (ENTIRE LOT)

PARCEL NO. 721
 MICHAEL J. THORNTON JR.
 LAND TAKEN = 20,900 ± S.F.
 (ENTIRE LOT)

PARCEL NO. 722
 MARY E. ARSENAULT
 LAND TAKEN = 14,000 ± S.F.
 (ENTIRE LOT)

PARCEL NO. 723
 J.B. BROWN & SONS
 MARGARET E. BLACK
 HELEN S. BEYER
 HENRY ST. JOHN SMITH JR.
 NANCY S. SALTONSTALL
 J. HOPKINS SMITH JR.
 BANK OF NEW YORK } TRUSTEES
 LANGDON P. MARVIN } UNDER THE
 WILL OF
 ST. JOHN SMITH

LAND TAKEN =
 TOTAL AREA =

PARCEL NO. 724-1
 H.P. HOOD & SONS, INC.
 LAND TAKEN = 4,900 ± S.F.
 TOTAL AREA = 73,750 ± S.F.

PARCEL NO. 724-2
 LAND TAKEN =
 1970185

PARCEL NO. 725
 E&A REALTY COMPANY
 LAND TAKEN = 6,500 ± S.F.
 (ENTIRE LOT)

PARCEL NO. 726
 (OMMITTED)

PARCEL NO. 727
 J.B. BROWN & SONS
 MARGARET E. BLACK
 HELEN S. BEYER
 HENRY ST. JOHN SMITH JR.
 NANCY S. SALTONSTALL
 CITY OF PORTLAND
 LAND TAKEN =
 TOTAL AREA =

PARCEL NO. 728
 CITY OF PORTLAND