Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 11/06/14

GENERAL NOTES

1. PARTITIONS SHALL BE CARRIED TO THE FLOOR DECKING OF THE FLOOR ABOVE UNLESS NOTED OTHERWISE
2. IN BATH ROOMS, TOILET ROOMS, TRASH ROOMS, RECYCLING ROOMS, JANITOR ROOMS, MAINTENANCE ROOMS W/ GPDW WALLS, PROVIDE 5/8" MR GPDW IN LIEW OF REGULAR GPDW ON ALL PARTITIONS WITHIN THE ROOM
3. ALL GPDW TO BE TYPE-X GPDW
4. ALL MR GPDW TO BE TYPE-X MR GPDW
5. INSTALL A CONTINUOUS BEAD SEALANT BETWEEN ALL TOP AND BOTTOM WALL PLATES AND THE FLOOR & STRUCTURAL DECKING ABOVE.

PARTITION LEGEND

NO SCALE

A1

ROBERT J. FOSTER ARCHITECT
36 Groveside Road, Portland, Maine 04102
(207) 761-3822

REGISTERED ARCHITECT ROBERT J FOSTER #1734 STATE OF MAINE

Project Title

U-HAUL MOVING & STORAGE

425 MARGINAL WAY
Portland, Maine

Mark	Date	Description
	09 - 08 - 14	ISSUED FOR CONSTRUCTION

Issue Dates

Drawing Title

SYSTEMS

Drawing Number

A40.1