Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 11/06/14

NOTES:

1. SEE E0.0 FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES.

KEYED NOTES:

1. MOUNT 42" A.F.F.
2. TYPICAL POWER POLE LOCATION. RUN ALL POWER/INTERNET FROM ABOVE TO POWER POLE. THEN RUN POWER/INTERNET TO CABINET UTILIZING BASE AREA, BRINGING UP THROUGH HOLES AT BOTTOM OF EACH CABINET. WIRE MOLD P/N 25DTC-4. ORDER HEIGHT TO SUIT SPECIFIC SHOWROOM APPLICATION.
3. COUNTERTOP RECEPTACLE. MOUNT 8" ABOVE COUNTERTOP. COORDINATE WITH BACKSPLASH.
4. VEHICLE LIFT SYSTEM. COORDINATE WITH OWNER-FURNISHED EQUIPMENT.
5. VESTIBULE SLIDING DOOR OPERATOR. COORDINATE WIRING REQUIREMENTS WITH MANUFACTURERS DRAWINGS.
6. JUNCTION BOX FOR EXTERIOR SIGNAGE POWER LOAD MUST BE FIELD-VERIFIED. 120V-20AMP CURCUIT BEING FURNISHED.

1 ELECTRICAL POWER & SYSTEMS PLAN
SCALE: 1/8 = 1'-0"

ISSUE FOR CONSTRUCTION

PLAN NORTH

STATE OF MAINE
TIMOTHY D. MATTHEWS
No. 9199
LICENSED
PROFESSIONAL ENGINEER

9/4/14

ROBERT J. FOSTER ARCHITECT
36 Groveside Road, Portland, Maine 04102
(207) 761-3822

SWIFTCURRENT
Engineering Services
10 Forest Falls Drive, Unit 4B
Yarmouth, ME 04096
Tel: (207) 847-9280

Project Title

U-HAUL MOVING & STORAGE

425 MARGINAL WAY
Portland, Maine

Mark	Date	Description
	09 - 1 - 14	ISSUE FOR CONSTRUCTION
	07 - 18 - 14	PROGRESS DRAWING

Issue Dates

Drawing Title

ELECTRICAL POWER & SYSTEMS PLAN

Drawing Number

E1.0