Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 11/06/14

LAVATORY SECTION — 1/4" = 1'-0" — D1

LEGEND – TOILET RM ACCESSORIES

	ITEMS	MANUF. NO.	MTD. HEIGHTS
1	42" X 1 1/2" GRAB BAR	BOBRICK B-6806.99	34" A.F.F. TO C.L.
2	36" X 1 1/2" GRAB BAR	BOBRICK B-6806.99	34" A.F.F. TO C.L.
3	18" X 1 1/2" GRAB BAR	BOBRICK B-6806.99	40" A.F.F. TO BOT.
4	TOILET TISSUE DISPENSER	BOBRICK B-5288	28" A.F.F. TO TOP
5	PAPER TOWEL DISPENSER	BOBRICK B-52860	PER MANUF. INSTRUCTIONS
6	SOAP DISPENSER	BOBRICK B-5050	PER MANUF. INSTRUCTIONS
7	TOILET SEAT COVER DISPENSER	BOBRICK B-5221	45" A.F.F. TO TOP
8	24"W X 40"H MIRROR	N.A.	3'-3" TO BOT. OF GLASS

ACCESSORIES SCHEDULE — N.A. — C1

TOILET RM. ELEVATION | TOILET RM. ELEVATION | TOILET RM. ELEVATION | TOILET RM. ELEVATION

TYP. TOILET ROOM ELEVATIONS — 1/4" = 1'-0" — B1

TOILET RM. PLANS

TOILET RMS 106, 107 & 108 — 1/4" = 1'-0" — A1

ROBERT J. FOSTER ARCHITECT
36 Groveside Road, Portland, Maine 04102
(207) 761-3822

REGISTERED ARCHITECT ROBERT J. FOSTER #1734 STATE OF MAINE

Project Title

U-HAUL MOVING & STORAGE

425 MARGINAL WAY
Portland, Maine

Mark	Date	Description
	09 - 08 - 14	ISSUED FOR CONSTRUCTION

Issue Dates

Drawing Title

ENLARGED PLANS & DETAILS

Drawing Number

A90.1