Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 11/06/14

ROOF PLAN — 1/8" = 1'-0" — B1

EQUIP. CURB DETAIL — 1" = 1'-0" — A4

ROOF DRAIN DETAIL — 1" = 1'-0" — A3

ROOF VENT DETAIL — 1" = 1'-0" — A2

GENERAL NOTES:

CO-ORDINATE ROOF PENETRATIONS WITH MECHANICAL PLUMBING AND ELECTRICAL CONTRACTORS.

VERIFY THAT ADEQUATE STRUCTURAL SUPPORT IS PROVIDED AT ROOF PENETRATIONS FOR MECHANICAL UNITS.

PROVIDE CRICKET INSULATION AT MECHANICAL CURB LOCATIONS

PROVIDE ADEQUATE SUPPORT FOR ROOF LEADERS FOR ROOF DRAINS ONCE THEY ENTER THE BUILDING.

PROVIDE ROOF WALK PADS TO ALL ROOF TOP MECHANICAL UNITS - PADS SHALL BE APPROVED BY ROOFING MANUFACTURER.

GENERAL NOTES — NTS — A1

ROBERT J. FOSTER ARCHITECT
36 Groveside Road, Portland, Maine 04102
(207) 761-3822

REGISTERED ARCHITECT ROBERT J. FOSTER #1734 STATE OF MAINE

Project Title

U-HAUL MOVING & STORAGE

425 MARGINAL WAY
Portland, Maine

Mark	Date	Description
	09 - 08 - 14	ISSUED FOR CONSTRUCTION

Issue Dates

0 5 10 15 20
Graphic Scale (feet)

Drawing Title

ROOF PLAN

Drawing Number

A15.1