Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 11/06/14

NOTES:

1. SEE E0.0 FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES.
2. WIRE EMERGENCY EXIT SIGNS AND LIGHTS TO LOCAL LIGHTING CIRCUIT.

KEYED NOTES:

1. MOUNT REMOTE TEST INDICATOR AT FIRE ALARM CONTROL PANEL.
2. LIGHTING SWITCH IN ANY OF THE THREE BATHROOMS SHALL BE WIRED TO A RELAY TO TURN EF-1 ON. FURNISH A 2-POLE OCCUPANCY SENSOR IN THESE ROOMS. WIRE THE SECOND POLE ON THESE SWITCHES IN PARALLEL AND WIRE TO RELAY FOR TURNING ON THE FAN. RELAY TO BE FURNISHED BY ELECTRICAL.

1 ELECTRICAL LIGHTING & FIRE ALARM PLAN
SCALE: 1/8 = 1'-0"

ISSUE FOR CONSTRUCTION

PLAN NORTH

2 EXTERIOR LIGHTING CONTROLS
SCALE: NOT TO SCALE

STATE OF MAINE
TIMOTHY D. MATTHEWS
No. 9199
LICENSED
PROFESSIONAL ENGINEER

9/4/14

ROBERT J. FOSTER ARCHITECT
36 Groveside Road, Portland, Maine 04102
(207) 761-3822

SWIFTCURRENT
Engineering Services
10 Forest Falls Drive, Unit 4B
Yarmouth, ME 04096
Tel: (207) 847-9280

Project Title

U-HAUL MOVING & STORAGE

425 MARGINAL WAY
Portland, Maine

Mark	Date	Description
1	09 - 26 - 14	REVISED EXIT SIGN
0	09 - 1 - 14	ISSUE FOR CONSTRUCTION

Issue Dates

Drawing Title

ELECTRICAL LIGHTING & FIRE ALARM PLAN

Drawing Number

E2.0