



ID	Width	Height	Thickness	Quantity	Model #	Manufacturer	Type	Finish	Glazing	Fire Rating	Notes
1	3'-0"	6'-8"	0'-1 3/4"	4			INTERIOR SWING	SOLID CORE WD			
2	6'-0"	6'-8"	0'-1 3/4"	1			INTERIOR SWING PAIR	SOLID CORE WD			
3	3'-0"	6'-8"	0'-1 3/4"	1			FIRE RATED SWING	FIRE RATED	NONE	90 MIN	
4	2'-6"	6'-8"	0'-1 3/4"	1			INSULATED COOLER				BY COOLER MANUFACTURER
P	2'-6"	6'-8"	0'-1 1/4"	2			TOILET PARTITION				BY MANUFACTURER
P	3'-0"	6'-8"	0'-1 1/4"	1			TOILET PARTITION				BY MANUFACTURER
				10							

IBC OCCUPANCY KEY NOTES		NFPA OCCUPANCY KEY NOTES	
BAY 1	<p>A: ASSEMBLY 2,337 SF / 15 = 156 Occupants</p> <p>F-2: FACTORY, LOW-HAZARD 669 SF / 100 = 7 Occupants</p>	BAY 1 (MIXED OCCUPANCY)	<p>ASSEMBLY 2,108 SF / 15 = 156 Occupants</p> <p>INDUSTRIAL 669 SF / 100 = 7 Occupants</p>
BAY 2, 3 & 4	<p>F-2: FACTORY, LOW-HAZARD 5,624 SF / 100 = 57 Occupants</p>	BAY 2, 3 & 4	<p>INDUSTRIAL 5,624 SF / 100 = 57 Occupants</p>

1 MAIN LEVEL
SCALE: 1/8" = 1'-0"

