Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 08/26/14

1 WINDOW TYPES
1/4" = 1'-0"

LEGEND:
T = TEMPERED GLASS
FG = FIBERGLASS
AL = ALUMINUM
DH = DOUBLE HUNG
AW = AWNING
LV = LOUVER
F = FIXED
CL = GLIDER
C = CASEMENT

NOTES:
1. FULL SCREENS ALL OPERABLE OPENINGS
2. CONTRACTOR TO VERIFY ALL ROUGH OPENINGS
3. ALL EXTERIOR GLAZING INSULATED
4. FRAME OPENINGS WITH ELEVATIONS
5. SEAL WINDOW TO ROUGH OPENINGS WITH LOW EXPANDING FOAM INSULATION - SEE DETAILS

WINDOW SCHEDULE

KEY	ACTION	ROUGH * OPENING (WxH) VIF	TO CTRED HEIGHT FROM 1ST FLOOR	DETAILS HEAD	DETAILS JAMB	DETAILS SILL	MATERIAL	FINISH	FOR TEMPERED GLASS LOCATIONS SEE WINDOW ELEVATION TYPES FOR MASONRY OPENING DIMENSIONS COORDINATE COURSING WITH EXTERIOR ELEVATION SHEETS AND PLAN AND SECTION DETAIL SHEETS REMARKS
A	F/AW	4'-0" X 8'-0"	-	-	-	-	AL	PTD	4 LIGHT (1 ACTIVE AWNING)
A'	F/AW	4'-0" X 8'-0"	-	-	-	-	AL	PTD	4 LIGHT (1 ACTIVE AWNING) 1 UNIT TEMPERED
B	AW	7'-9" X 2'-9"	-	-	-	-	AL	PTD	DIVIDED 2 LIGHT AWNING 2
C	F/AW	7'-9" X 8'-1"	-	-	-	-	AL	PTD	DIVIDED 2 LIGHT AWNING (TOP) + 4 LIGHT FIXED (BELOW)
D	F/AW	4'-1 1/2" X 4'-1 1/2"	-	-	-	-	AL	PTD	SINGLE AWNING
E	AW	3'-0" X 2'-0"	-	-	-	-	AL	PTD	SINGLE AWNING
F	AW	2'-7" X 2'-0"	-	-	-	-	AL	PTD	SINGLE AWNING
G	AW	1'-9" X 2'-10 1/2"	-	-	-	-	AL	PTD	SINGLE AWNING
H	F	14'-0" X 9'-10"	-	-	-	-	AL	PTD	THERMALLY BROKEN STOREFONT UNIT WITH MULL REINFORCING AS REQUIRED
I	F/AW	8'-0" X 8'-0"	-	-	-	-	AL	PTD	8 LIGHT (2 ACTIVE AWNING) 1

2 TYPICAL WINDOW TRIM
NOT TO SCALE

WINDOW NOTES:

* 1.) COORDINATE AND ADJUST ROUGH OPENING DIMENSIONS TO ACCOMMODATE SILL PAN FLASHING SYSTEM

2.) PROVIDE MULL REINFORCING AT ALL MULTI-UNIT WINDOWS AS REQUIRED TO ACHEIVE SPECIFIED DP-50 RATING

3.) ALL EXTERIOR GLAZING TO BE LOW-E ARGON FILLED INSULATED GLAZING UNITS

REGISTERED ARCHITECT
RYAN J. SENATORE
No. 3323
STATE OF MAINE

© 2014 RYAN SENATORE ARCHITECTURE

RENOVATIONS TO
170 ANDERSON STREET
PORTLAND, MAINE

RSA
RYAN SENATORE
ARCHITECTURE
565 CONGRESS STREET
SUITE 304
PORTLAND, MAINE 04101
207-650-6414
senatorearchitecture.com

CONSULTANTS:

STRUCTURAL:
Structural Integrity
77 Oak Street
Portland, ME 04101
207-774-4614

REVISIONS:
1 REVISION #1 - 06/12/14
2 REVISION #2 - 06/30/14

DATE:	JUNE 4, 2014
PROJECT No.	1416
DRAWN BY:	RJS / RRT
CHECKED BY:	RJS
SCALE:	AS NOTED

SHEET TITLE:
WINDOW SCHEDULE

A7-0