



Submittal Data Sheet

1.5-Ton 2x2 Ceiling Cassette

FFQ18LVJU

FEATURES

- 2,3, or 4-way airflow pattern
- Built-in condensate pump (up to 22")
- Fresh air intake knockout
- Matches with multi-split MXS outdoor models only
- 12 year limited parts and compressor warranty with online registration

BENEFITS

- Compact design





Submittal Data Sheet

1.5-Ton 2x2 Ceiling Cassette

FFQ18LVJU

PERFORMANCE

Indoor Unit Model No.	FFQ18LVJU	Indoor Unit Name:	1.5-Ton 2x2 Ceiling Cassette
Type:	Ceiling Cassette	Rated Cooling Conditions:	Indoor (°F DB/WB): 80 / 67 Ambient (°F DB/WB): 95 / 75
Rated Cooling Capacity (Btu/hr):	18,000	Rated Heating Conditions:	Indoor (°F DB/WB): 70 / 70 Ambient (°F DB/WB): 47 / 43
Sensible Capacity (Btu/hr):		Rated Piping Length(ft):	
Cooling Input Power (kW):		Rated Height Separation (ft):	
Rated Heating Capacity (Btu/hr):	21,500		

INDOOR UNIT DETAILS

Power Supply (V/Hz/Ph):	208-230 / 60 / 1	Airflow Rate (H/L) (CFM):	530/353
Power Supply Connections:	L1, L2, Ground	Moisture Removal (Gal/hr):	
Min. Circuit Amps MCA (A):		Gas Pipe Connection (inch):	1/2
Max Overcurrent Protection (MOP) (A):		Liquid Pipe Connection (inch):	1/4
Dimensions (HxWxD) (in):	11-1/4 x 22-5/8 x 22-5/8	Condensate Connection (inch):	1-1/32
Panel (HxWxD) (in):	2 5/32 x 27 9/16 x 27 9/16	Sound Pressure (H/M/L/SL) (dBA):	37/35/33/31
Net Weight (lb):	39	Sound Power Level (dBA):	
Panel Weight (lb):	48	Ext. Static Pressure (Rated/Max) (inWg):	0.00 / 0.00

Submittal Data Sheet

1.5-Ton 2x2 Ceiling Cassette

FFQ18LVJU

DIMENSIONAL DRAWING

