


GENERAL NOTES FROM FINAL APPLICATION FIRE DEPARTMENT CHECKLIST:

- APPLICANT: Steven & Roberta Cope, 172 Concord St., Portland, ME 04103, 207-415-5833
- ARCHITECT: Kevin Moquin Architect, 207-615-6421, kevin@km-a.me
- USE: IBC=R-2 RESIDENTIAL; NFPA=APARTMENT BUILDING (6.1.8.1.5)
- CONSTRUCTION TYPE V-B, SPRINKLERED
- AREA, Proposed Renovation: 450 sf. Total Building: 4,130 sf. 3 stories
- OCCUPANT LOAD (TABLE 7.3.1.2): 450 sf. @ 200 SQ.FT. PER FOR APARTMENTS = 3 OCCUPANTS
- EMERGENCY LIGHTING NOT REQUIRED NFPA 101-30.2.9
- EXISTING SPRINKLER SYSTEM IS TYPE 13 R SYSTEM.
- EXISTING KNOX BOX LOCATED AT MAIN ENTRANCE.
- EXISTING SMOKE ALARMS ARE INTERCONNECTED SUCH THAT THE ACTIVATION OF ONE ALARM ACTIVATES ALL ALARMS IN THE INDIVIDUAL UNIT. SMOKE ALARMS RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WIRING AND ARE EQUIPPED WITH BATTERY BACKUP.



Kevin Moquin Architect
 Maine Licensed Architect
 Portland, ME
 www.km-a.me
 kevin@km-a.me | (207) 615-6421



58 Hammond
Efficiency
 Portland, ME
 1/15/2016

Life Safety Plan

A.03