

PROJECT OWNER
JTE
INVESTMENTS
16 SLED RUN RD.
N. YARMOUTH ME

General Contractor
GREEN LEAF
CONSTRUCTION
320 Penney Road
New Gloucester, ME

MOBILE FITNESS
PERSONAL TRAINING CENTER
50 COVE STREET

Drawings
BENTAMM
WENTLING
207 632 1827

10 MAY 2013

DEMO
PLAN

A1.0

NOTES

- Interior walls to be removed
- Electrician to leave ample whips to ensure ease of reuse / useful termination.
- Plumber to remove and discontinue plumbing to utility sink
- Fluorescent lighting to be removed in office overhead locations see A3.0 Ceiling Plan
- Walls to be repaired to new condition for completion
- Photos From A.0.2

