

Sequence of Operations

	Audio/visual activation at FACP	Activate audible/visual signal at FACP & Annunciator	Device Description at FACP	Log event in system history	Silence of audible devices including FACP & annunciator	Event acknowledgement	Reset of all system functions and all visual devices	Remote transmission to Central Station A=alarm; T=trouble; S=Supervisory; L = log only	Remote indicator
Manual Pull Station at FACP	X	X	X	X				A	
Smoke detector at FACP	X	X	X	X				A	
Sprinkler flow or pressure switches	X	X	X	X				A	
Sprinkler Tamper, low temp, or low air		X	X	X				S	
FACP/annunciator silence button		X	X	X	X			L	
FACP/annunciator acknowledge button		X	X	X		X			
FACP/annunciator reset button		X	X	X			X	L	
Removal of any device		X	X	X				T	
Ground fault		X	X	X				T	
System wiring "open"		X	X	X				T	
AC Power loss		X	X	X				T	
Secondary power loss		X	X	X				T	
Telephone line loss		X	X	X				T	