Attackment N.1



Preliminary Geotechnical Report

Munjoy Heights Development Walnut Street Portland, Maine

Prepared for:

Redfern Properties P.O. Box 8816 Portland, Maine 04104

Prepared by:

Summit Geoengineering Services, Inc. 640 Main Street Lewiston, Maine

> SGS #13067 July 2013

N.2



July 29, 2013 SGS #13067

Jonathan Culley Redfern Properties P.O. Box 8816 Portland, Maine 04104

Reference:

Preliminary Geotechnical Investigation, Munjoy Heights

Walnut Street, Portland, Maine

Dear Jonathan;

We have completed a preliminary geotechnical investigation for the proposed Munjoy Heights project. Our scope of services included excavating 5 test pits at the proposed site, and preparing this preliminary geotechnical letter summarizing our findings and general geotechnical recommendations.

Exploration and Testing

Summit observed the subsurface conditions at the site with the excavation of 5 test pits on May 23, 2013. The test pits were excavated to depths ranging from 7 to 14 fect, using a tracked excavator. The test pits were field located by SGS during the exploration based on identifiable site features. The location of the test pits is shown on Figure 1, Test Pit Location Plan. Logs of the test pits are also attached. The test pits are limited to the southeast half of the site. We originally planned to excavate test pits over the entire site; however, the test pits in the northern portion of the site were not completed due to the steep wooded topography and the necessity to limit disturbance.

Subsurface Conditions

The soil at the site generally consists of topsoil overlying a sand and gravel marine near shore deposit, overlying glacial till. A glacial marine layer (silt, sand, and clay) was encountered beneath the near shore deposit at TP-1, TP-3, and TP-5. A 2 foot layer of fill was observed at the surface at TP-2.

The topsoil ranged from 1 foot to 1.5 feet in thickness. It is described as dark brown sandy silt or silty sand with a trace of rootlets. This soil is moist and is classified as ML or SM in accordance with the USCS Classification System.

N.3

The fill, encountered in the upper 2 fect of soil profile at TP-2, is described as dark brown sandy silt with a trace of ash and rootlets. The fill contained glass fragments and pieces of metal; it was moist, loose, and is classified as ML.

The marine near shore deposit, encountered at all the test pit locations, is described as brown gravelly sand or brown sand with cobbles and boulders. This soil was compact and is visually classified as SP or SW in accordance with the USCS.

The glacial marine deposit, encountered beneath the marine near shore deposits at TP-1, TP-3, and TP-5, varies from brown silty fine sand to olive-brown fine sandy silt to olive-brown silty clay. The glacial marine layer was 1 to 4 feet thick and is classified as SM or ML in accordance with the USCS.

The glacial till was observed at TP-1 and TP-4. It is described as olive-brown to olive-gray sandy silt with a little clay and gravel. The glacial till is stiff and has a USCS classification of ML.

Groundwater was not observed in the test pits. No mottling was observed.

Bedrock was not encountered in the test pits.

Evaluation and Preliminary Recommendations

The existing ground surface at the site slopes relatively steeply toward the west. We anticipate that there will be significant cut on the east half of the site and a significant amount of fill placed to raise the existing grade on the west side of the site. Grading at the site will require the construction of retaining walls near both the east and west property lines.

Based on preliminary grading plans, the retaining walls required to support the proposed cut along the east property line, will be up to 25 feet high. We anticipate the following permissible OSHA excavation slopes.

OSHA Excavation Soil Classification			
Soil Type Permissible Slo			
Marine Near Shore and Fill	1.5H:1V		
Glacial Marine	1H:1V		
Glacial Till	0.75H:1V		

The excavations required to install many sections of the east retaining walls will disturb soil on the abutting properties. This disturbance will occur in many cases despite the type of wall system used. Options to install walls in these areas could include obtaining permission to disturb abutters properties, purchasing these properties or portions of these properties, or using a retaining system that does not require excavation to install, such as soldier pile and lagging or sheet piling. A secondary issue with this portion of the site is the potential presence of bedrock.

N.A

Test pits were not excavated in the area of the proposed retaining wall in the north portion of the site. It is possible at the proposed cut depths that bedrock could be encountered. The presence of bedrock would further limit the type of soil retention system possible for this area.

Retaining walls will be required to retain the fill, up to 23 feet, on the west side of the site. These walls will be constructed at the top of a steep slope (up to 4H:1V) in close proximity to existing houses. Based on this, a segmental type retaining wall with geogrid tiebacks is highly recommended for these walls. The geogrid will create a stable fill embankment for this condition. We recommend that final geotechnical analyses include a global stability for these walls.

In general, the soil at this site is suitable for support of the proposed building foundations. Proofrolling of the exposed footing subgrade soils will be required in cut areas and beneath the fill in built-up areas. For preliminary design, we recommend an allowable bearing pressure of 4,000 psf for footing constructed on the proofrolled native soil and compacted fill soil at this site. Some footings may be constructed at of near bedrock. Special preparation of the soil/bedrock subgrade in these areas will be required to minimize potential differential settlement.

Based on the test pits, we classify the soil at the site as Site Class D, Stiff Soil Profile. It is possible that the site could be reclassified as Site Class C at some locations. Reclassifying would require test boring explorations at the site to confirm.

Groundwater was not observed in the test pits. TP-1 was dry at a depth of 14 feet. Groundwater could be present, however, in areas where excavations exceed this depth.

The marine near shore deposits at the site are reusable as fill for most areas of the development. Reuse of the glacial marine and glacial till soil is also possible.

Closure

The preliminary recommendations above are based on professional judgment and generally accepted principles of geotechnical engineering. Some changes in subsurface conditions from those presented in this report may occur.

The development of building and site plans is on-going. Once final plans are available, SGS should be provided an opportunity to review them and prepare a final geotechnical report. The explorations at this site were limited. It may be desirable to obtain additional subsurface information in conjunction with our final report.

We appreciate the opportunity to serve you during this phase of your project. If there are any questions or additional information is required, please do not hesitate to call.

Sincerely yours,


Summit Geoengineering Services, Inc.

William M. Peterlein, P.E.

Principal Geotechnical Engineer



note - layout is not as pro-



1	VA. 1040			00		
Project:		TEST PIT LOG		Test Pit#	TP-1	
		Munjoy Heights		Project #:	13067	
		Walnut Street		Groundwater		
		Portland, Maine Surface Elevation		None o	bservec	
Contractor: Ground S Equipment: Large Tracked Excavator Reference						
Summit Staff: B. Peterlein, P.E. Date:			5/23/2013	Weather	: Overcast	
Depth	B. Fetereni, F.D.		RIPTION	Weather	. Overcast	
(ft)	ENGINEERING	DESC	1	OI OCIC	CENEDAL	W.
	Dark brown Silty SAND, trace rootlets, moist	loose	GEOLOGIC/GENERAL			<u>.</u>
1_	SM	i, 100se,	TOPSOIL			
2_	Brown Gravelly SAND, trace Cobbles, damp	, compact,				
3	SP		MARINE NEAR SHORE			
4_	Olive-brown fine Sandy SILT, damp, firm, M	IL		GLACIAL MARINE		
5_	Olive-brown Silty CLAY, moist, firm, CL					
6_						
7_	Brown Silty fine SAND, moist, compact, SM					
8_	Olive-gray Sandy SILT, little Clay and Gravel, moist, stiff, ML		GLACIAL TILL			
9_	Cobbles					
10_						
11_	Becomes gray at 10.5 ft					
12_						
13_						
14_	End of Test Pit at 14 feet					
15_	End of Test Pit at 14 feet					
16_						
17_						

	^^		TEST PIT LOG	Test Pit # TP-2	
SUMMIT			Munjoy Heights	Project #: 13067	
		Troject.	Walnut Street	Groundwater:	
GEOENGINEERING SERVICES		Portland, Maine	None observed		
		Surface Elevation			
Equipn		Referen			
Summi	t Staff: B. Peterlein, P.E.	Date:	5/23/2013 Weat	her: Overcast	
Depth		DESC	RIPTION		
(ft)	ENGINEERING		GEOLOG	IC/GENERAL	
	Dark brown Sandy SILT with trace of ash, rootlets,				
1_	glass, metal, moist, loose, ML		FILL		
2_					
3	Brown SAND, well graded, damp, compact	· SW	MADINE	NEAR SHORE	
	Thowards wen graced, damp, compact	., 0 11	WARINE	NEAR SHORE	
4					
-	Ī		Bag sample at 5 ft		
5_					
6_	,				
62247					
7_					
8					
°-	End of Test Pit at 8 ft				
9	End of Test Fit at 6 ft				
<u> </u>	1				
10					
-					
11_]				
12_	-				
1110					
13_	1				
14					
12.55	1				
¹⁵ _					
16_					
17_	_			ž.	

		Т .				
SUMMIT GEOENGINEERING SERVICES Project:			FEST PIT LO	UG	Test Pit#	TP-3
		Project:	: Munjoy Heights		Project #:	13067
		Walnut Street		Groundwat		
		Portland, Maine		None	observed	
Contractor: Ground S Equipment: Large Tracked Excavator Reference			Surface Elevation			
	t Staff: B. Peterlein, P.E.	Date:	5/23/2013	Weather	Overcast	
	I Stant. B. Feterichi, F.E.			w camer.	Overcast	
Depth (ft)		DESCI	RIPTION	~~ ~~~	.~	
(11)	ENGINEERING		GEOLOGIC/GENERAL			<u>L</u>
	Dark brown Sillty SAND, trace rootlets, moist, loose,		TOPSOIL			
1	SM					
2	Brown SAND, well graded, Cobbles and Bould	lers, moist	M	ARINE NEA	AR SHORE	
	compact, SW					
3	ence described was		Bag sample at 3 f	ì		
-	1			•		
4						
	Olive-gray Silty CLAY, moist, stiff, ML	-				
5	Olive gray diny CERT, moist, still, ME			GLACIAL I	MADINE	
~-			8	ULACIAL I	MAKINE	
_	OL 1 C C I CITE 14 C					
6_	Olive-brown fine Sandy SILT with fine sand se	eams				
7-00	(<1mm), damp, stiff, ML					
7_						
	End of Test Pit at 7 ft					
8						
9						
10						
11						
11	1					
10						
12_	1					
13_	-					
2,380.7						
14_						
15_						
16						
127/00/0						
17						
	1					
l						

	^^		TEST PIT LOG	Test Pit # TP-4	
			Munjoy Heights	Project #: 13067	
		Walnut Street	Groundwater:		
GEOENGINEERING SERVICES		Portland, Maine	None observed		
			Surface Elevation		
Equipn	nent: Large Tracked Excavator	e			
Summi	t Staff: B. Peterlein, P.E.	Date:	5/23/2013 Weath	er: Overcast	
Depth		DESCI	RIPTION		
(ft)	ENGINEERING		GEOLOGI	C/GENERAL	
	Dark brown Silty SAND, trace rootlets, moist,	loose,	TOPSOIL		
1_	SM				
2_	Brown Gravelly SAND, Cobbles and boulders,	Brown Gravelly SAND, Cobbles and boulders, damp,		IEAR SHORE	
3	compact, SW				
3_	-				
4_	ra i				
5_					
	Olive-brown Sandy SILT, trace Clay and Grave	el, damp,			
6	stiff, ML		GLACI	IAL TILL	
7					

8					
"-	-				
9					
- T	End of Test Pit at 9 ft				
10_					
11					
12_					
13_					
14_					
15					
¹⁶ _					
17_				155	

	^^	1 6	TEST PIT LOG	Test Pit # TP-5	
Project:			Munjoy Heights	Project #: 13067	
		Walnut Street	Groundwater:		
		Portland, Maine	None observed		
		Surface Elevation			
Equipment: Large Tracked Excavator Reference					
Summit Staff: B. Peterlein, P.E. Date: 5/23/2013 Weather: Overcast				her: Overcast	
Depth		DESCI	RIPTION	AND	
(ft)	ENGINEERING		GEOLOG	IC/GENERAL	
	Dark brown Silty SAND, trace rootlets, mo	ist, loose,	TOPSOIL		
1	SM				
2	Brown Gravelly SAND, Cobbles, damp, co	mpact, SW	MARINE 1	NEAR SHORE	
		1			
3					
<i>-</i>	İ		Grab sample at 3 ft		
4			Grao sample at 5 ft		
4					
8					
5					
6					
7	Olive-brown Sandy SILT, trace clay, damp,	, stiff, ML	GLACIAL MARINE		
8					
_	End of Test Pit at 8 ft				
9	Esta of Test That of I				
<i>,</i> —					
1.0					
10	ļ				
11					
12_					
5					
13	2		23		
_	1				
14					
	1				
15					
15_	1				
10					
¹⁶ _	1				
120					
17_	-				