


**NOTES:**


- THE EROSION CONTROL MIX SHALL CONFORM TO THE FOLLOWING STANDARDS AND IN ACCORDANCE WITH THE MAINE DEP'S EROSION AND SEDIMENT CONTROL BMP'S SECTION B-1:
  - THE ORGANIC PORTIONS SHALL BE FIBROUS AND ELONGATED TO ALLOW FOR THE INTERLOCKING OF MATERIAL.
  - pH - 5.0 - 8.0.
  - PARTICLE SIZE BY WEIGHT SHALL BE 100% PASSING A 6" SCREEN AND A MINIMUM OF 70% TO A MAXIMUM 85% PASSING A 0.75" (3/4") SCREEN.
  - THE ORGANIC MATTER CONTENT SHALL BE BETWEEN 80 AND 100% DRY WEIGHT BASIS.
  - NO STONES LARGER THAN 4" IN DIAMETER.
  - LARGE PORTIONS OF SILTS, CLAYS OR FINE SANDS ARE NOT ACCEPTABLE IN THE MIX.
- THE BERM SHOULD BE PLACED, UNCOMPACTED, ALONG A RELATIVELY LEVEL CONTOUR, WHEN NECESSARY THE BERM MAY BE PLACED PERPENDICULAR TO THE SLOPE ALONG THE PROPERTY LINE TO CONTAIN THE SEDIMENT PROVIDED A BERM IS LOCATED AT THE BASE OF THE SLOPE.
- THE BERM MAY BE USED IN LIEU OF SILTATION FENCE, AT THE TOE OF SHALLOW SLOPES, ON FROZEN GROUND, LEDGE OUT CROPS, VERY ROOTED FORESTED AREA OR AT THE EDGE OF GRAVEL PARKING AREAS.
- BERMS SHALL REMAIN IN PLACE UNTIL UPSTREAM AREA IS STABILIZED OR 90% CATCH OF VEGETATION IS ATTAINED. BERMS SHALL BE REMOVED OFFSITE OR BY SPREADING SUCH THAT NATIVE EARTH CAN BE SEEN BELOW.




**EROSION CONTROL MIX BERM DETAIL**  
NOT TO SCALE

**NOTES:**


- REFER TO THE REFER TO THE GRADING & DRAINAGE PLANS AND UTILITY PLANS FOR ADDITIONAL INFORMATION.




**CLEANOUT DETAIL**  
NOT TO SCALE



**EROSION CONTROL BLANKET CHANNEL INSTALLATION**  
NOT TO SCALE



**SOIL FILTER CROSS SECTION**



**SOIL FILTER SIDE VIEW**

- NOTES:**
- THE SIDESLOPES SHALL BE STABILIZED WITH A MIN. OF 4" LOAM, EROSION CONTROL BLANKETS SC150BN BY NORTH AMERICAN GREEN OR APPROVED EQUAL AND A CONSERVATION SEED MIX.
  - LIGHT COMPACTION SOIL FILTER AND PIPE BEDDING MATERIAL. (90 TO 92% STANDARD PROCTOR). TESTING SHALL BE PERFORMED BY A QUALIFIED MATERIAL TESTING FIRM.
  - THE SOIL FILTER MEDIA SHALL NOT BE CONSTRUCTED UNTIL THE AREA DRAINING TO THE BASIN HAS BEEN PERMANENTLY STABILIZED.
  - A LANDSCAPE DESIGNER OR ARCHITECT SHALL SELECT THE APPROPRIATE PLANTS FOR THE BIORETENTION CELL FOR THE SITE CONDITIONS. PLANTING PLAN BY OTHERS.
  - MINIMUM UNDERDRAIN SLOPE 0.0025.
  - TESTING: SIEVE ANALYSIS INCLUDING HYDROMETER TESTING FOR CLAY CONTENT FOR EACH LAYER SHALL BE PERFORMED BY A QUALIFIED SOIL TESTING LABORATORY AND SUBMITTED TO THE PROJECT ENGINEER FOR APPROVAL 2 WEEKS PRIOR TO CONSTRUCTION. ALL TESTING AND SUBMITTALS SHALL BE IN ACCORDANCE WITH THE MOST RECENT VERSION OF THE MAINE DEP - TECHNICAL DESIGN MANUAL SECTION 7.2.5 TESTING AND SUBMITTALS.
  - ACORN ENGINEERING, INC., RECOMMENDS THE SOIL FILTER LAYER BE SUPPLIED BY JONES ASSOCIATES, INC., AUBURN, ME.

ITEM	SCHEDULE	BIOCCELL
(A)	PROPOSED OVERFLOW RIM	111.06
(B)	TOP OF LOAM TOPSOIL LAYER	110.56
(C)	TOP OF SOIL FILTER	109.89
(D)	TOP OF GRAVEL	107.89
(E)	TOP OF STONE	107.39
(F)	BOTTOM OF STONE	106.39
(G)	UNDERDRAIN INVERT	106.72

SOIL FILTER BED - TRANSITION ZONE (TYPE B)		
SIEVE SIZE	% PASSING BY WEIGHT	
1"	90-100	
1/2"	75-100	
#4	50-100	
#20	15-80	
#50	0-15	
#200	0-5	

SOIL FILTER BED - UNDERDRAIN BEDDING (TYPE C)		
SIEVE SIZE	% PASSING BY WEIGHT	
1"	100	
3/4"	90-100	
3/8"	0-75	
#4	0-25	
#10	0-5	

6" LOAM TOPSOIL LAYER SPECIFICATION	
SIEVE SIZE	% PASSING BY WEIGHT
#4	75-95
#10	60-90
#40	35-85
#200	20-70

1. CLAY FRACTION <10% PASSING THE #200 SIEVE.\*

2. LOAM SHALL BE LOOSE AND FRIABLE AND SHALL BE FREE FROM ADMIXTURE OF SUBSOIL, REFUSE, LARGE STONES, CLOUDS OR ROOTS OR RHIZOMES OR "WITCH GRASS" OR OTHER UNDESIRABLE GRASSES.

\*10% CLAY PASSING THE #200 SIEVE ALLOWED PER EMAIL FROM MARIANNE HUBERT - MDEP TO WILL SAVAGE DATED 9/20/13

SOIL FILTER BED - SUPERHUMUS OR EQUIV. SPECIFICATION	
SIEVE SIZE	% PASSING BY WEIGHT
1"	100
#200	0-5


MINIMAL CLAY CONTENT, NO MORE THAN 3-5% PASSING #200 SIEVE

12" SOIL FILTER BED - BLENDED SAND, LOAM, SUPERHUMUS SIEVE ANALYSIS	
SIEVE SIZE	% PASSING BY WEIGHT
#10	85-100
#20	70-100
#60	15-40
#200	8-15

1. CLAY FRACTION <2% PASSING THE #200 SIEVE.

2. SUPERHUMUS OR EQUIVALENT


**RAIN GARDEN OR BIORETENTION CELL DETAIL**  
NOT TO SCALE



**SILTATION FENCE DETAIL**  
NOT TO SCALE

**CONSTRUCTION OBSERVATION:**

- CONSTRUCTION OBSERVATION SHALL BE PROVIDED FOR EACH PHASE OF CONSTRUCTION BY ACORN ENGINEERING. THE CONTRACTOR OR OWNERS REPRESENTATIVE SHALL NOTIFY ACORN ENGINEERING A MINIMUM 48 HOURS OR 2 BUSINESS DAY WHICH EVER IS GREATER PRIOR TO ANY OF THE PHASES OF CONSTRUCTION LISTED BELOW SO THAT THE FOLLOWING SITE VISITS MAY BE SCHEDULED.
- ONE SITE VISIT AFTER PRELIMINARY CONSTRUCTION OF THE BIORETENTION CELL GRADES;
  - ONE SITE VISIT DURING THE INSTALLATION OF THE IMPERVIOUS LINER.
  - ONE SITE VISIT AFTER THE UNDER DRAIN PIPES ARE INSTALLED BUT NOT BACKFILLED.
  - ONE SITE VISIT DURING THE CONSTRUCTION OF THE SOIL FILTER LAYER.
  - ONE SITE VISIT DURING THE CONSTRUCTION OF THE TOPSOIL LAYER.
  - ONE SITE VISIT DURING THE FLOODING OF THE BIORETENTION CELL, IF REQUIRED.



**EROSION CONTROL BLANKET SLOPE INSTALLATION**  
NOT TO SCALE

**CHANNEL INSTALLATION DETAIL**

- PREPARE SOIL BEFORE INSTALLING ROLLED EROSION CONTROL BLANKET (ECB), INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED.
- BEGIN AT THE TOP OF THE CHANNEL BY ANCHORING THE ECB IN A 6" (15CM) DEEP X 6" (15CM) WIDE TRENCH WITH APPROXIMATELY 12" (30CM) OF ECB EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. USE SHOREMAX MAT AT THE CHANNEL/CULVERT OUTLET AS SUPPLEMENTAL SCOUR PROTECTION AS NEEDED. ANCHOR THE ECB WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30CM) APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO THE COMPACTED SOIL AND FOLD THE REMAINING 12" (30CM) PORTION OF ECB BACK OVER THE SEED AND COMPACTED SOIL. SECURE ECB OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" APART ACROSS THE WIDTH OF THE ECB.
- ROLL CENTER ECB IN DIRECTION OF WATER FLOW IN BOTTOM OF CHANNEL. ECB WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL ECB MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE.
- PLACE CONSECUTIVE ECB END-OVER-END (SHINGLE STYLE) WITH A 4"-6" OVERLAP. USE A DOUBLE ROW OF STAPLES STAGGERED 4" APART AND 4" ON CENTER TO SECURE ECB. THE TOP LAYER SHALL GO OVER THE DOWNSTREAM LAYER.
- FULL LENGTH EDGE OF ECB AT TOP OF SIDE SLOPES MUST BE ANCHORED WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30CM) APART IN A 6" (15CM) DEEP X 6" (15CM) WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.
- ADJACENT ECB MUST BE OVERLAPPED APPROXIMATELY 2"-5" (5-12.5CM) (DEPENDING ON ECB TYPE) AND STAPLED.
- IN HIGH FLOW CHANNEL APPLICATIONS A STAPLE CHECK SLOT IS RECOMMENDED AT 30 TO 40 FOOT (9 - 12M) INTERVALS. USE A DOUBLE ROW OF STAPLES STAGGERED 4" (10CM) APART AND 4" (10CM) ON CENTER OVER ENTIRE WIDTH OF THE CHANNEL.
- THE TERMINAL END OF THE ECB MUST BE ANCHORED WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30CM) APART IN A 6" (15CM) DEEP X 6" (15CM) WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.

\*NOTE: IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" MAY BE NECESSARY TO PROPERLY SECURE THE ECB.

PERMIT DRAWINGS  
NOT FOR CONSTRUCTION

ISSUED FOR	BY
WORKSHOP #2	WHS
FINAL SUBMISSION	WHS
MAINE DEP MCGP	WHS

REVISION	REV	DATE
REV. STANDARD DETAIL	WHS	12/2/13
STAFF COMMENTS	WHS	12/16/13

DRAINAGE DETAILS - 2


MUNJOY HEIGHTS

REDFERN MUNJOY, LLC.  
P.O. BOX 8816, PORTLAND, MAINE 04104

DRAWING NAME: PROJECT NAME: CLIENT:

**ACORN ENGINEERING, INC.**  
ENGINEERING, INC.  
1000 W. BROAD ST., SUITE 200, PORTLAND, MAINE 04104  
P.O. BOX 3372, PORTLAND, MAINE 04104  
(207) 775-2655

DATE: 7/11/13  
JN: 302-001  
SCALE: NTS  
DESIGN BY: WHS  
DRAWN BY: ZRJ  
CHECKED BY: WHS



DRAWING NO. C-42