



ID	BOTANICAL NAME	COMMON NAME	QTY	SIZE
PROPOSED PLANT LIST				
DECIDUOUS TREES				
AC	ACER RUBRUM	RED MAPLE	27	8'-10'
AC	AMELANCHIER CANADENSIS	SERVICEBERRY (LEVIS)	17	8'
PA	PLATANUS X ACERIFOLIA	LONDON PLANETREE	22	12'-14'
QR	QUERCUS ROBUR X	CRIMSON SPIRE	1	TBD
SHRUBS				
AC	VACCINIUM ANGUSTIFOLIUM	LOWBUSH BLUEBERRY	120	2 GAL.
VC	VACCINIUM CORYMBOSUM	HIGHBUSH BLUEBERRY	78	5 GAL.
SV	SYRINGA VULGARE	LILAC	65	5 GAL.
MP	MYRICA PENNSYLVANICA	BAYBERRY	167	5 GAL.
IV	ILEX VERTICILLATA	WINTERBERRY	289	5 GAL.
CA	CLETHRA ALNIFOLIA	SUMMER SWEET	75	2 GAL.
HP	HYDRANGEA PANICULATA	HYDRANGEA 'TARDIVA'	TBD	5 GAL.
PERENNIALS / GRASSES / GROUND COVER 1,430 SF				
AU	ARCTOSTAPHYLOS UVA-URSI	BEARBERRY	500	3" POT
AC	DENNSTAEDTIA PUNCTILOBULA	HAYSCENTED FERN	315	3" POT
MS	MATTEUCCIA STRUTHIOPTERIS	OSTRICH FERN	TBD	1 GAL.
SS	SALVIA SYLVESTRIS	SAGE 'MAY NIGHT'	TBD	1 GAL.
CA	CALAMAGROSTIS ACUTIFLORA	KARL FOERSTER	TBD	1 GAL.
PT	PARTHENOCISSUS T.	BOSTON IVY	200	4" POT
IS	IRIS SIBERICA	SIBERIAN IRIS	50	1 GAL.
IS	CLEMATIS	CLEMATIS JACKMANII	6	1 GAL.
IS	ALLIUM GLADIATOR	ALLIUM	200	BULB
IS	TULIPA SP.	TULIP	600	BULB

SYMBOLS LEGEND

- Proposed Shrub (Detail 2, L3.0)
- Proposed Street Tree (Detail 3, L3.0)
- Native Seed Mix
- Perennial Plantings (Detail 1, L3.0)
- Unit Paving (geneste Chamberlin Stone or approved equivalent, see civil dwg.)
- Unit Paving (B. Pinehill Brick or approved equivalent, see civil dwg.)
- 3/8" Crushed Stone Surface
- Bench (Detail 2, L3.0)
- Brick end course flush to grade
- Steps
- Bicycle Parking
- Bollard Light (BEGA 8500LED)
- Pole Light (BEGA 8977LED)
- 36" Tall, 6" Diameter Galvanized Steel Bollard (Capped)

- PLANTING NOTES**
- All plant selection and installation will be in compliance with the City of Portland Technical Manual (Section 4).
 - No planting will be installed until all grading and construction has been completed in immediate area.
 - Contractor to verify all utilities on property and to protect all utilities during excavation for plants.
 - If there is a discrepancy between the number of plants shown on the plan and the number of plants shown in plant list, the number of plants shown on plan will take precedence.
 - All container material to be grown in container a minimum of 6 months.
 - All material shall comply with the latest edition of the American Standard for Nursery Stock, American Association of Nurseryman.
 - Contractor shall repair all damage to property from planting operations at no cost to the owner.
 - Contractor shall guarantee new plant material through one calendar year from time of provisional acceptance.
 - The Landscape Architect will tag all plants at the nursery and inspect them after delivery to the site. All plant materials shall be inspected by the Landscape Architect on site prior to installation.
 - All proposed plants shall be located carefully as shown on the plans and the placements shall be approved by Landscape Architect before the plants are installed.
 - All disturbed areas not to be paved or planted shall be loamed and seeded as shown. The seed mix specifications are as follows: LESCO Fine Fescue Links Blend of 35% hard fescue, 35% creeping red fescue, 20% chewings fescue and 10% sheep fescue. Add 5% Little Bluestem and 5% Northeast Wildflower seed mixture by weight to the Links Blend.
 - Staking and guying shall be determined by the Landscape Architect on a tree by tree basis. For pricing purposes, provide a per tree unit cost for staking and guying. If staking and guying is required, remove tree wrap, stakes, and guy wires at end of first growing season.
 - For tree planting in lawn areas, any disturbed lawn shall be loamed and seeded as necessary.
 - Landscape Architect to flag trees to be protected on site.

- IRRIGATION NOTES**
- AUTOMATIC IRRIGATION SYSTEM WITH SMART CONTROLLER TO BE PROVIDED FOR ALL SHRUB AND TREE PLANTINGS, GROUNDCOVERS, PERENNIAL BEDS AND LAWN AREAS.
 - PROVIDE DRIP SYSTEM FOR SHRUB AND PERENNIAL BEDS.
 - PROVIDE 2 BUBBLERS PER TREE.
 - CONTRACTOR TO PROVIDE SHOP DRAWINGS SHOWING ALL EQUIPMENT SUCH AS SPRAY HEADS, DRIP LINES, PIPING, VALVES, ETC. AND CATALOGUE CUTS FOR APPROVAL. INDICATE COVERAGE DIAMETER FOR ALL SPRAY HEADS.
 - CONTRACTOR TO COORDINATE WITH ARCHITECT AND LANDSCAPE ARCHITECT ON LOCATION OF CONTROLLER
 - ALL VALVE BOXES TO BE SET PERPENDICULAR OR PARALLEL TO CLOSEST EDGE OF BUILT STRUCTURE. COORDINATE LOCATIONS WITH LANDSCAPE ARCHITECT.

Munjoy Heights
 Walnut Street
 Portland Maine

PERMIT SET
 NOT FOR CONSTRUCTION

Revisions:
 date: December 13, 2013
 scale: As Noted
 drawn: SD
 checked: SD

