



PILE CAP SCHEDULE			
CAP No.	No. OF PILES	DIMENSIONS	REINFORCING
PC1	3	7'-4\"/>	

**FOUNDATION PLAN**  
 SCALE 1/8"=1'-0"  
 NOTES:  
 1. SEE SHEET S1.0 FOR GENERAL STRUCTURAL NOTES  
 2. ALL FOOTINGS UNDER WALLS ARE 10" DEEP x 2'-6" WIDE x CONT. WITH (4) #4 BARS LONGITUDINAL -TYP. UNO  
 3. STEP IN TOP OF FOUNDATION WALLS IS INDICATED THUS:  $\nabla$ , AND SHOWS LOWER SIDE OF WALL  
 4. TOP OF FOOTING, TOP OF PILE CAP, BOTTOM OF GRADE BEAM 4'-0" BELOW GRADE, MIN. AND IS INDICATED THUS: (XX-XX")  
 5. STEP IN TOP OF FOOTING, BOTTOM OF GRADE BEAM IS INDICATED THUS:  $\nabla$  AND SHOWS LOWER FOOTING  
 6. TOP OF WALL ELEV.=100'-2", UNLESS INDICATED THUS: T.W.=XXX'-XXX"  
 7. 4" THICK CONCRETE SLAB IS EXPOSED IN SOME AREAS AND SHALL BE GROUND AND POLISHED PER ARCH.  
 8. REFERENCE ELEVATION 100'-0" = USGS ELEVATION 11.9'  
 9. TOP OF PILE CAP ELEV.=98'-0", UNLESS INDICATED THUS: (XXX'-XXX")

**FOR PERMIT**  
**MAY 27, 2015**

**STATE OF MAINE**  
**AARON C. JONES**  
 No. 10988  
 LICENSED PROFESSIONAL ENGINEER  
 May 27th, 2015

**Structural Integrity**  
 Consulting Engineers, Inc.  
 77 Oak Street  
 Portland, ME 04101  
 p. 207-774-4614  
 f. 866-793-7835  
 www.structuralintegrity.com

**FOUNDATION PLAN**