
# EAST BAYSIDE LOFTS

REDFERN BAYSIDE, LLC 89 ANDERSON STREET PORTLAND, MAINE

## **LEGEND:**



CALL BEFORE YOU DIG 1-888-DIG-SAFE -888 - 344 - 7233

SITE DETAILS - 1

SITE DETAILS - 2

DRAINAGE DETAILS

EROSION CONTROL DETAILS & NOTES

UTILITY DETAILS

C - 43

## **UTILITIES**

## PROJECT TEAM

# **SEWER:**

PUBLIC SERVICES ENGINEERING DEPARTMENT 55 PORTLAND STREET PORTLAND, MAINE 04101 CONTACT: DAVID MARGOLIS-PINEO (207) 874-8850

PORTLAND WATER DISTRICT 225 DOUGLAS STREET PO BOX 3553 PORTLAND, MAINE 04104 ATTN: GORDON JOHNSON, P.E. (207)-761-8310

**WATER:** 

## **ELECTRIC**:

CENTRAL MAINE POWER COMPANY (CMP) 162 CANCO ROAD PORTLAND, MAINE 04103 CONTACT: JAMIE COUGH (207) 842-2367

## **TELEPHONE:**

FAIRPOINT COMMUNICATIONS 45 FOREST AVE PORTLAND MAINE 04101 CONTACT: JOHN CAPRIO (207) 797-1842

## CABLE:

TIME WARNER CABLE 118 JOHNSON ROAD PORTLAND, MAINE, 04102 CONTACT: MARK PELLETIER (877) 546-0962

# NATURAL GAS:

UNITIL SERVICE CORP ATTN: KELLY FOWLER 1075 FOREST AVENUE PORTLAND, ME 04103 (207) 541-2536

## **DEVELOPER:**

REDFERN BAYSIDE, LLC PORTLAND, MAINE CONTACT: JONATHAN CULLEY (207) 776-9715

## **ARCHITECT:**

RYAN SENATORE ARCHITECTURE PORTLAND, MAINE CONTACT: RYAN SENATORE, AIA LEED-AP BD+C MAINE LICENSED ARCHITECT (207) 650 - 6414

## **SURVEYOR:**

NADEAU LAND SURVEYS PORTLAND, MAINE CONTACT: JAMES NADEAU, PLS (207) 878-7870

## LANDSCAPE DESIGNER:

SOREN DENIORD DESIGN STUDIO PORTLAND MAINE CONTACT: SOREN DENIORD (207) 400-2450

# **GEOTECHNICAL ENGINEER:**

SUMMIT GEOENGINEERING SERVICES, INC. LEWISTON, MAINE CONTACT: BILL PETERLEIN, P.E. (207) 576-3313

## STRUCTURAL ENGINEER:

STRUCTURAL INTEGRITY CONSULTING ENGINEERS, INC. PORTLAND, MAINE CONTACT: AARON JONES, P.E. (207) 774-4614

## CONSTRUCTION MANAGEMENT CO .:

ALLIEDCOOK CONSTRUCTION SCARBOROUGH, MAINE CONTACT: MATTHEW COOK, LEED AP (207) 772-2888

# TRAFFIC ENGINEER:

TRAFFIC SOLUTIONS PORTLAND, MAINE CONTACT: BILL BRAY, P.E. (207) 774-3603

## 

ABBREVIATIONS  PARTIAL LIST OF ABBREVIATIONS AND THEIR CORRESPONDING MEANING. PLEASE CONTACT THE ENGINEER FOR ANY CLARIFICATION		
BC	BOTTOM OF CURB	
ВМР	BEST MANAGEMENT PRACTICE	
вот.	воттом	
СВ	CATCH BASIN	
CF	CUBIC FOOT	
CIP	CAST IN PLACE	
CM	CONSTRUCTION MANAGER	
CONC.	CONCRETE	
CUBIC YARD	CY	
DIA.	DIAMETER	
DIM.	DIMENSION	
EA.	EACH	
ELEC.	ELECTRICAL	
ELEV.	ELEVATION	
EQUIV.	EQUIVALENT	
EST.	ESTIMATE	
EX.	EXISTING	
FFE	FINISH FLOOR ELEVATION	
FT.	FEET	
GAL.	GALVANIZED	
ID	INNER DIAMETER	
IN.	INCH	
INV.	INVERT	
L	LENGTH	
MAX.	MAXIMUM	
MDOT	MAINE DEPARTMENT OF	
	TRANSPORTATION	
MFG.	TRANSPORTATION  MANUFACTURED	
MFG.		
5.	MANUFACTURED	
МН	MANUFACTURED  MANHOLE	
MH MIN.	MANUFACTURED  MANHOLE  MINIMUM	
MH MIN. OD	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD	
MH MIN. OD OHE/T/C	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE	
MH MIN. OD OHE/T/C PC	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST	
MH MIN. OD OHE/T/C PC PE	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER	
MH MIN. OD OHE/T/C PC PE PE PL	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE	
MH MIN. OD OHE/T/C  PC PE PL PLS	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE  PROFESSIONAL LAND SURVEYOR	
MH MIN. OD OHE/T/C  PC PE PL PLS PROP. PSI	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE  PROFESSIONAL LAND SURVEYOR  PROPOSED  POUNDS PER SQUARE INCH	
MH MIN. OD OHE/T/C  PC PE PL PLS PROP. PSI PVC	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE  PROFESSIONAL LAND SURVEYOR  PROPOSED  POUNDS PER SQUARE INCH POLYVINYL CHLORIDE	
MH MIN. OD OHE/T/C  PC PE PL PLS PROP. PSI PVC R	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE  PROFESSIONAL LAND SURVEYOR  PROPOSED  POUNDS PER SQUARE INCH  POLYVINYL CHLORIDE  RADIUS	
MH MIN.  OD OHE/T/C  PC PE PL PLS PROP. PSI PVC R RD	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE  PROFESSIONAL LAND SURVEYOR  PROPOSED  POUNDS PER SQUARE INCH POLYVINYL CHLORIDE  RADIUS  ROOF DRAIN	
MH MIN.  OD OHE/T/C  PC PE PL PLS  PROP. PSI PVC R RD RET.	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE  PROFESSIONAL LAND SURVEYOR  PROPOSED  POUNDS PER SQUARE INCH  POLYVINYL CHLORIDE  RADIUS  ROOF DRAIN  RETAINING	
MH MIN. OD OHE/T/C  PC PE PL PLS PROP. PSI PVC R R RD RET. ROW	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE  PROFESSIONAL LAND SURVEYOR  PROPOSED  POUNDS PER SQUARE INCH POLYVINYL CHLORIDE  RADIUS  ROOF DRAIN  RETAINING  RIGHT OF WAY	
MH MIN.  OD OHE/T/C  PC PE PL PLS  PROP. PSI PVC R RD RET.	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE  PROFESSIONAL LAND SURVEYOR  PROPOSED  POUNDS PER SQUARE INCH  POLYVINYL CHLORIDE  RADIUS  ROOF DRAIN  RETAINING  RIGHT OF WAY  SLOPE	
MH MIN. OD OHE/T/C  PC PE PL PLS PROP. PSI PVC R R RD RET. ROW	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE  PROFESSIONAL LAND SURVEYOR  PROPOSED  POUNDS PER SQUARE INCH POLYVINYL CHLORIDE  RADIUS  ROOF DRAIN  RETAINING  RIGHT OF WAY	
MH MIN. OD OHE/T/C  PC PE PL PLS PROP. PSI PVC R RD RET. ROW S	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE  PROFESSIONAL LAND SURVEYOR  PROPOSED  POUNDS PER SQUARE INCH  POLYVINYL CHLORIDE  RADIUS  ROOF DRAIN  RETAINING  RIGHT OF WAY  SLOPE	
MH MIN.  OD OHE/T/C  PC PE PL PLS PROP. PSI PVC R R RD RET. ROW S SD	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE  PROFESSIONAL LAND SURVEYOR  PROPOSED  POUNDS PER SQUARE INCH POLYVINYL CHLORIDE  RADIUS  ROOF DRAIN  RETAINING  RIGHT OF WAY  SLOPE  STORM DRAIN	
MH MIN.  OD OHE/T/C  PC PE PL PLS  PROP. PSI PVC R RD RET. ROW S SD SDR	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE  PROFESSIONAL LAND SURVEYOR  PROPOSED  POUNDS PER SQUARE INCH  POLYVINYL CHLORIDE  RADIUS  ROOF DRAIN  RETAINING  RIGHT OF WAY  SLOPE  STORM DRAIN  STANDARD DIMENSION RATIO	
MH MIN. OD OHE/T/C  PC PE PE PL PLS  PROP. PSI PVC R R RD RET. ROW S SD SDR SDR	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE  PROFESSIONAL LAND SURVEYOR  PROPOSED  POUNDS PER SQUARE INCH  POLYVINYL CHLORIDE  RADIUS  ROOF DRAIN  RETAINING  RIGHT OF WAY  SLOPE  STORM DRAIN  STANDARD DIMENSION RATIO  SQUARE FEET	
MH MIN.  OD OHE/T/C  PC PE PL PLS PROP. PSI PVC R R RD RET. ROW S SD SDR SF SMH	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE  PROFESSIONAL LAND SURVEYOR  PROPOSED  POUNDS PER SQUARE INCH  POLYVINYL CHLORIDE  RADIUS  ROOF DRAIN  RETAINING  RIGHT OF WAY  SLOPE  STORM DRAIN  STANDARD DIMENSION RATIO  SQUARE FEET  SEWER MANHOLE	
MH MIN.  OD OHE/T/C  PC PE PL PLS PROP. PSI PVC R RD RET. ROW S SD SDR SDR SF SMH SPEC. TC	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE  PROFESSIONAL LAND SURVEYOR  PROPOSED  POUNDS PER SQUARE INCH  POLYVINYL CHLORIDE  RADIUS  ROOF DRAIN  RETAINING  RIGHT OF WAY  SLOPE  STORM DRAIN  STANDARD DIMENSION RATIO  SQUARE FEET  SEWER MANHOLE  SPECIFICATION  TOP OF CURB	
MH MIN.  OD OHE/T/C  PC PE PL PLS PROP. PSI PVC R RD RET. ROW S SD SDR SF SMH SPEC. TC TW	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE  PROFESSIONAL LAND SURVEYOR  PROPOSED  POUNDS PER SQUARE INCH  POLYVINYL CHLORIDE  RADIUS  ROOF DRAIN  RETAINING  RIGHT OF WAY  SLOPE  STORM DRAIN  STANDARD DIMENSION RATIO  SQUARE FEET  SEWER MANHOLE  SPECIFICATION  TOP OF CURB  TOP OF WALL	
MH MIN. OD OHE/T/C  PC PE PL PLS PROP. PSI PVC R R RD RET. ROW S SD SDR SF SMH SPEC. TC TW TYP.	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE  PROFESSIONAL LAND SURVEYOR  PROPOSED  POUNDS PER SQUARE INCH  POLYVINYL CHLORIDE  RADIUS  ROOF DRAIN  RETAINING  RIGHT OF WAY  SLOPE  STORM DRAIN  STANDARD DIMENSION RATIO  SQUARE FEET  SEWER MANHOLE  SPECIFICATION  TOP OF CURB  TOP OF WALL  TYPICAL	
MH MIN.  OD OHE/T/C  PC PE PL PLS PROP. PSI PVC R RD RET. ROW S SD SDR SF SMH SPEC. TC TW	MANUFACTURED  MANHOLE  MINIMUM  OUTSIDE DIAMETER  OVERHEAD ELECTRIC/TELEPHONE/CABLE  PRECAST  PROFESSIONAL ENGINEER  PROPERTY LINE  PROFESSIONAL LAND SURVEYOR  PROPOSED  POUNDS PER SQUARE INCH  POLYVINYL CHLORIDE  RADIUS  ROOF DRAIN  RETAINING  RIGHT OF WAY  SLOPE  STORM DRAIN  STANDARD DIMENSION RATIO  SQUARE FEET  SEWER MANHOLE  SPECIFICATION  TOP OF CURB  TOP OF WALL	

CONSTRUCTION DRAWINGS

UTILITY STUB COMMENT RESPONS PRICING SET CONSTRUCTION REVISION LOFTS **DETAILS** SITE **EAST** 1053\_DETAILS 12/5/201 SCALE: DESIGNED BY: DRAWN BY: CHECKED BY:

ISSUED FOR

PRELIMINARY S

DRAWING NO C-01

## GENERAL NOTES:

- 1. THE CONTRACTOR SHALL CALL THE APPROPRIATE UTILITY COMPANIES AND DIG SAFE AT LEAST 4 DAYS PRIOR TO ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION FOR UTILITIES. OTHERWISE IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY THE LOCATION OF UNDERGROUND UTILITIES AND LOCATE ANY POTENTIAL CONFLICTS WITH THE APPROVED PLANS PRIOR TO CONSTRUCTION.
- 2. THE CONTRACTOR IS RESPONSIBLE FOR MAINTENANCE OF ALL EROSION CONTROL MEASURES SHOWN ON THE PLAN. IF DEEMED NECESSARY BY THE OWNER OR OWNER'S REPRESENTATIVE, ADDITIONAL EROSION CONTROL MEASURES SHALL BE INSTALLED AT NO ADDITIONAL COST TO THE OWNER.
- 3. THE CONTRACTOR SHALL PREPARE THEIR OWN MATERIAL SCHEDULE BASED ON THE PLANS AND FIELD VERIFICATION BY THE CONTRACTOR. ALL MATERIAL SCHEDULES SHOWN WITHIN THE PLAN SET ARE FOR GENERAL INFORMATION ONLY.
- 4. ALL CONSTRUCTION METHODS, TESTING AND MATERIALS SHALL CONFORM TO THE MAINE DEPARTMENT OF TRANSPORTATION SPECIFICATIONS, THE CITY OF PORTLAND AND SERVICING UTILITY REQUIREMENTS, IF ANY. IN CASES WHERE THESE CONFLICT

THE MOST STRINGENT SPECIFICATION SHALL APPLY AT NO ADDITIONAL COST TO THE OWNER.

- 5. THE SITE CONTRACTOR SHALL MAINTAIN A SET OF DRAWINGS WHICH SHALL RECORD THE ACTUAL LOCATION, DIMENSIONS, ELEVATIONS, MATERIALS OF THEIR WORK, INDICATING THEREON ALL VARIATIONS FROM THE CONTRACT DRAWINGS. THE CONTRACTOR SHALL PROVIDE THE OWNER WITH ONE COMPLETE SET OF REPRODUCIBLE RECORD DRAWINGS STAMPED "AS-BUILT".
- 6. THE CONTRACTOR WILL REMAIN SOLELY AND COMPLETELY RESPONSIBLE FOR ENFORCEMENT OF AND COMPLIANCE WITH 1) ALL CONTRACT PLANS AND SPECIFICATIONS, 2) APPLICABLE INTERNATIONAL BUILDING CODE REQUIREMENTS, AND 3) ALL SITE WORKING CONDITIONS AND SAFETY REQUIREMENTS, DAY AND NIGHT, FOR BOTH PERSONS AND PROPERTY, IN EACH CASE BOTH BY THE CONTRACTOR AND ITS SUBCONTRACTORS. THESE INCLUDE ALL OSHA, NIOSH, U.S. EPA AND ANY OTHER APPLICABLE GOVERNMENTAL REGULATIONS.
- 7. EXISTING CONDITIONS, BOUNDARY SURVEY AND TOPOGRAPHIC FROM THE PLAN TITLED EXISTING CONDITIONS SURVEY BY NADEAU LAND SURVEYS FOR REDFERN PROPERTIES, DATED 3/30/15.
- 8. SUBSURFACE DATA HAVE BEEN OBTAINED BY SUMMIT GEOENGINEERING SERVICES, INC. AND SHALL BE INCLUDED IN THE CONTRACT DOCUMENTS.
- 9. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING ACCESS TO THE SITE AND ALL ADJACENT PROPERTIES AT ALL TIMES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY MARKINGS, SIGNAGE AND INCIDENTALS TO MAINTAIN A SAFE VEHICLE AND PEDESTRIAN ACCESS THOUGH THE LIFE OF THE PROJECT. THE CONTRACTOR SHALL NOTIFY THE PORTLAND PUBLIC SAFETY DIVISION ROUTINELY REGARDING TEMPORARY IMPACTS OR CHANGES TO SITE ACCESS CONDITIONS.
- 10. CONSTRUCTION MANAGEMENT PLAN BY THE ALLIEDCOOK CONSTRUCTION CO. SHALL BE REFERRED TO FOR ANTICIPATED PROJECT SCHEDULE AND CLOSURES. TRAFFIC CONTROL SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
- 11. CONTRACTOR TO DETERMINE SOIL CLASSIFICATION INDEPENDENTLY FOR TRENCH, SHORING, AND OTHER SIMILAR CONSTRUCTION MEANS AND METHODS APPLICATIONS.
- 12. THE CONTRACTOR SHALL CONDUCT A PRE-CONSTRUCTION SURVEY OF INTERIOR SUBGRADE AND ABOVE GRADE ACCESSIBLE WALLS, CEILINGS, FLOORS, ROOF AND VISIBLE EXTERIOR AS VIEWED FROM THE GRADE LEVEL. THIS SHALL BE COMPLETED AT A MINIMUM FOR THE GREENLEAF APARTMENTS AND STRONGLY RECOMMENDED FOR STRUCTURES DIRECTLY ACROSS THE SITE ALONG EVERETT ST., ANDERSON ST. AND FOX. ST. A COPY OF THE SURVEY SHOULD BE PROVIDED TO THE OWNER.

## CIVIL SITE NOTES:

- 1. THE CONTRACTOR SHALL SUBMIT IN WRITING ANY REQUESTS TO MODIFY THE CONTRACT DOCUMENTS.
- 2. ALL SHOP AND ERECTION DRAWINGS SHALL BE CHECKED AND STAMPED BY THE GENERAL CONTRACTOR PRIOR TO SUBMISSION FOR ENGINEER'S REVIEW. ANY UNCHECKED OR NON-STAMPED SUBMITTALS WILL BE RETURNED WITHOUT REVIEW.
- 3. CONTRACTOR SHALL THOROUGHLY INSPECT AND SURVEY EXISTING STRUCTURES AND SITE TO VERIFY CONDITIONS THAT AFFECT THE WORK SHOWN ON THE DRAWINGS. CONTRACTOR TO NOTIFY THE ENGINEER OF ANY DISCREPANCIES PRIOR TO PROCEEDING.
- 4. DETAILS SHOWN APPLY TO ALL SIMILAR CONDITIONS UNLESS OTHERWISE INDICATED.
- 5. ALTHOUGH ALL DUE DILIGENCE HAS BEEN APPLIED TO MAKE THE DRAWINGS AS COMPLETE AS POSSIBLE, NOT ALL DETAILS ARE ILLUSTRATED, NOT IS EVERY EXCEPTION CONDITION ADDRESSED WITHIN THE CONTRACT DOCUMENTS.
- 6. ALL PROPRIETARY CONNECTIONS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

VERIFICATION, MATERIALS COORDINATION, SHOP DRAWING REVIEW, AND THE WORK OF ANY SUBCONTRACTORS.

- 7. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR THE COORDINATION OF ALL WORK, INCLUDING DIMENSION AND LAYOUT
- 8. UNLESS OTHERWISE SPECIFICALLY INDICATED, THE DRAWINGS DO NOT DESCRIBE OR DIRECT MEANS OR METHODS OF CONSTRUCTION.
- 9. THE CONTRACTOR, IN THE PROPER SEQUENCE, SHALL PERFORM OR SUPERVISE ALL WORK NECESSARY TO ACHIEVE THE FINAL COMPLETED STRUCTURE, AND TO PROTECT THE STRUCTURE, WORKMEN, AND OTHERS DURING THE CONSTRUCTION. SUCH WORK SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, SHORING FOR CONSTRUCTION EQUIPMENT, SHORING FOR EXCAVATION, FORMWORK, SCAFFOLDING, SAFETY DEVICES AND PROGRAMS OF ALL KINDS, SUPPORT AND BRACING FOR CRANES AND OTHER ERECTION EQUIPMENT.
- 10. DO NOT BACKFILL AGAINST RETAINING WALLS UNTIL SUPPORTING SLABS AND FLOOR FRAMING ARE IN PLACE AND SECURELY ANCHORED, UNLESS ADEQUATE BRACING IS PROVIDED.
- 11. TEMPORARY BRACING SHALL REMAIN IN PLACE UNTIL ALL FLOORS, WALLS, ROOFS AND OTHER SUPPORTING ELEMENTS ARE IN PLACE.
- 12. THE ENGINEER BEARS NO RESPONSIBILITY FOR THE ABOVE ITEMS, AND OBSERVATION VISITS TO THE SITE DO NOT IN ANY WAY INCLUDE INSPECTION OF THEM.

## SPECIAL INSPECTION NOTES:

- 1. ALL SITE SOILS—RELATED WORK AND FOOTING EXCAVATIONS PRIOR TO PLACING FORMS, AS WELL AS SITE DRAINAGE, SHALL BE REVIEWED BY THE PROJECT GEOTECHNICAL ENGINEER.
- 2. NORMAL REVIEWS BY LOCAL BUILDING DEPARTMENT.
- 3. NOTIFY 48 HOURS PRIOR TO REQUIRED REVIEW.
- 4. REQUIRED SPECIAL INSPECTIONS PER I.B.C. SECTION 1705.6 BY AN APPROVED SPECIAL INSPECTOR RETAINED BY OWNER. CONTRACTOR TO COORDINATE SPECIAL INSPECTIONS.
- 5. SPECIAL INSPECTOR SHALL BE A QUALIFIED PERSON WHO SHALL DEMONSTRATE COMPETENCE, TO THE SATISFACTION OF THE BUILDING OFFICIAL, FOR INSPECTION OF THE PARTICULAR TYPE OF CONSTRUCTION OR OPERATION REQUIRING SPECIAL INSPECTION.
- 6. DUTIES AND RESPONSIBILITIES OF THE SPECIAL INSPECTOR SHALL BE TO OBSERVE AND/OR TEST THE WORK ASSIGNED AND OUTLINE ABOVE FOR CONFORMANCE WITH THE CONTRACT DOCUMENTS, ALL DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTOR FOR CORRECTION.
- 7. THE SPECIAL INSPECTOR SHALL FURNISH REGULAR REPORTS TO THE BUILDING OFFICIAL, THE ARCHITECT AND ENGINEER OF RECORD, AND OTHER DESIGNATED PERSONS. PROGRESS REPORTS FOR CONTINUOUS INSPECTION SHALL BE FURNISHED WEEKLY. INDIVIDUAL REPORTS OF PERIODIC INSPECTIONS SHALL BE FURNISHED WITHIN ONE WEEK OF INSPECTION DATES. THE REPORTS SHALL NOTE UNCORRECTED DEFICIENCIES, AND NET CHANGES TO THE APPROVED CONSTRUCTION DOCUMENTS AUTHORIZED BY THE ENGINEER OF RECORD.
- 8. THE SPECIAL INSPECTOR SHALL SUBMIT A FINAL SIGNED REPORT WITHIN TEN DAYS OF THE FINAL INSPECTION STATING WHETHER THE WORK REQUIRING A SPECIAL INSPECTION WAS, TO THE BEST OF THE INSPECTOR'S KNOWLEDGE AND BELIEF, IN CONFORMANCE WITH THE APPROVED CONSTRUCTION DOCUMENTS AND THE APPLICABLE WORKMANSHIP PROVISIONS OF THE INTERNATIONAL BUILDING CODE. WORK NOT IN COMPLIANCE SHALL BE NOTED IN THE REPORT.
- 9. SPECIAL INSPECTION FIRM SHALL BE EMPLOYED BY REDFERN AND COORDINATED BY THE CONTRACTOR.

## LAYOUT NOTES:

- 1. MONUMENTS DELINEATING PROPERTY LINES OR RIGHT OF WAYS SHALL NOT BE DISTURBED DURING CONSTRUCTION OPERATIONS. IN THE CASE A MONUMENT IS DISTURBED, AT THE CONTRACTOR'S EXPENSE, THE MONUMENT SHALL BE RESET TO THEIR ORIGINAL LOCATION BY A REGISTERED LAND SURVEYOR.
- 2. ALL DIMENSIONS ON THE FOLLOWING SHEETS TAKE PRECEDENT OVER SCALED DIMENSIONS. EACH DRAWING WITH A BAR SCALE MEANS THAT THE DRAWING/DETAIL HAS BEEN SCALED AS ACCURATELY AS POSSIBLE, AND THE BAR SCALE IS FOR GENERAL REFERENCE ONLY. IF NO BAR SCALE IS PRESENT, THEN THERE IS NO SCALE TO THAT DRAWING/DETAIL. AT NO TIME SHOULD DRAWINGS BE SCALED FROM. ANY DISCREPANCIES BETWEEN DRAWINGS, DETAILS, SPECIFICATIONS AND THE FIELD CONDITION SHALL BE IMMEDIATELY REPORTED TO THE CIVIL ENGINEER FOR FURTHER DIRECTIONS BEFORE ANY ADDITIONAL WORK
- 3. SIGNAGE, STRIPING AND PAVEMENT MARKINGS SHALL BE IN ACCORDANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).
- 4. ALL TRAFFIC CONTROL SIGNS INDICATED ON THE SITE LAYOUT PLAN ARE TO MEET ALL REQUIREMENTS & CONDITIONS OF THE CITY OF PORTLAND, MAINE DEPARTMENT OF TRANSPORTATION AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, LATEST EDITION.
- 5. THE CONTRACTOR SHALL OBTAIN THE SERVICES OF A LICENSED PROFESSIONAL LAND SURVEYOR TO PROVIDE A MINIMUM OF TWO TEMPORARY BENCHMARKS WITHIN THE SITE.
- 6. CONTRACTOR TO ENSURE THAT DRIVEWAYS AND MAILBOXES ADJACENT TO THE PROJECT REMAIN FUNCTIONAL AND IN USE AT ALL TIMES.

### PERMITTING NOTES

- 1. THIS PROJECT IS SUBJECT TO THE TERMS AND CONDITIONS OF SITE PLAN LEVEL III AND SUBDIVISION PERMIT FROM THE CITY OF PORTLAND.
- 2. THE CONTRACTOR SHALL REVIEW THE ABOVE REFERENCED PERMITS PRIOR TO SUBMITTING A BID FOR THIS PROJECT, AND INCLUDE COSTS AS NECESSARY TO COMPLY WITH THE CONDITIONS OF THESE PERMITS.

## GRADING AND DRAINAGE NOTES:

- 1. TOPSOIL STRIPPED FROM THE SITE THAT IS SUITABLE FOR REUSE AS LOAM SHALL BE STOCKPILED WITHIN THE PROPOSED LIMIT OF WORK AREA. THE CONTRACTOR SHALL NOT ASSUME THAT ANY LOAM WILL BE ACCEPTABLE FOR REUSE WITH THEIR ESTIMATE.
- 2. THE CONTRACTOR SHALL ANTICIPATE THAT GROUNDWATER WILL BE ENCOUNTERED DURING CONSTRUCTION AND SHALL INCLUDE SUFFICIENT COSTS WITHIN THEIR BID TO PROVIDE DEWATERING AS NECESSARY; NO SEPARATE PAYMENT SHALL BE MADE TO THE CONTRACTOR FOR DEWATERING. SEE BORING LOGS FOR ADDITIONAL INFORMATION.
- 3. THE OWNER SHALL BE RESPONSIBLE FOR OBTAINING ANY EASEMENT OR TEMPORARY CONSTRUCTION RIGHTS AS NECESSARY BY PRIVATE ADJACENT LAND OWNERS. THE CONTRACTOR SHALL NOT DISTURB ANY SOIL BEYOND THE PROPERTY LINE WITHOUT NOTIFYING AND OBTAINING SUCH EASEMENT OR TEMPORARY CONSTRUCTION RIGHT FROM THE OWNER. PRIOR TO THE CONTRACTOR PRICING THE WORK THE CONTRACTOR SHALL REQUEST PROOF OF SUCH EASEMENT OR TEMPORARY RIGHTS. SHOULD EASEMENTS OR TEMPORARY RIGHTS NOT BE AVAILABLE THE CONTRACTOR SHALL INCLUDE COST FOR BRACING AND SHORING AS NECESSARY.
- 4. THE CONTRACTOR SHALL PROVIDE A FINISH PAVEMENT SURFACE FREE OF LOW SPOTS AND PONDING AREAS. THE MINIMUM SLOPE SHALL MEET OR EXCEED 0.5% IN ALL CASES. ALL SLOPES SHALL BE AWAY FROM BUILDINGS AND TOP OF PAVEMENT SHALL BE AT OR BELOW EXISTING FINISH FLOOR ELEVATIONS.
- 5. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST GEOTECHNICAL REPORT PREPARED BY THE PROJECT GEOTECHNICAL ENGINEER.
- 6. NO ADDITIONAL PAYMENT FOR UNSUITABLE MATERIALS.
- 7. ALL STORM DRAIN PIPE SHALL BE SMOOTH BORE INTERIOR PROVIDING A MANNINGS ROUGHNESS COEFFICIENT OF N=0.012 OR LESS.
- 8. ADJUST ALL MANHOLES, CATCH BASINS, CURB BOXES, ETC. WITHIN LIMITS OF WORK TO FINISH GRADE.
- 9. NATIVE SOILS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LIMIT THE DISTURBANCE TO SUBGRADE SOILS. SHOULD THE SUBGRADE BECOME YIELDING OR DIFFICULT TO WORK, DISTURBED AREAS SHALL BE EXCAVATED AND BACKFILLED WITH COMPACTED SELECT FILL OR CRUSHED STONE AT NO ADDITIONAL EXPENSE TO THE OWNER. ALL SUBGRADE PREPARATION IS SUBJECT TO THE RECOMMENDATIONS OF THE PROJECT GEOTECHNICAL ENGINEER.

## EROSION CONTROL NOTES:

- 1. ALL ROUTINE MAINTENANCE ACTIVITIES SHALL BE CONDUCTED IN SUCH A WAY TO LIMIT THE AMOUNT OF DISTURBED AREA AT ONE TIME TO THE EXTENT PRACTICABLE.
- 2. PRIOR TO THE START OF ANY CLEARING/LAND DISTURBING ACTIVITIES, THE CONTRACTOR SHALL INSTALL APPLICABLE EROSION CONTROL DEVICES SUCH AS PERIMETER SILT FENCE, AND OTHER APPLICABLE MEASURES. IN THE EVENT THE CONTRACTOR IS NOT SURE A EROSION CONTROL MEASURE SHOULD BE IMPLEMENTED, THE CONTRACTOR SHALL CONTACT THE ENGINEER OF RECORD TO CONFIRM IMPLEMENTATION OF ANY EROSION CONTROL DEVICES.
- 3. ALL GROUND AREAS GRADED FOR CONSTRUCTION SHALL BE GRADED, LOAMED, SEEDED AND MULCH SHALL BE APPLIED AS SOON AS POSSIBLE WITHIN 7 DAYS FOLLOWING THE COMPLETION OF ANY SOIL DISTURBANCE, AND PRIOR TO ANY STORM EVENT.
- 4. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL SHALL BE INSTALLED TO THE SATISFACTION OF THE CITY. THE CONTRACTOR SHALL REFERENCE THE APPROVED EROSION AND SEDIMENTATION CONTROL REPORT FOR TEMPORARY AND PERMANENT EROSION AND SEDIMENTATION CONTROL DEVICES IN ADDITION TO THE PLAN SET. THE CONTRACTOR SHALL ALSO REFER TO THE MAINE D.E.P.'S PERMIT CONDITIONS, FINDINGS OF FACT AND ORDER (IF ANY), AND THE CURRENT MAINE EROSION AND SEDIMENT CONTROL BMP MANUAL FOR ADDITIONAL INFORMATION
- 5. PRIOR TO PAVING, THE CONTRACTOR SHALL REMOVE ALL SEDIMENT FROM STORM DRAINS, CATCH BASINS, AND APPURTENANCES.
- 6. REFER TO THE EROSION CONTROL DETAILS & NOTES FOR ADDITIONAL INFORMATION.

## UTILITY NOTES:

- 1. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND ELEVATION OF THE EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED UPON RECORDS OF VARIOUS UTILITY COMPANIES AND WHERE POSSIBLE MEASUREMENTS TAKEN IN THE FIELD. THIS INFORMATION IS NOT TO BE RELIED UPON AS BEING EXACT OR COMPLETE. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO TEST PIT TO DETERMINE THE EXACT LOCATION AND ELEVATION OF UTILITIES TO COORDINATE WITH THE PROPOSED CONNECTIONS OR CROSSING. ANY DISCREPANCIES SHALL BE IMMEDIATELY REPORTED TO THE CIVIL ENGINEER FOR FURTHER DIRECTIONS BEFORE ANY ADDITIONAL WORK PROCEEDS.
- 2. CONTRACTOR TO BYPASS EXISTING SEWER FLOW CONTROL AT CONNECTION TO EXISTING SYSTEM AT NO ADDITIONAL COST.
- 3. CONTRACTOR SHALL, AT NO ADDITIONAL COST TO THE OWNER, CONDUCT EXPLORATORY EXCAVATIONS AT LOCATIONS WHERE PROPOSED EXCAVATION WILL INTERSECT WITH EXISTING UTILITIES.
- 4. ALL NEW SANITARY MANHOLES SHALL BE VACUUM TESTED BEFORE BACKFILLING. TESTING SHALL BE COMPLETED IN ACCORDANCE WITH TECHNICAL REPORT #16 (TR-16): GUIDES FOR THE DESIGN OF WASTEWATER TREATMENT WORKS, PREPARED BY THE NEW ENGLAND INTERSTATE WATER POLLUTION CONTROL COMMISSION.
- 5. SEWER MANHOLES SHALL BE 4' ID UNLESS OTHERWISE STATED ON THE PLANS.
- 6. CONTRACTOR TO PROVIDE 5' OF COVER FROM TOP OF PIPE TO FINISH GRADE FOR WATER MAINS.
- 7. THRUST BLOCKS SHALL BE USED FOR THRUST RESTRAIN ON WATER MAINS, LIMITS FOR THRUST BLOCKS ARE SHOWN ON SHEET C-42.
- 8. WATER INFRASTRUCTURE SHALL BE TESTED IN ACCORDANCE WITH THE PORTLAND WATER DISTRICT DOCUMENT "WATER AND SEWER CONSTRUCTION SPECIFICATIONS AND PROCEDURES", MOST RECENT REVISION.
- 9. ALL REQUIRED FITTINGS FOR THE WATER MAIN ARE NOT SHOWN ON DRAWINGS. CONTRACTOR SHALL FURNISH AND INSTALL ALL NECESSARY FITTINGS REQUIRED TO CONSTRUCT THE WATER MAIN IN ACCORDANCE WITH CITY OF PORTLAND, STATE OF

- MAINE, AND AMERICAN WATER WORKS ASSOCIATION STANDARDS AND REGULATIONS
- 10. CONTRACTOR SHALL COORDINATE WORK REGARDING ANY WATER MAIN CONNECTION AND WATER MAIN SHUTDOWN WITH THE PORTLAND WATER DISTRICT AT LEAST SEVEN (7) DAYS PRIOR TO CONSTRUCTION.
- 11. ALL WATER PIPE INSTALLATION SHALL CONFORM WITH THE PORTLAND WATER DISTRICT SPECIFICATIONS AND PROCEDURES, MOST RECENT EDITION.
- 12. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.
- 13. SEWER, GAS, TELEPHONE, ELECTRICITY, CABLE, WATER AND ANY OTHER UTILITY CONNECTIONS SHALL BE REVIEWED BY PLUMBING, ELECTRICAL, AND MECHANICAL DESIGNER FOR CONSISTENCY WITH THEIR PLANS PRIOR TO CONSTRUCTION.
- 14. COORDINATE EXIT POINT FOR SECONDARY SERVICE WITH THE ARCHITECT/ELECTRICAL ENGINEER. SECONDARY LINE LOCATIONS NOT PROVIDED BY ACORN ENGINEERING WITHIN THE UTILITY PLAN.
- 15. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN ALL THE NECESSARY PERMITS FOR THE INSTALLATION OF THE UTILITIES AND STORMDRAINS WITHIN THE PUBLIC RIGHT OF WAY. THE CONTRACTOR SHALL SUBMIT A MAINTENANCE OF TRAFFIC PLAN TO THE CITY IN ACCORDANCE WITH THE CITY OF PORTLAND TECHNICAL MANUAL PRIOR TO ANY WORK.
- 16. THE CONTRACTOR SHALL PROVIDE AND INSTALL ALL BOXES, FITTINGS, CONNECTORS, COVER PLATES AND OTHER MISCELLANEOUS ITEMS NOT NECESSARILY DETAILED ON THE DRAWINGS TO RENDER INSTALLATION OF UTILITIES COMPLETE AND OPERATIONAL AT NO EXTRA EXPENSE TO THE OWNER.
- 17. CITY LIGHTS SHALL BE IN ACCORDANCE WITH THE CITY OF PORTLAND TECHNICAL MANUAL SECTION 10.5.

		SUBMITTALS
ITEM NUMBER	ITEM	SUBMITTAL
1	WORK SCHEDULE	WORK SCHEDULE
2	BIKE RACK	BIKE RACK MANUFACTURER'S PRODUCT SHEET
3	PAVEMENT (CITY)	SIEVE ANALYSIS HMA MDOT 403.09 GRADE C (12.5 MM)
		SIEVE ANALYSIS HMA MDOT 403.09 GRADE B (19.0 MM)
		BASE GRAVEL 703.06 TYPE B
		SUBBASE GRAVEL MDOT 703.06 TYPE D
4	BRICK WITHIN THE ROW	MANUFACTURE'S PRODUCT SHEET
		SAND MDOT 703.05 SIEVE ANALYSIS
		CRUSHED GRAVEL TYPE B SIEVE ANALYSIS
5	PAVEMENT (SITE)	SIEVE ANALYSIS HMA MDOT 403.09 GRADE C (12.5 MM)
		SIEVE ANALYSIS HMA MDOT 403.09 GRADE B (19.0 MM)
		BASE GRAVEL 703.06 TYPE A
		SUBBASE GRAVEL MDOT 703.06 TYPE D
		BITUMINOUS JOB MIX FORMULA
6	GEOTEXTILE	MANUFACTURE'S PRODUCT SHEET
7	LIGHT POLE	LIGHT POLE MANUFACTURE'S PRODUCT SHEET
		LIGHT POLE BASE MANUFACTURER'S PRODUCT SHEET
8	CATCH BASIN INLET PROTECTION	MANUFACTURE'S PRODUCT SHEET
9	UNDERDRAIN/FOUNDATION DRAIN	UNDERDRAIN PIPE MANUFACTURER'S PRODUCT SHEET
10	ROOF DRAIN	ROOF DRAIN MANUFACTURER'S PRODUCT SHEET
11		MANUFACTURER'S SEWER MANHOLE SPECIFICATION SHEET
		MANHOLE JOINT STRIPS MANUFACTURER'S PRODUCT SHEET
		MANHOLE FRAMES, COVERS MANUFACTURER'S PRODUCT SHEET
12	SEWER PIPE	SEWER PIPE MANUFACTURER'S PRODUCT SHEET
		SAND MDOT 703.33 TYPE C SIEVE ANALYSIS
		PIPE GASKETS MANUFACTURER'S PRODUCT SHEET
13	CONNECTION TO EXISTING SEWER	SEWER CONNECTION PLAN
		SEWERAGE BYPASS PLAN
14	STORM DRAIN	DRAIN PIPING MANUFACTURER'S PRODUCT SHEET
		SAND MDOT 703.33 TYPE C SIEVE ANALYSIS
15	DRAIN MANHOLE	DRAIN MANHOLE MANUFACTURER'S PRODUCT SHEET
		MANHOLE JOINT STRIPS MANUFACTURER'S PRODUCT SHEET
		MANHOLE FRAMES AND COVERS MANUFACTURER'S PRODUCT SHEE
16	CATCH BASIN	CATCH BASIN MANUFACTURER'S PRODUCT SHEET
		BASIN COVERS AND FRAMES MANUFACTURER'S PRODUCT SHEET
17	WATER PIPE	PIPE MANUFACTURER'S PRODUCT SHEET
		MDOT 703.33 TYPE B UD BACKFILL
		3/4" CRUSHED STONE SIEVE ANALYSIS
18	SERVICE CONNECTION	WATER SERVICE CONNECTION PLAN
		WATER SERVICE MANUFACTURER'S PRODUCT SHEET
19	WATER VALVE	WATER VALVE MANUFACTURE'S PRODUCT SHEET
		VALVE BOX MANUFACTURE'S PRODUCT SHEET
		BOX COVER MANUFACTURE'S PRODUCT SHEET
20	CONNECTION TO EXISTING WATER	CONNECTION PLAN SHOP DRAWING
21	CONNECTION TO EXISTING DRAIN	CONNECTION PLAN SHOP DRAWING
22	BICYCLE PARKING	SHOP DRAWING DETAILING LAYOUT
22	DIGICELIAMMO	SHOT BRAVING BETALLING LATOUT

CONSTRUCTION DRAWINGS

ISSUED FOR DATE
PRELIMINARY SUB 1/14/15
UTILITY STUB 4/14/15
COMMENT RESPONSE 4/16/15
PRICING SET 6/5/15
CONSTRUCTION B/12/15
REV. DATE

REVISION TO DATE

BY
DATE
WHS
4/14/15
WHS
6/5/15
CONSTRUCTION REV.
DATE

| PROJECT NAME: | PROJECT NAME

12/5/2014

SCALE:


DESIGNED BY:


CHECKED BY:


SAVAGE

DRAWING NO

DRAWN BY:







### General Notes:

- 1. This plan is not intended to depict limits or extent of fee title ownership. An opinion of title should be rendered by a title attorney.
- 2. This office reserves the right to be held harmless by all 3rd party claims.
- 3. This survey does not purport to reflect any of the following: a. easements other than those that are visible or specifically stated in
  - the referenced documents. b. building setback compliance or restrictive covenants.
  - c. zoning or other land use regulations.
- d. the location of any underground utilities or structures.
- 4. This office reserves the right to be held harmless for unknown or unobtainable private records which could affect the results of this survey.
- 5. Reference is made to "Letter Of Agreement" dated May 16, 2014 between Nadeau Land Surveys and the below listed client(s), which shall be considered an integral part of this survey.
- 6. N/F is an abbreviation for Now or Formerly.
- 7. All deeds referenced on this plan are recorded at the Cumberland County Registry of Deeds (CCRD).
- 8. This office does not accept any liability for errors in the Plan References listed hereon, except Plan Reference 13.
- 9. Locus Parcel is shown on the City of Portland Assessor's Map 12, Block I, as Lots 1 and 5, and is listed as 89 Anderson Street, and 29 Everett Street.
- 10. Area of Locus Parcel, including easement, is 23,239.1 square feet (0.53 acre) to monumented line of Anderson Street; 23,425.7 square feet (0.54 acre) to
- 11. The apparent right of way lines depicted on this plan are based on the Plan References listed hereon, monumentation found in the field, and

the R/W line of Anderson Street per Plan Reference 14.

City Engineering Street Notes.

- 12. The Locus Parcel does not scale in a Special Flood Hazard Area per FEMA Flood Insurance Rate Map Community-Panel Number 230051 0013B, index dated December 8, 1998. The parcel scales in Zone C.
- 13. All building corner offsets to boundary lines are from brick building corners.
- Call 1-888-DIGSAFE at least three business days before performing ANY
- 15. Per City of Portland Records 14-371, dated October 1, 1866, the name of Fremont Street was changed to Anderson Street, and was accepted June 19, 1857 as fifty (50) feet wide per City of Portland Records 10-182. Fox Street was accepted November 20, 1851 as fifty (50) feet wide per City of Portland Records 8-31. Everett Street was accepted June 19, 1857 as fifty (50) feet wide per City of Portland Records 10-199.
- 16. See Easement Deed from Patrick J. and Sharon A. Lee to New England Telephone and Telegraph Company, dated September 6, 1991 and recorded in CCRD Book 9816, Page 171. (See Plan Reference 12)
- 17. Horizontal and vertical datums are city datums based on Plan Reference 14. Monuments "MF 34" at southerly intersection of Anderson & Fox Streets and "MF 35" at westerly intersection of Anderson & East Lancaster Streets held as common points with Plan Reference 14. "DMH 3180" held for elevation per Plan Reference 14.
- 18. Existing building appears to encroach the Fox Street right of way by 0.2' along its northwesterly face.
- 19. Underground utility lines, sizes, and inverts are based solely on Plan Reference 16 and have not been verified by this office, except for the three manholes depicted northerly of the Locus Parcel. See Note 8.

Rev. 3/30/2015: Note 19 & Legend, Add bldg.'s for setback calc.'s, Add coord.'s, Add 2 manholes/inverts n'ly of site, MH 3304 inverts

Rev. 9/9/2014: Name, Add underground utility lines, sizes and inverts, Add Note 19 and Plan Reference 16, Vicinity map, Add to Legence

Plan Depicting The Results Of A Boundary, Topographic & Existing Conditions Survey Made For Redfern Properties, LLC

Southeasterly Sideline Of Fox Street, Northeasterly Sideline Of Anderson Street, & Northwesterly Sideline Of Everett Street Portland, Maine


PREPARED BY:


Nadeau Land Surveys


**Professional Land Surveyors** Certified Floodplain Managers


PH. (207) 878-7870 FAX (207) 878-7871


DRAWN BY: PLAN DATE: RECORD OWNER: TPB7/21/2014 Perigee, LLC 120 Sheridan Street CHECKED BY: JDN/MLC SURVEY DATE: June 2014 Portland, Maine INSTR. Topcon GPT-3003W & Topcon Hyper II GPS SCALE: 1"=20' FB 402 & Topcon Ranger FIELD BOOK: SHEET No: 1 of 1 2141510BTR1

















### 1.0 EROSION CONTROL MEASURES AND SITE STABILIZATION

AS PART OF THE SITE DEVELOPMENT, THE FOLLOWING TEMPORARY AND PERMANENT EROSION AND SEDIMENTATION CONTROL DEVICES SHALL BE IMPLEMENTED. DEVICES SHALL BE INSTALLED AS DESCRIBED IN THIS REPORT OR WITHIN THE PLAN SET. SEE THE MAINE EROSION AND SEDIMENT CONTROL HANDBOOK FOR CONSTRUCTION: BEST MANAGEMENT PRACTICES FOR FURTHER

#### 1.1 TEMPORARY EROSION CONTROL MEASURES

THE FOLLOWING TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES ARE PLANNED FOR THE PROJECT'S CONSTRUCTION PERIOD.

- 1.1.1 CRUSHED STONE STABILIZED CONSTRUCTION ENTRANCES SHALL BE PLACED AT ALL ACCESS POINTS TO THE PROJECT SITE WHERE THERE ARE DISTURBED AREAS. THE FOLLOWING SPECIFICATIONS SHALL BE FOLLOWED AT A MINIMUM:
  - STONE SIZE SHALL BE 2-3 INCHES, OR RECLAIMED OR RECYCLED CONCRETE EQUIVALENT. • THE THICKNESS OF THE ENTRANCE SHALL BE NO LESS THAN 6 INCHES. • THE ENTRANCE SHALL NOT BE LESS THAN 20 FEET WIDE, HOWEVER NOT LESS THAN THE FULL WIDTH OF POINTS WHERE INGRESS OR EGRESS OCCURS. THE LENGTH SHALL NOT
- BE LESS THAN 50 FEET IN LENGTH. • GEOTEXTILE FABRIC (WOVEN OR NON WOVEN) SHALL BE PLACED OVER THE ENTIRE ENTRANCE AREA. PIPING FOR SURFACE WATER DRAINAGE SHALL BE PROVIDED UNDER THE ENTRANCE; HOWEVER A MOUNTABLE BERM WITH 5:1 SLOPES SHALL BE PERMITTED.
- THE ENTRANCE/EXIT SHALL BE MAINTAINED TO THE EXTENT THAT IT WILL PREVENT THE TRACKING OF SEDIMENT ONTO PUBLIC ROAD WAYS. 1.1.2 SILTATION FENCE OR EROSION CONTROL BERM SHALL BE INSTALLED DOWN GRADIENT OF ANY DISTURBED AREAS TO TRAP RUNOFF BORNE SEDIMENTS UNTIL PERMANENT STABILIZATION IS ACHIEVED. THE SILT FENCE OR EROSION CONTROL BERM SHALL BE INSTALLED PER THE DETAILS PROVIDED IN THE PLAN SET AND INSPECTED BEFORE AND IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. REPAIRS SHALL BE MADE IF THERE ARE ANY SIGNS OF EROSION OR SEDIMENTATION BELOW THE FENCE LINE OR BERM. IF THERE ARE SIGNS OF UNDERCUTTING AT THE CENTER OR THE EDGES, OR IMPOUNDING OF LARGE VOLUMES OF WATER BEHIND THE FENCE OR BERM, THE BARRIER SHALL BE REPLACED WITH A STONE CHECK DAM.
- 1.1.3 HAY MULCH INCLUDING HYDRO SEEDING IS INTENDED TO PROVIDE COVER FOR DENUDED OR SEEDED AREAS UNTIL REVEGETATION IS ESTABLISHED. MULCH PLACED BETWEEN APRIL 15TH AND NOVEMBER 1ST ON SLOPES OF LESS THAN 15 PERCENT SHALL BE COVERED BY FABRIC NETTING AND ANCHORED WITH STAPLES IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATION. MULCH PLACED BETWEEN NOVEMBER 1ST AND APRIL 15TH ON SLOPES EQUAL TO OR STEEPER THAN 8 PERCENT AND EQUAL TO OR FLATTER
- THAN 2:1 SHALL USE MATS OR FABRIC NETTING AND ANCHORED WITH STAPLES IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATION. 1.1.4 AT ANY TIME OF THE YEAR, ALL SLOPES GREATER THAN 3:1 SHALL BE STABILIZED WITH DOUBLE NET EROSION CONTROL BLANKET BIONET SC150BN BY NORTH AMERICAN GREEN OR
- APPROVED EQUAL, OR EROSION CONTROL MIX SLOPE PROTECTION AS DETAILED WITHIN THE PLANS. 1.1.5 ALL STREETS USED AS CONSTRUCTION ENTRANCES SHALL BE SWEPT TO CONTROL MUD AND DUST AS NECESSARY. ADD ADDITIONAL STONE TO THE STABILIZED CONSTRUCTION ENTRANCE TO MINIMIZE THE TRACKING OF MATERIAL OFF THE SITE AND ONTO THE SURROUNDING ROADWAYS.
- 1.1.6 DURING CLEARING AND GRUBBING OPERATIONS, STONE CHECK DAMS SHALL BE INSTALLED AT ANY AREAS OF CONCENTRATED FLOW. THE MAXIMUM HEIGHT OF THE CHECK DAM SHALL NOT EXCEED 2 FEET. THE CENTER OF THE CHECK DAM SHALL BE 6 INCHES BELOW THE OUTER EDGES OF THE DAM. THE CONTRACTOR SHALL MULCH THE SIDE SLOPES AND INSTALL STONE CHECK DAMS FOR ALL NEWLY EXCAVATED DITCH LINES WITHIN 24 HOURS OF THEIR CREATION.
- 1.1.7 SILT FENCE STAKE SPACING SHALL NOT EXCEED 6 FEET UNLESS THE FENCE IS SUPPORTED WITH 14 GAUGE WIRE IN WHICH CASE THE MAXIMUM SPACING SHALL NOT EXCEED 10 FEET. THE SILT FENCE SHALL BE "TOED" INTO THE GROUND. 1.1.8 STORMDRAIN INLET PROTECTION SHALL BE PROVIDED THROUGH THE USE OF ANY OF THE FOLLOWING: HAY BALE DROP INLET STRUCTURES, SILT FENCE DROP INLET SEDIMENT FILTER,
- GRAVEL AND WIRE MESH DROP INLET SEDIMENT FILTER, OR CURB INLET SEDIMENT FILTER. BARRIERS SHALL BE INSPECTED AFTER EVERY RAINFALL EVENT AND REPAIRED AS NECESSARY. SEDIMENTS SHALL BE REMOVED WHEN ACCUMULATION HAS REACHED 1/2 THE DESIGN HEIGHT. DUST CONTROL SHALL BE ACCOMPLISHED BY THE USE OF ANY OF THE FOLLOWING: WATER, CALCIUM CHLORIDE, STONE, OR AN APPROVED MDEP PRODUCT. DUST CONTROL SHALL BE
- APPLIED AS NEEDED TO ACCOMPLISH DUST CONTROL. TEMPORARY LOAM, SEED, AND MULCHING SHALL BE USED IN AREAS WHERE NO OTHER EROSION CONTROL MEASURE IS USED. APPLICATION RATES FOR SEEDING ARE PROVIDED AT THE END OF THIS REPORT 1.1.11 STOCKPILES SHALL BE STABILIZED WITHIN 7 DAYS OF FORMATION UNLESS A SCHEDULED RAIN EVENT OCCURS PRIOR TO THE 7 DAY WINDOW, IN WHICH CASE THE STOCKPILE SHALL BE
- STABILIZED PRIOR TO THE RAIN EVENT. METHODS OF STABILIZATION SHALL BE MULCH, EROSION CONTROL MIX, OR EROSION CONTROL BLANKETS/MATS. SILT FENCE OR A WOOD WASTE COMPOST FILTER BERM SHALL BE PLACED DOWNHILL OF ANY SOIL STOCKPILE LOCATION. 1.1.12 FOR DISTURBANCE BETWEEN NOVEMBER 1 AND APRIL 15, PLEASE REFER TO WINTER STABILIZATION PLAN IN THIS REPORT AND THE MAINE EROSION AND SEDIMENT CONTROL BMP MANUAL FOR FURTHER INFORMATION
- 1.1.13 IT IS OF THE UTMOST IMPORTANCE THAT STORMWATER RUNOFF AND POTENTIAL SEDIMENT FROM THE CONSTRUCTION SITE BE DIVERTED AROUND THE PROPOSED UNDERDRAINS UNTIL THE TRENCH IS BACKFILLED.

### 1.2 PERMANENT EROSION CONTROL MEASURES

THE FOLLOWING PERMANENT EROSION CONTROL MEASURES ARE INTENDED FOR POST DISTURBANCE AREAS OF THE PROJECT.

- 1.2.1 ALL DISTURBED AREAS DURING CONSTRUCTION, NOT SUBJECT TO OTHER PROPOSED CONDITIONS, SHALL RECEIVE A MINIMUM 4"OF LOAM, LIMED, FERTILIZED, AND MULCHED. EROSION CONTROL BLANKETS OR MATS SHALL BE PLACED OVER THE MULCH IN AREAS NOTED IN PARAGRAPH 4.1 OF THIS REPORT.
- 1.2.2 ALL STORMDRAIN OUTLETS SHALL HAVE RIPRAP APRONS OR STABILIZED SWALES AS DEPICTED ON THE PLANS. THE RIPRAP APRONS OR STABILIZED APRONS SHALL CONSTRUCTED WITHIN 48 HOURS OF THE CONSTRUCTION OF THE STORMDRAIN OUTLET.
- 1.2.3 ALL STORMWATER DEVICES SHALL BE INSTALLED AND STABILIZED PRIOR RECEIVING STORMWATER. 1.2.4 REFER TO THE MAINE EROSION AND SEDIMENT CONTROL BMP MANUAL FOR ADDITIONAL INFORMATION.

### 2.0 EROSION AND SEDIMENTATION CONTROL PLAN

2.1 THE EROSION AND SEDIMENTATION CONTROL PLAN IS INCLUDED WITHIN THE PLAN SET.

### 3.0 DETAILS AND SPECIFICATIONS

3.1 EROSION CONTROL DETAILS AND SPECIFICATION ARE INCLUDED IN THE PLAN SET.

### 4.0 STABILIZATION PLAN FOR WINTER CONSTRUCTION

WINTER CONSTRUCTION CONSISTS OF EARTHWORK DISTURBANCE BETWEEN THE DATES OF NOVEMBER 1 AND APRIL 15. IF A CONSTRUCTION SITE IS NOT STABILIZED WITH PAVEMENT, A ROAD GRAVEL BASE, 75% MATURE VEGETATION COVER OR RIPRAP BY NOVEMBER 15, THEN THE SITE SHALL BE PROTECTED WITH OVER-WINTER STABILIZATION. ANY AREA NOT STABILIZED WITH PAVEMENT, VEGETATION, MULCHING, EROSION CONTROL MIX, EROSION CONTROL MATS, RIPRAP OR GRAVEL BASE ON A ROAD SHALL BE CONSIDERED OPEN.

THE CONTRACTOR SHALL LIMIT THE WORK AREA TO AREAS THAT WORK WILL OCCUR IN DURING THE SUBSEQUENT 15 DAYS AND SO THAT IT CAN BE MULCHED ONE DAY PRIOR TO A SNOW EVENT. THE CONTRACTOR SHALL STABILIZE WORK AREAS PRIOR TO OPENING ADDITIONAL WORK AREAS TO MINIMIZE AREAS WITHOUT EROSION CONTROL MEASURES.

### THE FOLLOWING MEASURES SHALL BE IMPLEMENTED DURING WINTER CONSTRUCTION PERIODS:

### 4.1 SEDIMENT BARRIERS

4.2 MULCHING

DURING FROZEN CONDITIONS, SEDIMENT BARRIERS MAY CONSIST OF EROSION CONTROL MIX BERMS OR ANY OTHER RECOGNIZED SEDIMENT BARRIERS AS FROZEN SOIL PREVENTS THE PROPER INSTALLATION OF HAY BALES OR SILT FENCES.

ALL AREAS SHALL BE CONSIDERED TO BE DENUDED UNTIL SEEDED AND MULCHED. HAY AND STRAW MULCH SHALL BE APPLIED AT A RATE OF 150 LB. PER 1,000 SQUARE FEET OR TONS/ACRE (TWICE THE NORMAL ACCEPTED RATE OF 75-LBS./1,000 S.F. OR 1.5 TONS/ACRE) AND SHALL BE PROPERLY ANCHORED. EROSION CONTROL MIX MUST BE APPLIED WITH A MINIMUM 4 INCH THICKNESS. MULCH SHALL NOT BE SPREAD ON TOP OF SNOW. THE SNOW SHALL BE REMOVED DOWN TO A ONE-INCH DEPTH OR LESS PRIOR TO APPLICATION. AFTER EACH DAY OF FINAL GRADING, THE AREA SHALL BE PROPERLY STABILIZED WITH ANCHORED HAY OR STRAW OR EROSION CONTROL MATTING. AN AREA SHALL BE CONSIDERED TO HAVE BEEN STABILIZED WHEN EXPOSED SURFACES HAVE BEEN EITHER MULCHED OR ADEQUATELY ANCHORED SO THAT GROUND SURFACE IS NOT VISIBLE THROUGH THE MULCH. BETWEEN THE DATES OF NOVEMBER 1 AND APRIL 15, ALL MULCH SHALL BE ANCHORED BY EITHER MULCH NETTING, TRACKING OR WOOD CELLULOSE FIBER. THE COVER WILL BE CONSIDERED SUFFICIENT WHEN THE GROUND SURFACE IS NOT VISIBLE THROUGH THE MULCH. AFTER NOVEMBER 1ST, MULCH AND ANCHORING OF ALL EXPOSED SOIL SHALL OCCUR AT THE END OF EACH FINAL GRADING WORKDAY.

## 4.3 SOIL STOCKPILING

STOCKPILES OF SOIL OR SUBSOIL SHALL BE MULCHED FOR OVER WINTER PROTECTION WITH HAY OR STRAW AT TWICE THE NORMAL RATE OR WITH A FOUR-INCH LAYER OF EROSION CONTROL MIX. THIS SHALL BE DONE WITHIN 24 HOURS OF STOCKING AND RE-ESTABLISHED PRIOR TO ANY RAINFALL OR SNOWFALL.

## 4.4 SEEDING

BETWEEN THE DATES OF OCTOBER 15TH AND APRIL 1ST, LOAM OR SEED SHALL NOT BE REQUIRED. DURING PERIODS OF ABOVE FREEZING TEMPERATURES FINISHED AREAS SHALL BE FINE GRADED AND EITHER PROTECTED WITH MULCH OR TEMPORARILY SEEDED AND MULCHED UNTIL SUCH TIME AS THE FINAL TREATMENT CAN BE APPLIED. IF THE DATE IS AFTER NOVEMBER 1ST AND IF THE EXPOSED AREA HAS NOT BEEN LOAMED, FINAL GRADING WITH A UNIFORM SURFACE, THEN THE AREA MAY BE DORMANT SEEDED AT A RATE OF 3 TIMES HIGHER THAN SPECIFIED FOR PERMANENT SEED AND THEN MULCHED.

DORMANT SEEDING MAY BE PLACED PRIOR TO THE PLACEMENT OF MULCH OR EROSION CONTROL BLANKETS. IF DORMANT SEEDING IS USED FOR THE SITE. ALL DISTURBED AREAS SHALL RECEIVE 4 OF LOAM AND SEED AT AN APPLICATION RATE OF 5 LBS/1,000 S.F. ALL AREAS SEEDED DURING THE WINTER SHALL BE INSPECTED IN THE SPRING FOR ADEQUATE CATCH. ALL AREAS INSUFFICIENTLY VEGETATED (LESS THAN 75% CATCH) SHALL BE REVEGETATED BY REPLACING LOAM, SEED AND MULCH. IF DORMANT SEEDING IS NOT USED FOR THE SITE, ALL DISTURBED AREAS SHALL BE REVEGETATED IN THE SPRING

## 4.5 OVER WINTER STABILIZATION OF DISTURBED SOILS

BY SEPTEMBER 15TH, ALL DISTURBED SOILS ON AREAS HAVING A SLOPE LESS THAN 15% SHALL BE SEEDED AND MULCHED. IF THE DISTURBED AREAS ARE NOT STABILIZED BY THIS DATE,

- THEN ONE OF THE FOLLOWING ACTIONS SHALL BE TAKEN TO STABILIZE THE SOIL FOR LATE FALL AND WINTER: • STABILIZE THE SOIL WITH TEMPORARY VEGETATION - BY OCTOBER 1ST, SEED THE DISTURBED SOIL WITH WINTER RYE AT A SEEDING RATE OF 3LBS PER 1,000 S.F., LIGHTLY MULCH THE SEEDED SOIL WITH HAY OR STRAW AT 75 LBS PER 1,000 S.F., AND ANCHOR THE MULCH WITH PLASTIC NETTING. MONITOR GROWTH OF THE RYE OVER THE NEXT 30 DAYS. IF THE RYE FAILS TO GROW AT LEAST THREE INCHES OR FAILS TO COVER AT LEAST 75% OF THE DISTURBED SOIL BEFORE NOVEMBER 1ST, THEN MULCH THE AREA FOR
- STABILIZE THE SOIL WITH SOD STABILIZE THE DISTURBED SOIL WITH PROPERLY INSTALLED SOD BY OCTOBER 1ST. PROPER INSTALLATION INCLUDES PINNING THE SOD ONTO THE SOIL WITH WIRE PINS, ROLLING THE SOD TO GUARANTEE CONTACT BETWEEN THE SOD AND UNDERLYING SOIL, AND WATERING THE SOD TO PROMOTE ROOT GROWTH INTO THE
- STABILIZE THE SOIL WITH MULCH BY NOVEMBER 15TH, MULCH THE DISTURBED SOIL BY SPREADING HAY OR STRAW AT A RATE OF AT LEAST 150 LBS PER 1,000 S.F. ON THE AREA SO THAT NO SOIL IS VISIBLE THROUGH THE MULCH. IMMEDIATELY AFTER APPLYING THE MULCH, ANCHOR THE MULCH WITH PLASTIC NETTING TO PREVENT WIND FROM

## 4.6 OVER WINTER STABILIZATION OF DISTURBED SLOPES

OVER-WINTER PROTECTION.

ALL STONE—COVERED SLOPES SHALL BE CONSTRUCTED AND STABILIZED BY NOVEMBER 15TH. ALL SLOPES TO BE VEGETATED SHALL BE SEEDED AND MULCHED BY SEPTEMBER 1ST. A SLOPE IS CONSIDERED A GRADE GREATER THAN 15%. IF A SLOPE TO BE VEGETATED IS NOT STABILIZED BY SEPTEMBER 1ST, THEN ONE OF THE FOLLOWING ACTION SHALL BE TAKEN TO STABILIZE THE SLOPE FOR LATE FALL AND WINTER:

- STABILIZE THE SOIL WITH TEMPORARY VEGETATION AND EROSION CONTROL MATS BY OCTOBER 1ST THE DISTURBED SLOPE SHALL BE SEEDED WITH WINTER RYE AT A SEEDING RATE OF 3 LBS PER 1,000 S.F. AND THEN INSTALL EROSION CONTROL MATS OR ANCHORED MULCH OVER THE SEEDING. IF THE RYE FAILS TO GROW AT LEAST THREE INCHES OR FAILS TO COVER AT LEAST 75% F THE SLOPE BY NOVEMBER 1ST, THEN THE CONTRACTOR SHALL COVER THE SLOPE WITH A LAYER OF EROSION CONTROL MIX OR WITH
- STABILIZE THE SOIL WITH SOD THE DISTURBED SLOPE SHALL BE STABILIZED WITH PROPERLY INSTALLED SOD BY OCTOBER 1ST. PROPER INSTALLATION INCLUDES THE CONTRACTOR PINNING THE SOD ONTO THE SLOPE WITH WIRE PINS, ROLLING THE SOD TO GUARANTEE CONTACT BETWEEN THE SOD AND UNDERLYING SOIL, AND WATERING THE SOD TO PROMOTE ROOT GROWTH INTO THE DISTURBED SOIL. THE CONTRACTOR SHALL NOT USE LATE—SEASON SOD INSTALLATION TO STABILIZE SLOPES HAVING A GRADE GREATER THAN 3H:1V OR HAVING GROUNDWATER SEEPS ON THE SLOPE FACE.
- STABILIZE THE SOIL WITH EROSION CONTROL MIX EROSION CONTROL MIX SHALL BE PROPERLY INSTALLED BY NOVEMBER 15TH. THE CONTRACTOR SHALL NOT USE EROSION CONTROL MIX TO STABILIZE SLOPES HAVING GRADES GREATER THAN 2H:1V OR HAVING GROUNDWATER SEEPS ON THE SLOPE FACE.
- STABILIZE THE SOIL WITH STONE RIPRAP PLACE A LAYER OF STONE RIPRAP ON THE SLOPE BY NOVEMBER 15TH. A REGISTERED PROFESSIONAL ENGINEER SHALL BE HIRED TO DETERMINE THE STONE SIZE NEEDED FOR STABILITY ON THE SLOPE AND TO DESIGN A FILTER LAYER FOR UNDERNEATH THE RIPRAP.

## 5.0 INSPECTION AND MAINTENANCE

A PERSON WITH KNOWLEDGE OF EROSION AND STORMWATER CONTROL, INCLUDING THE STANDARDS AND CONDITIONS IN THE PERMIT, SHALL CONDUCT PERIODIC VISUAL INSPECTIONS OF INSTALLED EROSION CONTROL MEASURES. THE FREQUENCY OF INSPECTION SHALL OCCUR AT LEAST ONCE EVERY TWO WEEKS, PRIOR TO COMPLETING PERMANENT STABILIZATION MEASURES, AS WELL AS AFTER A "STORM EVENT". A "STORM EVENT" SHALL CONSIST 0.5 INCHES OF RAIN WITHIN A 24 HOUR PERIOD. THE FOLLOWING EROSION AND SEDIMENT CONTROL - BEST MANAGEMENT PRACTICES (BMP'S) SHALL INSPECTED IN THE MANNER AS DESCRIBED.

SEDIMENT BARRIERS: HAY BALE BARRIERS. SILT FENCES AND FILTER BERMS SHALL BE INSPECTED AND REPAIRED FOR THE FOLLOWING IF THERE ARE ANY SIGNS OF EROSION OR SEDIMENTATION BELOW THEM. IF THERE ARE SIGNS OF UNDERCUTTING AT THE CENTER OR THE EDGES OF THE BARRIER, OR IMPOUNDING OF LARGE VOLUMES OF WATER BEHIND THEM, SEDIMENT BARRIERS SHALL BE REPLACED WITH A TEMPORARY CHECK DAM. SHOULD THE FABRIC ON A SILT FENCE OR FILTER BARRIER DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER IS STILL NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY. SEDIMENT DEPOSITS SHOULD BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE—HALF THE HEIGHT OF THE BARRIER. FILTER BERMS SHOULD BE RESHAPED AS NEEDED. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE OR FILTER BARRIER IS NO LONGER REQUIRED SHOULD BE DRESSED TO CONFORM TO THE EXISTING GRADE, PREPARED AND SEEDED.

STABILIZED STONE CONSTRUCTION ENTRANCES THE EXIT SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. WHEN THE CONTROL PAD BECOMES INEFFECTIVE, THE STONE SHALL BE REMOVED ALONG WITH THE COLLECTED SOIL MATERIAL AND REDISTRIBUTED ON SITE IN A STABLE MANNER. THE ENTRANCE SHOULD THEN BE RECONSTRUCTED. THE CONTRACTOR SHALL SWEEP OR WASH PAVEMENT AT EXITS, WHICH HAVE EXPERIENCED MUD-TRACKING ON TO THE PAVEMENT OR TRAVELED WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH AGGREGATE, WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING STORM DRAINS, DITCHES, OR WATERWAYS.

MULCHED AREAS ALL MULCHES MUST BE INSPECTED PERIODICALLY, IN PARTICULAR AFTER RAINSTORMS, TO CHECK FOR RILL EROSION. IF LESS THAN 90% OF THE SOIL SURFACE IS COVERED BY MULCH, ADDITIONAL MULCH SHALL BE IMMEDIATELY APPLIED. NETS MUST BE INSPECTED AFTER RAIN EVENTS FOR DISLOCATION OR FAILURE. IF WASHOUTS OR BREAKAGE OCCUR, RE-INSTALL THE NETS AS NECESSARY AFTER REPAIRING DAMAGE TO THE SLOPE. INSPECTIONS SHALL TAKE PLACE UNTIL GRASSES ARE FIRMLY ESTABLISHED (95% SOIL SURFACE COVERED WITH GRASS). WHERE MULCH IS USED IN CONJUNCTION WITH ORNAMENTAL PLANTINGS, INSPECT PERIODICALLY THROUGHOUT THE YEAR TO DETERMINE IF MULCH IS MAINTAINING COVERAGE OF THE SOIL SURFACE. REPAIR AS NEEDED.

DUST CONTROL WHEN TEMPORARY DUST CONTROL MEASURES ARE USED, REPETITIVE TREATMENT SHALL BE APPLIED AS NEEDED TO ACCOMPLISH CONTROL.

STORMWATER APPURTENANCES INCLUDING THE UNDERDRAINS, STORM DRAINS, AND CATCH BASINS.

### EROSION AND SEDIMENTATION CONTROL INSPECTIONS:

ACORN ENGINEERING HAS PERSONNEL QUALIFIED TO CONDUCT EROSION AND SEDIMENTATION CONTROL INSPECTIONS. FOR FURTHER INFORMATION CONTACT:

#### CONTACT: WILL SAVAGE, PE TELEPHONE: (207) 775-2655

- MAINE PROFESSIONAL ENGINEERING LICENSE #11419
- MAINE DEP CERTIFIED IN MAINTENANCE & INSPECTION OF STORMWATER BMP'S CERT #14 • CERTIFIED EROSION, SEDIMENT AND STORM WATER INSPECTOR (CESSWI) CERT #0293
- CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL (CPESC) CERT. #4620

THE CONTRACTOR HAS SOLE RESPONSIBILITY FOR COMPLYING WITH THE EROSION AND SEDIMENTATION REPORT/PLAN, INCLUDING CONTROL OF FUGITIVE DUST. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY MONETARY PENALTIES RESULTING FROM FAILURE TO COMPLY WITH THESE STANDARDS. 6.0 IMPLEMENTATION SCHEDULE

THE FOLLOWING IMPLEMENTATION SEQUENCE IS INTENDED TO MAXIMIZE THE EFFECTIVENESS OF THE ABOVE DESCRIBED EROSION CONTROL MEASURES. CONTRACTORS SHOULD AVOID OVEREXPOSING DISTURBED AREAS AND LIMIT THE AMOUNT OF STABILIZATION AREA.

- INSTALL A STABILIZED CONSTRUCTION ENTRANCE IN ALL LOCATIONS WHERE CONSTRUCTION TRAFFIC WILL ENTER AND EXIT THE SITE.
- INSTALL PERIMETER SILT FENCE OR EROSION CONTROL BERM. INSTALL ALL OTHER EROSION CONTROL DEVICES AS NECESSARY THROUGHOUT THE REMAINDER OF THIS SCHEDULE.
- CUT AND FILL ONLY AS NECESSARY TO BACKFILL THE RETAINING WALL AND FOUNDATION WALL AS DESIGNED WITHIN THE APPROPRIATE PLAN(S). COMMENCE EARTHWORK OPERATIONS, WALL AND FOUNDATION INSTALLATION.
- COMMENCE INSTALLATION OF DRAINAGE INFRASTRUCTURE. COMMENCE INSTALLATION OF OTHER UTILITIES.
- CONTINUE EARTHWORK AND GRADING TO SUBGRADE AS NECESSARY FOR CONSTRUCTION.
- COMPLETE INSTALLATION OF DRAINAGE INFRASTRUCTURE, AS WELL AS OTHER UTILITY WORK. COMPLETE REMAINING EARTHWORK OPERATIONS.
- INSTALL SUB-BASE AND BASE GRAVELS IN PAVED AREAS.
- INSTALL PAVING, CURBING AND BRICKWORK LOAM, LIME, FERTILIZE, SEED AND MULCH DISTURBED AREAS AND COMPLETE ALL LANDSCAPING.
- ONCE THE SITE IS STABILIZED AND 90% CATCH OF VEGETATION HAS BEEN OBTAINED, REMOVE ALL TEMPORARY EROSION CONTROL MEASURES. TOUCH UP AREAS WITHOUT A VIGOROUS CATCH OF GRASS WITH LOAM AND SEED.
- COMPLETE SITE SIGNAGE AND STRIPING EXECUTE PROPER MAINTENANCE OF ALL TEMPORARY AND PERMANENT EROSION CONTROL MEASURES THROUGHOUT THE PROJECT.

THE ABOVE IMPLEMENTATION SEQUENCE SHOULD BE GENERALLY FOLLOWED BY THE SITE CONTRACTOR. HOWEVER, THE CONTRACTOR MAY CONSTRUCT SEVERAL ITEMS SIMULTANEOUSLY. THE CONTRACTOR SHALL SUBMIT TO THE OWNER A SCHEDULE OF THE COMPLETION OF THE WORK. IF THE CONTRACTOR IS TO COMMENCE THE CONSTRUCTION OF MORE THAN ONE ITEM ABOVE, THEY SHALL LIMIT THE AMOUNT OF EXPOSED ARE TO THOSE AREAS IN WHICH WORK IS EXPECTED TO BE UNDERTAKEN DURING THE FOLLOWING 30 DAYS.

THE CONTRACTOR SHALL REVEGETATE DISTURBED AREAS AS RAPIDLY AS POSSIBLE. ALL AREAS SHALL BE PERMANENTLY STABILIZED WITHIN 7 DAYS OF FINAL GRADING OR BEFORE A STORM EVENT. THE CONTRACTOR SHALL INCORPORATE PLANNED INLETS AND DRAINAGE SYSTEMS AS EARLY AS POSSIBLE INTO THE CONSTRUCTION PHASE. 7.0 CONCLUSION

THE ABOVE EROSION CONTROL NARRATIVE IS INTENDED TO MINIMIZE THE DEVELOPMENT IMPACT BY IMPLEMENTING TEMPORARY AND PERMANENT EROSION CONTROL MEASURES. THE CONTRACTOR SHALL ALSO REFER TO THE MAINE EROSION AND SEDIMENT CONTROL BMP MANUAL FOR ADDITIONAL INFORMATION.

### TEMPORARY SEEDING PLAN

SEEDING

THE SEEDED AREAS SHALL BE FEASIBLY GRADED OUT TO PROVIDE THE USE OF EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH APPLICATION, AND MULCH ANCHORING. IF NECESSARY, THE SITE MAY REQUIRE ADDITIONAL TEMPORARY EROSION CONTROL MEASURES OUTLINED IN THE EROSION CONTROL REPORT. SEEDBED PREPARATION

FERTILIZER SHALL BE APPLIED TO THE SITE AT A RATE OF 13.8 POUNDS PER 1,000 SQUARE FEET. THE COMPOSITION OF THE FERTILIZER SHALL BE 10-10-10 (N-P205-K20) OR EQUIVALENT. LIMESTONE SHALL BE APPLIED TO THE SITE AT A RATE OF 138 POUNDS PER 1,000 SQUARE FEET

THE COMPOSITION AND AMOUNT OF TEMPORARY SEED APPLIED TO A SITE SHALL BE DETERMINED BY THE FOLLOWING TABLE

SEEDPOUNDS / 1,000 S.F.RECOMMENDED SEEDING DATESWINTER RYE2.57AUG-15 TO OCT-10ATS1.84APR-1 TO JUL-1 AUG-15 TO SEP-15ANNUAL RYEGRASSO.92APR-1 TO JUL-1SUDANGRASSO.92MAY-15 TO AUG-15PERENNIALO.92AUG-15 TO SEP-15

MULCH SHALL BE APPLIED AT A RATE OF 70 LBS - 90 LBS PER 1,000 SQUARE FEET. THE MULCH SHALL BE INSTALLED AT A MINIMUM DEPTH OF 4 INCHES. THE SEEDED AREA SHALL BE MULCHED IMMEDIATELY AFTER SEED IS APPLIED. MULCHING DURING THE WINTER SEASON SHALL BE DOUBLE THE NORMAL AMOUNT. CONCLUSION

PLEASE REFER TO THE MAINE EROSION AND SEDIMENT CONTROL BMP MANUAL FOR ADDITIONAL INFORMATION PERTAINING TO TEMPORARY SEEDING AND MULCHING.

## PERMANENT SEEDING PLAN

## SITE PREPARATION

IHE SEEDED AREAS SHALL BE FEASIBLY GRADED OUT TO PROVIDE THE USE OF EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH APPLICATION, AND MULCH ANCHORING. IF NECESSARY, THE SITE MAY REQUIRE ADDITIONAL TEMPORARY EROSION CONTROL MEASURES OUTLINED IN THE EROSION CONTROL REPORT SEEDBED PREPARATION

FERTILIZER SHALL BE APPLIED TO THE SITE AT A RATE OF 13.8 POUNDS PER 1,000 SQUARE FEET. THE COMPOSITION OF THE FERTILIZER SHALL BE 10-10-10 (N-P205-K20) OR EQUIVALENT. LIMESTONE SHALL BE APPLIED TO THE SITE AT A RATE OF 138 POUNDS PER 1,000 SQUARE FEET

## SEEDING

THE COMPOSITION AND AMOUNT OF PERMANENT SEED APPLIED TO A SITE SHALL BE DETERMINED BY THE FOLLOWING TABLE

#### SEEDPOUNDS / 1,000 S.F.KENTUCKY BLUEGRASSO.46CREEPING RED FESCUEO.46PERENNIAL RYEGRASSO.11TOTAL1.03 MULCHING

MULCH SHALL BE APPLIED AT A RATE OF 70 LBS - 90 LBS PER 1,000 SQUARE FEET. THE MULCH SHALL BE INSTALLED AT A MINIMUM DEPTH OF 4 INCHES. THE SEEDED AREA SHALL BE MULCHED IMMEDIATELY AFTER SEED IS APPLIED. MULCHING DURING THE WINTER SEASON SHALL BE DOUBLE THE NORMAL AMOUNT. RECOMMENDATIONS


PERMANENT SEEDING IS RECOMMENDED TO BE COMPLETED IN THE SPRING. LATER SUMMER SEEDING IS ALLOWED IF COMPLETED PRIOR TO SEPTEMBER 1ST. IF SEEDING CANNOT BE ACCOMPLISHED DURING THE PERIODS RECOMMENDED FOR PERMANENT SEEDING, THEN THE CONTRACTOR SHALL PERFORM TEMPORARY SEEDING PER THE TEMPORARY SEEDING PLAN. CONCLUSION


PLEASE REFER TO THE MAINE EROSION AND SEDIMENT CONTROL BMP MANUAL FOR ADDITIONAL INFORMATION PERTAINING TO PERMANENT SEEDING AND MULCHING.

#### FEMPORARY SEED APPLICATION RATES SEED LBS / ACRE RECOMMENDED SEEDING DATES 8/15 TO 10/1 WINTER RYE 2.57 OATS 1.84 4/1 TO 7/1 8/15 TO 9/15 ANNUAL RYGRAS 0.92 4/1 TO 7/1 **SUDANGRASS** 5/15 TO 8/15 0.92 PERENNIAL 0.92 8/15 TO 9/15 7.17 LBS/ACRE TOTAL

PERMANENT SEED APPLICATION RATES SEED LBS / ACRE KENTUCKY BLUEGRASS 20.00 CREEPING RED FESCUE 20.00 PERENNIAL RYEGRASS 4.80 TOTAL 44.8 LBS/ACRE

CONSTRUCTION DRAWINGS





STONE CHECK DAM NOT TO SCALE

0.100


SEDIMENTS ONTO PUBLIC RIGHT-OF-WAY


1) CONTRACTOR SHALL ADD STONE TO ENTRANCE AS MUD/SILT MATERIAL ACCUMULATES 2) STONE SHALL BE 2"-3" COARSE AGGREGATE

3) CONSTRUCTION ENTRANCE SHALL BE GRADED TO NOT ALLOW ANY STORMWATER TO BE CONVEYED OFF SITE. IN SITUATIONS WHERE THIS IS NOT POSSIBLE, ANY STORMWATER CONVEYED OFFSITE SHALL BE TREATED OR RETAINED IN A MANNER APPROVED BY ENGINEER.


5) CONSTRUCTION ENTRANCE SHALL BE GRADED IN A MANNER THAT PREVENTS TRACKING OF

4) WHEN NECESSARY, ON-SITE VEHICLES SHALL HAVE THEIR WHEELS CLEANED PRIOR TO LEAVING





STABILIZED CONSTRUCTION ENTRANCI NOT TO SCALE



CATCH BASIN INLET PROTECTION NOT TO SCALE

ISSUED RELIMINARY COMMENT RESPON PRICING SET CONSTRUCTION REVISION AND

DRAWN BY: CHECKED BY: an SAVAGE drawing nc

DATE:

SCALE:

DESIGNED BY:

1053\_DETAI

12/5/20