## REFLECTED CEILING PLAN NOTES

1.) G.C. TO COORDINATE LOCATIONS OF PLUMBING CLEAN OUTS WITH ACCESS PANELS AS SHOWN ON REFLECTED CEILING PLANS

2.) G.C. TO PROVIDE ACCESS PANELS AS REQUIRED FOR ALL ELEMENTS (SPRINKLER, VALVES, ETC) NOT SHOWN ON THIS REFLECTED CEILING PLAN)

3.) G.C. TO PROVIDE METAL FRAMING AND BLOCKING REQUIRED FOR ALL ACCESS PANELS AND CONTROL JOINTS

RYAN J. SENATORE

© 2015 RYAN SENATOR

ARCHITECTURE

**TMENT** 

ARCHITECTURE

565 CONGRESS STREET

PORTLAND, MAINE 04101

207-650-6414

senatorearchitecture.com

STRUCTURAL:

77 Oak Street

207-774-4614

Structural Integrity

Portland, ME 04101

JULY 3, 201

RRT / RJS

AS NOTED

CONSULTANTS:

REVISIONS:

PROJECT No.

DRAWN BY:

CHECKED BY:

SHEET TITLE:

UNIT 201, 301

AND 401 PLANS

AND INTERIOR

**ELEVATIONS** 

SCALE:

FROM FLOOR TO FLOOR, INTERIOR ELEVATIONS GRAPHICALLY DEPICT ONE FLOOR ONLY, FOR HEIGHT INFORMATION REFER TO BUILDING SECTIONS AND WALL SECTIONS 2.) G.C. TO CONFRIM AND COORDINATE ALL ROUGH FRAMING DIMENSIONS FOR TUBS, SHOWERS, BUILT-IN FIXTURES ETC.

G.C. TO CONFRIM AND COORDINATE ALL CABINETRY AND APPLIANCES DIMENSIONS 3.) PROVIDE APPROPRIATE BLOCKING IN WALLS BEHIND ALL

1.) CEILING HEIGHTS. WINDOW HEAD AND SILL HEIGHTS VARY

FIXTURES, PARTITIONS AND ACCESSORIES. BLOCKING FOR GRAB BARS TO BE PROVIDED IN WALLS OF BATHROOMS IN

4.) PROVIDE MOISTURE RESISTANT GWB AT ALL WALLS AND CEILINGS IN BATHROOMS TYPICAL

5.) SET ALL CLOTHES WASHERS IN PANS WITH WATER SENSOR 6.) REFER TO ELECTRICAL AND MECHANICAL DRAWINGS FOR ADDITIONAL INFORMATION REGARDING, LIGHTING, DIFFUSERS,

7.) PROVIDE FIRE EXTINGUISHER ON BRACKET IN BASE CABINET BELOW KITCHEN SINK - TYPICAL

8.) HANG HOT WATER HEARER FROM CEILING ABOVE CLOTHES ROD IN CLOSET, PROVIDE UNISTRUT SUPPORTS ON TOP OF BOTTOM CHORDS OF TRUSSES PRIOR TO CEILING INSTALLATION

9.) WHERE DROPPED SOFFITS AND CEILINGS ARE SHOWN, THESE ARE IN ADDITION TO THE FIRE RATED GWB CEILING ABOVE WHICH IS PART OF THE RATED ASSEMBLY

10.) WHERE PLUMBING VALVES (TUB, SHOWER, ETC) ARE LOCATED IN FIRE RATED WALLS, PROVIDE FIRE RATED BOX IN WALL FOR VALVE TO BE INSTALLED WITHIN

CABINETRY AND APPLIANCE ABBREVIATIONS DB = DRAWER BASE

DRB = DOOR BASE SB = SINK BASE WC = WALL CABINET

UNIT NOTES

WC(24) = WALL CABINET 24" DEEP PU = PANTRY UNIT 24" DEEP OS = OPEN SHELVES RA = RANGE

DW = DISHWASHER REF = REFRIGERATOR

REFLECTED CEILING PLAN AND LIGHTING LEGEND


SYMBOL TAG DESCRIPTION A TROSS IKEA SURFACE MOUNT B SURFACE MOUNTED - TBD C SURFACE MOUNT - IN CLOSETS

D SURFACE MOUNTED ON WALL ABOVE DOOR ☐ E WALL SCONCE IN BATHROOM OVER VANITY SURFACE MOUNT - WET LOCATION H SURFACE MOUNT CENTER IN BEDROOMS

RECESSED DOWN LIGHT - WET LOCATION 

RECESSED CAN LIGHT FIXTURE

CEILING GRILLE



BATHROOM ELEVATIONS

SOLID 2X8 BLOCKING

FOR FUTURE INSTALLATION

- CURTAIN ROD

(2) TOWEL HOOKS 42" O.C. AFF. -

PROVIDE BLOCKING

