



REVISED 9/29/16

REPAIR THIS WATER DAMAGED BRICK FOUNDATION WALL.

AFTER ADEQUATELY SHORING EXTERIOR WALL ABOVE, REMOVE ALL CRUMBLING AND DETERIORATED BRICK TO THE POINTS WHERE SOLID UNDAUNAGED BRICK IS FOUND. REPLACE WITH NEW BRICK TO MATCH AND HI STRENGTH MORTAR. PAINT NEW BRICK TO MATCH EXISTING.

REVISED 9/29/16

NEW  
Tread depth  
10" with 3/4" nosing  
Riser height  
7 3/4"

NOTE: ALL EXTERIOR DECKS AND STAIRS ARE NEW CONSTRUCTION SEE S-DRAWINGS

42 Greenleaf Street  
South Elevation 1/4"=1'-0"

42 Greenleaf Street  
North Elevation 1/4"=1'-0"

4 Meeting House Lane, WEST BATH, MAINE 04550  
JAMES HOARE Architectural Design  
Phone (207) 843-6251 cell 751-2134

REVISIONS

1 2nd 20% ADDED NOTES RE REPAIRS TO FOUNDATION WALL, AND STAIR TREAD DEPTH AND RISER HEIGHT INFORMATION.

HARRIS EVANS ASSOCIATES  
42 GREENLEAF STREET  
PORTLAND, MAINE

DRAWINGS THIS SHEET

Remodeled Elevations

DATE	
Number	
Drawn By	JH
Checked By	

A-5

6/24/2016