

A-6  
ENTRY LANDING DETAILS

$\frac{1}{2}'' = 1'$

(4)  
1 1/4" CIRCULAR  
HANDRAIL SET @  
34"-38" ABOVE  
NOSING

Ledger Board 2x8  
(attached to house leaving  
1/2" drainage plane -  
Ledgerwork + SS WASHER  
1 of 6 2"x12" STRINGERS  
(2) 2"x8" FRAME  
(3) 2"x10" BEAM

2"x8" JOISTS  
IN GALVANIZED  
HANGERS

ENTRY

Guardrail @ 36"-40"  
Height

(2) DECK TENSIONERS

5/4" x 6" DECKING + STAIR  
MATERIAL TBD

SPACE BETWEEN PICKETS LESS THAN 4"

4"x4" GUARDRAIL POST (4)

1"x4" TRIM  
1"x10" TRIM

SPACE BETWEEN BALUSTERS  
LESS THAN 4 3/8"

(4) 1 1/4" CIRCULAR  
HANDRAIL (4)  
SET BETWEEN 34" + 38"  
ABOVE NOSING

STAIRS: 5 TREADS @ 10"  
6 RISES @ 6 2/3"

2"x12" STRINGERS

6"x6" PT

galvanized  
POST BASE

10" SONOTUBES (4)

STAIRS ATTACHED  
TO PT SLEEPER  
ATTACHED TO CEMENT  
PIER

