

Item : 0011

Exterior View



Qty : 6
Frame Size : 35 13/16" x 56 1/4"

Frame Size : 910 X 1429
Wood Species: Douglas Fir
Double Hung - Equal Split
Aluminum Clad - Exterior
Exterior Color: Hartford Green (HFGM)
Clear Wood Interior (Clear Wood)
Jamb : 6 9/16" (166)
Brick Mould : None
Includes Tilting Sash
Heat-Smart D 272 (HP1)
3.1 / 63-122 / 3.1
272/CLR
Black Stainless Steel Spacer (B63-122)
Bronze Hardware (BRZ)
Hartford Green Screen Frame (HFGM)
Integral Nailing Flange, Drip Cap applied (NFA)
Standard Packaging 76 cubic ft. each
(HFGM HP1 (272/CLR) SDL)

Location :
Rough Opening : 36 9/16" x 57"


25DSH - standard 25DH 3024
25DSH - standard 25DH 3024 - Heat-Smart D 272 (HP1) , Metal Clad Exterior, Hartford Green
Includes Aluminum Sill
Add for 6 9/16" Jamb
Includes Black Stainless Steel Spacer Bar (3.1 / 63-122 / 3.1)
Add for Upper Sash - (2W1H) Colonial 3/4" (19 mm) SDL (Ogee-Ogee) with Shallow Shadow Bar
Add for Lower Sash - (2W1H) Colonial 3/4" (19 mm) SDL (Ogee-Ogee) with Shallow Shadow Bar
NOTE: Grille Alignment - Equal lite
Add for Bronze Camlock (1 Per Unit)
Includes Hartford Green Full Screen - Standard Screen
Add for High Transparency Mesh
NFRFC: U-factor: 0.30 CR: 54 SHGC: 0.27 VT: 0.45

Casing not required

\$ 637.65
\$ 0.00
\$ 44.85
\$ 0.00
\$ 41.60
\$ 41.60
\$ 0.00
\$ 0.00
\$ 0.00
\$ 18.20
\$ 0.00

Item : 0014

Exterior View



Qty : 2
Frame Size : 35 7/16" x 56 1/4"

Bedroom EGRESS WINDOWS
CASEMENTS
LEFT HAND HINGE

WIDTH 35"
HEIGHT 56"
CLEAR OPENING 1,997 sq. INCHES
LOWEST POINT OF OPENING ABOVE FINISH 25"

Location : EGRESS

Rough Opening : 36 3/16" x 57"

Casing not required

Total Price for Qty -6 \$ 4703.40

28AC - custom CA1 0915 L \$ 547.30
28AC - custom CA1 0915 L Heat-Smart D 272 (HP1) , Metal Clad Exterior, Hartford Green \$ 37.70
Custom Size Cutting Charge \$ 0.00
Drawing Number - REQUIRED for custom grille \$ 42.90
Add for 6 9/16" Jamb \$ 0.00
Includes Black Stainless Steel Spacer Bar (3.1 / 63-130 / 3.1) \$ 0.00
Customized Grille : 4 Colonial Lites of 3/4" (19 mm) Simulated Divided Lite Grilles with Shallow Shadow Bar \$ 83.20
NOTE: All custom grilles require a drawing and pricing approval.
NOTE: Grille Alignment - Equal lite \$ 0.00
Add for Push Out Operable Unit (1) \$ 144.30
Add for Push Out - Multipoint \$ 39.00
Add for Clear Wood Swing Screen - Hinged Left with High Transparency Mesh \$ 170.30
NFRFC: U-factor: 0.28 CR: 59 SHGC: 0.26 VT: 0.43 \$ 0.00

EGRESS WINDOWS