

$\frac{1}{2}'' = 1'$

A-6

ENTRY LANDING DETAILS

(4) $\frac{1}{4}''$ CIRCULAR HANDRAIL SET @ 34-38" ABOVE NOSING

ENTRY

LEADER BOARD 2x8
(attached to house leaving $\frac{1}{2}''$ DRAINAGE PLANE -
LEADERBOARD + SS WASHERS)

2"x8" JOISTS IN GALVANIZED HANGERS

(2) 2"x8" FRAME
(3) 2"x10" BEAM

Guardrail @ 36"-40" Height

Space between balusters less than $4\frac{3}{8}''$

(4) $\frac{1}{4}''$ CIRCULAR HANDRAIL (4) SET BETWEEN 34" + 38" ABOVE NOSING

STAIRS: 5 TREADS @ 10" 6 RISES @ $6\frac{24}{32}''$ 2x12" STRINGERS

(2) DECK TENSIONERS

$\frac{5}{4}'' \times 6''$ DECKING + STAIR MATERIAL TBD
Space between pickets less than 4"

4"x4" GUARDRAIL POST (4)

1"x4" TRIM

ALL SONOTUBES SET AT 4' DEPTH FOR FROST PROTECTION

6"x6" PT
10" SONOTUBES (4)

galvanized POST BASE

STAIRS ATTACHED TO PT SLEEPER ATTACHED TO CEMENT PIER

