

WINDOW SCHEDULE

KEY	TYPE	ITEM	ROUGH OPENING (W X H)	GLAZING	CONSTRUCTION	LOCKSET	U-FACTOR	SHGC	REMARKS
A	CASEMENT	CXW155R	3'-0-1/2" X 5'-5-3/8"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	FIBERGLASS, WOODGRAIN FINISH	KEYED	.29	.32	EGRESS SIZE, CLEAR OPENABLE AREA OF 5.7 S.F.
B	CASEMENT	CXW155L	3'-0-1/2" X 5'-5-3/8"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	FIBERGLASS, SMOOTH FINISH	KEYED	.29	.32	EGRESS SIZE, CLEAR OPENABLE AREA OF 5.7 S.F.
C	CASEMENT	CXW155R	3'-0-1/2" X 5'-5-3/8"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	SOLID CORE	PASSAGE	.29	.32	EGRESS SIZE, CLEAR OPENABLE AREA OF 5.7 S.F.
D	AWNING	A335	3'-0-1/2" X 3'-5-1/4"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	SOLID CORE	PRIVACY	.29	.32	VENTING
E	CASEMENT	CXW155L	3'-0-1/2" X 5'-5-3/8"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	SOLID CORE	DUMMY	.29	.32	EGRESS SIZE, CLEAR OPENABLE AREA OF 5.7 S.F.
F	CASEMENT	CXW155R	3'-0-1/2" X 5'-5-3/8"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	SOLID CORE	PRIVACY	.29	.32	EGRESS SIZE, CLEAR OPENABLE AREA OF 5.7 S.F.
G	CASEMENT	CXW155R	3'-0-1/2" X 5'-5-3/8"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	SOLID CORE	PRIVACY	.29	.32	EGRESS SIZE, CLEAR OPENABLE AREA OF 5.7 S.F.
H	CASEMENT	CXW155R	3'-0-1/2" X 5'-5-3/8"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	SOLID CORE	DUMMY	.29	.32	EGRESS SIZE, CLEAR OPENABLE AREA OF 5.7 S.F.
I	CASEMENT	CXW155L	3'-0-1/2" X 5'-5-3/8"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	SOLID CORE	PRIVACY	.29	.32	EGRESS SIZE, CLEAR OPENABLE AREA OF 5.7 S.F.
J	CASEMENT	CXW155R	3'-0-1/2" X 5'-5-3/8"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	SOLID CORE	PRIVACY	.29	.32	EGRESS SIZE, CLEAR OPENABLE AREA OF 5.7 S.F.
K	AWNING	A335	3'-0-1/2" X 3'-5-1/4"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	SOLID CORE	PRIVACY	.29	.32	VENTING
L	CASEMENT	CXW155L	3'-0-1/2" X 5'-5-3/8"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	SOLID CORE	PRIVACY	.29	.32	EGRESS SIZE, CLEAR OPENABLE AREA OF 5.7 S.F.
M	CASEMENT	CXW155R	3'-0-1/2" X 5'-5-3/8"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	SOLID CORE	PRIVACY	.29	.32	EGRESS SIZE, CLEAR OPENABLE AREA OF 5.7 S.F.
N	CASEMENT	CXW155L	3'-0-1/2" X 5'-5-3/8"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	SOLID CORE	PRIVACY	.29	.32	EGRESS SIZE, CLEAR OPENABLE AREA OF 5.7 S.F.
O	CASEMENT	CXW155R	3'-0-1/2" X 5'-5-3/8"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	SOLID CORE	PRIVACY	.29	.32	EGRESS SIZE, CLEAR OPENABLE AREA OF 5.7 S.F.
P	CASEMENT	CXW155L	3'-0-1/2" X 5'-5-3/8"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	SOLID CORE	PRIVACY	.29	.32	EGRESS SIZE, CLEAR OPENABLE AREA OF 5.7 S.F.
Q	CASEMENT	CX145R	2'-8" X 4'-5-3/8"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	SOLID CORE	PRIVACY	.29	.32	EGRESS SIZE, CLEAR OPENABLE AREA OF 5.7 S.F.
R	CASEMENT	CX145L	2'-8" X 4'-5-3/8"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	SOLID CORE	PRIVACY	.29	.32	EGRESS SIZE, CLEAR OPENABLE AREA OF 5.7 S.F.
S	CASEMENT	CX145R	2'-8" X 4'-5-3/8"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	SOLID CORE	PRIVACY	.29	.32	EGRESS SIZE, CLEAR OPENABLE AREA OF 5.7 S.F.
T	CASEMENT	CX145L	2'-8" X 4'-5-3/8"	DOUBLE GLAZED HIGH PERFORMANCE LOW E4 GLASS	SOLID CORE	PRIVACY	.29	.32	EGRESS SIZE, CLEAR OPENABLE AREA OF 5.7 S.F.

DOOR SCHEDULE

KEY	TYPE	ROUGH OPENING (W X H)	GLAZING	CONSTRUCTION	LOCKSET
101	EXTERIOR RHHS	38-1/2" X 82-1/2"	LOW E FLUSH GLAZED	FIBERGLASS, WOODGRAIN FINISH	KEYED
102	EXTERIOR LHOS	34-1/2" X 81-5/8"	LOW E FLUSH GLAZED	FIBERGLASS, SMOOTH FINISH	KEYED
103	INTERIOR LHHS	38-1/2" X 82-1/2"	NONE	SOLID CORE	PASSAGE
104	INTERIOR LHHS	34-1/2" X 82-1/2"	NONE	SOLID CORE	PRIVACY
105	INTERIOR LHHS	34-1/2" X 82-1/2"	NONE	SOLID CORE	PRIVACY
106	INTERIOR PAIR OUTSWING	48" X 82-1/2"	NONE	SOLID CORE	DUMMY
107	INTERIOR POCKET	38-1/2" X 82-1/2"	NONE	SOLID CORE	NONE
108	INTERIOR LHHS	34-1/2" X 82-1/2"	NONE	SOLID CORE	PRIVACY
109	INTERIOR PAIR OUTSWING	48" X 82-1/2"	NONE	SOLID CORE	DUMMY
110	INTERIOR RHHS	34-1/2" X 82-1/2"	NONE	SOLID CORE	PRIVACY
111	INTERIOR RHHS	34-1/2" X 82-1/2"	NONE	SOLID CORE	PRIVACY
112	INTERIOR LHHS	34-1/2" X 82-1/2"	NONE	SOLID CORE	PRIVACY

BUILDING STATISTICS

BASEMENT: 769 SF.
 CEILING HEIGHT: 6'-5"
 VOLUME: 5,167 C.F.

FIRST FLOOR: 815 SF.
 CEILING HEIGHT: 9'-3"
 VOLUME: 7,538 C.F.

SECOND FLOOR: 815 SF.
 CEILING HEIGHT: 8'-9"
 VOLUME: 7,131 C.F.

THIRD FLOOR: 815 SF.
 CEILING HEIGHT: 7'-10" MAXIMUM
 VOLUME: 6,267 C.F.

OVERALL:
 TOTAL LIVING SPACE FLOOR AREA: 2,445 S.F.
 TOTAL BUILDING VOLUME: 26,103 C.F.