

ROOM	ROOM NAME	ROOM FINISH SCHEDULE						REMARKS	PARTIALS		
		WALLS			FLOOR	CEILING					
		WALL	DOOR	CEILING		HEIGHT	FINISH				
100	KITCHEN	1	1	2	1	10	25	33	-		
101	BAR	1	1	-	-	10	25	33	-		
102	ITCHEN	4	4	3	3	10	25	32	-		
103	COOLER STORAGE AND BREAKING	5	5	5	5	-	22	34	-		
104	REG ROOM	4	3	3	3	10	25	32	-		
105	OFFICE	1	1	3	3	10	25	31	-		
106	BATHROOM	2	1	1	1	11	25	31	-		
107	BATHROOM	2	1	1	1	11	25	31	-		
108	CORRIDOR	1	1	1	1	10	25	31	-		

FINISH SCHEDULE KEY	
WALLS	
1	CEILING PAINTED
2	CMU - PAINTED
3	CMU - MESH / FIBER REINFORCED PLASTER / PANEL
4	CMU - PAINTED EPOXY PAINT
5	
6	
7	
8	
9	
10	
BASE	
11	MVLS COVE BASE
12	BALUNOSE TRIZ BASE
13	
14	
FLOORS	
20	POURED CONCRETE WITH SEALER AND ANTI-ABR. COMPLETES
21	SEALED CONCRETE WORK-UP FINISH
22	WOOD PANEL FLOOR
23	POSSIBLE
24	
25	
26	
27	
CEILING	
31	CEILING - PAINTED
32	2" X 2" CEILING / ACUSTICAL CEILING TILE WITH GRID SYSTEM
33	2" X 2" CEILING / ACUSTICAL CEILING TILE WITH GRID SYSTEM
34	EXPOSED CEILING - PAINTING TRUSSES, BEAMS AND OTHER ELEMENTS
35	EXPOSED PANEL CEILING

ROOM FINISH GENERAL NOTES

1. ALSO SEE INTERIOR ELEVATIONS FOR GRAPHICAL NOTATIONS OF EXTENT OF FINISHES
2. INSTALL MOISTURE RESISTANT WALLS AND MOISTURE RESISTANT GYPSUM ALL AREAS WHERE PLUMBING FITTINGS (SINK, TOILET, AND WALK-IN CUPBOARD)
3. CLOSETS SHALL BE FINISHED AS THE ROOMS THEY SERVE.
4. PROVIDE APPROPRIATE BLOCKING ON WALLS OF ALL BATHROOMS BEHIND FIXTURES, PARTITIONS AND ACCESSORIES. PROVIDE BLOCKING FOR CABS BEHIND WALLS OF BATHROOMS.
5. PROVIDE APPROPRIATE BLOCKING ON WALLS FOR COOLER STOPS.
6. BOTTOM EDGE OF CAB ON WALL SURFACES TO BE HELD UP 1/2" FROM CONCRETE FLOOR SURFACES.
7. PROVIDE WALL TRANSITION STRIPS AT ALL FLOOR TRANSITIONS UNLESS OTHERWISE NOTED.
8. UNLESS OTHERWISE NOTED BY DRAWINGS THE TYPICAL WALL TYPE IS 'A', ALL OTHER PARTITION TYPES WILL BE INDICATED.
9. VERIFY UNDERLAYMENT MEETS MANUFACTURERS SPECIFICATIONS AT RESILIENT FLOORING.

PAINT SCHEDULE KEY	
001	001.00
01	XXXXX
02	XXXXX
03	XXXXX
04	XXXXX



RYAN SENATORE ARCHITECTURE
 988 CONGRESS STREET
 PORTLAND, MAINE 04101
 207-655-8414
 senatore@rsaarch.com

CONSULTANTS:

REVISIONS:
PROGRESS PRINT ONLY
 Not for Construction
 AUGUST 23, 2017

DATE:

PROJECT No. 1733

DRAWN BY: RRT, RJS, JPF

CHECKED BY: RJS

SCALE: AS NOTED

SHEET TITLE:
FINISH SCHEDULE

A7-1