


Viessmann Manufacturing
Company Inc.
Waterloo, ON Canada
1-800-387-7373
www.viessmann.ca

Viessmann Manufacturing
Company (U.S.) Inc.
Warwick, RI U.S.A.
1-800-288-0667
www.viessmann.us

Technical Data



Vitodens 222-F, B2TA gas-fired floor standing condensing boiler and DHW heating system

Model	B2TA	19	35
Min. Input	MBH	12	19
Max. Input	MBH	67	125
Max. Allowable Working Pressure	psig	45	45
Dimension			
Width	in.	23.5	23.5
Height	in.	65.5	65.5
Depth	in.	23.5	23.5
DHW Storage Tank			
Capacity	USG	26.5	26.5
Max. Allowable Working Pressure	psig	150	150
Continuous Draw Rate*	gpm	1.8	3.3
Max. Draw Rate* (over 10 min. period)	gal	44	60
Weight	lbs	313	313

* Based on a temperature rise of 70 °F (50 °F to 120 °F).
Information subject to change without notice.

