



1 FIRST FLOOR /GARAGE
 SCALE: 1/4" = 1'-0"

FIRE BLOCKING AND DRAFT STOPPING

PROVIDE FIRE BLOCKING AND DRAFT STOPPING IN WALL AND CEILING ASSEMBLIES TO DIVIDE ASSEMBLIES BETWEEN FLOORS, ATTIC, AND ROOF.

FIRE BLOCKING SHALL BE PROVIDED IN CONCEALED SPACES OF WALLS AND PARTITIONS INCLUDING SOFFITS AND STAIRWAYS, VERTICALLY AT CEILING AND FLAT LEVELS; AND HORIZONTALLY AT INTERVALS NOT EXCEEDING 10'.

FIRE BLOCKING SHALL BE PROVIDED IN CONCEALED SPACES BETWEEN CONCEALED VERTICAL STUD WALL SPACES AND CONCEALED HORIZONTAL SPACES SUCH AS OCCUR AT SOFFITS, DROP CEILINGS, COVE CEILINGS, AND SIMILAR LOCATIONS.

PENETRATIONS INTO OR THROUGH FIRE WALLS, FIRE BARRIERS, SMOKE BARRIERS AND FIRE PARTITIONS SHALL BE PROTECTED WITH APPROVED FIRESTOP SYSTEM PER IBC SECTION 714.

JP SHERIDAN LLC APARTMENT
 PORTLAND, ME
 88 WALNUT STREET

WHIPPLE CALLENDER ARCHITECTS

PO BOX 1276
 PORTLAND, ME 04104
 P 207.775.2696
 F 207.775.3631
 www.whipplecallender.com

DATE	DESCRIPTION
8-3-17	PERMITTING SET
9-11-17	CONSTRUCTION SET
9-21-17	REVISION TO GARAGE CANOPY LOCATION
10-16-17	REVISION FOR FINISHING FT. & MISC INT.

DATE: 12/22/17
 CHECKED BY: AEC
 DRAWN BY: AEC / NC
 JOB: 16-EHP
 SHEET TITLE: FIRST FLOOR /GARAGE PLAN

A1.1

12-18-17 ISSUED
 11-10-17 ISSUED
 9-21-17 REVISIONS
 9-11-17 FOR CONSTRUCTION