Date: 12/30/15

1 / E-2 WEST ELEVATION
1/4" = 1'-0"

2 / E-2 EAST ELEVATION
1/4" = 1'-0"

3 / E-2 NORTH ELEVATION
1/4" = 1'-0"

4 / E-2 SOUTH ELEVATION
1/4" = 1'-0"

RESTORATION KEY NOTES

- R1 NEW PAINTED WOOD CLAPBOARDS OVER NEW EXTERIOR PLYWOOD SHEATHING.
- R2 NEW WOOD RAKE AND EAVE RETURN TO MATCH PROFILE OF EXISTING EAVE RETURN REMNANT.
- R3 NEW PAINTED WOOD CORNER BOARDS TO MATCH EXISTING.
- R4 NEW PAINTED WOOD STOREFRONT SURROUND TO MATCH EXISTING.
- R5 RESTORED FLUTED GLASS TRANSOM WINDOW.
- R6 NEW REPLICA FLUTED GLASS TRANSOM WINDOW.
- R7 NEW PAINTED WOOD STOREFRONT SYSTEM BY "DURATHERM" - SEE WINDOW SCHEDULE.
- R8 NEW CUSTOM BUILT-UP PAINTED WOOD PANELS.
- R9 NEW PAINTED WOOD ENTRY DOOR BY "DURATHERM" - SEE DOOR SCHEDULE.
- R10 NEW METAL CLAD WOOD WINDOW BY "MARVIN" - SEE WINDOW SCHEDULE.
- R11 NEW ASPHALT SHINGLE ROOF OVER NEW EXTERIOR PLYWOOD SHEATHING.
- R12 NEW SHED DORMER.
- R13 RESTORE EXISTING BRICK / EXPOSED FIELDSTONE FOUNDATION.
- R14 NEW CONCRETE GRADE BEAM - SEE STRUCTURAL DRAWINGS.
- R15 NEW 3" DIAMETER PAINTED ALUMINUM DOWNSPOUT.
- R16 NEW PAINTED PVC PLUMBING VENT.
- R17 NEW MEMBRANE ROOF OVER NEW EXTERIOR PLYWOOD SHEATHING.
- R18 NEW PAINTED GALVANIZED STEEL PARAPET FLASHING AT PARAPET.
- R19 NEW 1'-0" WIDE BITUMINOUS STRIP TO MATCH PAVING TO REMAIN.
- R20 NEW PAINTED PLYWOOD SIGN.

ttl-architects, llc
28 DANFORTH STREET
SUITE 213
PORTLAND, MAINE 04101
TEL. 207.761.9662
FAX. 207.761.9696

REGISTERED ARCHITECT
JOHN TURK
No. 2059
STATE OF MAINE

Rehabilitation of the Main Block and Ell at
131 Washington Avenue
Jonathan Edwards
Portland, Maine

Date: 2 October 2015
Scale: As Shown
Revisions:

Title:
Exterior Elevations

Sheet No: A-2

PERMIT SET

0' 5' 10' 25' 50'