1ST FLOOR FRAMING PLAN

SCALE 1/8"=1'-0"

NOTES:

1. SEE GENERAL NOTES FOR ADDITIONAL INFORMATION.
2. (E) INDICATES EXISTING, (N) INDICATES NEW, (R) INDICATES REMOVE.
3. ALL WOOD COLUMNS IN 2x6 WALLS SHALL BE 3-2x6 AND IN 2x4 WALLS SHALL BE 3-2x4 UNLESS NOTED OTHERWISE ON PLANS.
4. ALL BEAMS ARE FLUSH, UNO.
5. ALL HEADERS IN 2x6 BEARING WALLS ARE (3) 2x6, UNO.
6. ALL HEADERS IN 2x4 BEARING WALLS ARE (2) 2x8, UNO.
7. AVOID MAJOR RE-WORK OF EXISTING ASPHALT AS POSSIBLE. REPAIR AS NEEDED.
8. REPAIR/PATCH THRESHOLDS AS NEEDED FOR CLEAN TRANSITION -TYP.

FOR PERMIT

Structural Integrity Consulting Engineers, Inc.
77 Oak Street
Portland, ME, 04101
p. 207-774-4614
f. 866-793-7835
www.structuralinteg.com

BUILD WITH CONFIDENCE

© 2017 Structural Integrity Consulting Engineers, Inc.

SI # 16-0239

STATE OF MAINE
AARON C. JONES
No. 10968
LICENSED
PROFESSIONAL ENGINEER
March 8, 2017

Date: 03/21/17

© 2015 RYAN SENATORE ARCHITECTURE

123 WASHINGTON

123 WASHINGTON AVENUE
PORTLAND, MAINE

RSA
RYAN SENATORE
ARCHITECTURE
565 CONGRESS ST. SUITE 304
PORTLAND, MAINE 04101
207-650-6414
senatorearchitecture.com

CONSULTANTS:

STRUCTURAL:
Structural Integrity
77 Oak Street
Portland, ME 04101
207-774-4614

REVISIONS:

DATE:	March 8, 2017
PROJECT No.	1638
DRAWN BY:	WMc
CHECKED BY:	ACJ
SCALE:	AS NOTED

SHEET TITLE:

FIRST FLOOR FRAMING PLAN

S-1.1