



© 2017 RYAN SENATORE ARCHITECTURE

MAINE CRAFT DISTILLING
 123 WASHINGTON STREET
 PORTLAND, MAINE



RYAN SENATORE
 ARCHITECTURE
 565 CONGRESS STREET
 PORTLAND, MAINE 04101
 207-650-6414
 senatorearchitecture.com

CONSULTANTS:

REVISIONS:

DATE: FEBRUARY 14, 2017

PROJECT No. 1666

DRAWN BY: RRT

CHECKED BY: RJS

SCALE: AS NOTED

SHEET TITLE:
**WALL TYPES
 AND
 ASSEMBLIES**

A0-1

GRAPHIC DEPICTION		DESCRIPTION			
		- LAYER OF TYPE 'X' 5/8" GWB - 6" LIGHT GAUGE METAL STUDS AT 24" O.C. - 5 1/2" SOUND BATT INSULATION - LAYER OF TYPE 'X' 5/8" GWB			
TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING	
1A	1 HR	V450	50-54	N/A	

GRAPHIC DEPICTION		DESCRIPTION			
		- LAYER OF 5/8" GWB - 6" LIGHT GAUGE METAL STUDS AT 16" O.C. - 5 1/2" SOUND BATT INSULATION - LAYER OF 5/8" GWB			
TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING	
NC	N/A	N/A		N/A	

GRAPHIC DEPICTION		DESCRIPTION			
		- LAYER OF 5/8" GWB - 3 5/8" LIGHT GAUGE METAL STUDS AT 16" O.C. - 3 1/2" SOUND BATT INSULATION - LAYER OF 5/8" GWB			
TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING	
NB	N/A	N/A		N/A	

GRAPHIC DEPICTION		DESCRIPTION			
		- LAYER OF 5/8" GWB - 3 5/8" LIGHT GAUGE METAL STUDS AT 16" O.C. - LAYER OF 5/8" GWB			
TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING	
NA	N/A	N/A		N/A	

WALL TYPE NOTES

- 1.) REFER TO STRUCTURAL DRAWINGS FOR STUD SIZE AND SPACING
- 2.) INSTALL WATER RESISTANT GYPSUM WALLBOARD IN ALL RESTROOMS AND TOILET ROOM WALLS AND CEILINGS, AND AT ANY WALL WITH PLUMBING FIXTURES
- 3.) PROVIDE 1/2" GWB BEHIND ALL TUBS AND SHOWERS AT EXTERIOR WALLS AND FIRE RATED ASSEMBLIES. PROVIDE ADDITIONAL LAYER OF GWB TO COVER TUB AND SHOWER FLANGE. EXTEND ADDED LAYER ALONG ADJACENT WALLS AND ADJUST DOOR JAMB WIDTHS AS REQUIRED.
- 4.) WHEN TWO ADJACENT WALL TYPES HAVE DIFFERING NUMBERS OF LAYERS OF GWB, THE FINISHED FACE OF GWB MUST FORM ONE CONTINUOUS PLANE. ADJUST STUD PLANE LOCATION AS REQUIRED TO ACHIEVE THE CONTINUOUS PLANE.
- 5.) HOLD BOTTOM OF GWB UP 1/2" FROM CONCRETE, PROVIDE SEALANT AT JOINT.
- 6.) ALL WALL TYPES WITH AN INSULATION COMPONENT TO BE ACOUSTICALLY SEALED