Reviewed for Code Compliance
Inspections Division
Portland, Maine
Date: 05/23/17

DOOR SCHEDULE

DOOR NOTES:

1.) ALL EXTERIOR GLAZING TO BE LOW-E ARGON FILLED INSULATED GLAZING UNITS

2.) FRAME ALL OPENINGS WITH ELEVATIONS

3.) SEAL EXTERIOR DOORS TO ROUGH OPENING WITH LOW EXPANDING FOAM INSULATION - SEE DETAILS

4.) ALL DOOR HARDWARE TO BE 'LEVER' TYPE

5.) ALL EXTERIOR DOORS TO BE WEATHERSTRIPPED

1 DOOR TYPES
1/4" = 1'-0"

FRAME TYPES

1
STEEL

GLAZING SCHEDULE

KEY	GLAZING TYPE
GL-1	INSULATED CLEAR TEMPERED GLAZING
GL-2	FIRE RATED INSULATED GLAZING
GL-3	CLEAR TEMPERED GLASS
GL-4	CLEAR INSULATED TEMPERED GLASS
GL-5	FIRE RATED GLAZING

DOOR SCHEDULE

DOOR							FRAME					GENERAL			
		SIZE							DETAILS						
DOOR NO.	TYPE	WIDTH	HEIGHT	THICKNESS	MATERIAL	FINISH	INSULATED	TYPE	MATERIAL	THRESHOLD	HEAD	JAMB	SILL	CLOSER	FIRE RATING (MINUTES)		REMARKS
121.1	C	12'-0"	8'-0"	1-3/4"	AL	PTD	-	-	-	AL	-	-	-	-	-	-	FULL GLASS OVERHEAD DOOR WITH CHAIN PULL, LOCK
121.2	D	12'-0"	8'-0"	-	STL	PTD	-	-	STL	-	-	-	-	Y	60	-	FIRE RATED OVERHEAD ROLLING DOOR WITH AUTOMATIC CLOSER TIED TO FIRE ALARM SYSTEM WITH LASER EYE SAFTEY FEATURE, OVERHEAD DOOR MODEL 631, FUSEABLE LINK
121.3	E	3'-0"	7'-0"	1-3/4"	STL	PTD	Y	1	STL	AL	-	-	-	Y	-	-	THERMALLY BROKEN STEEL DOOR WITH PANIC HARDWARE
1 124.1	F	6'-0'	7'-0"	1-3/4"	STL	PTD	Y	2	STL	-	-	-	-	Y	60	-	
125.1	B	3'-0"	7'-0"	1-3/4"	STL	PTD	Y	1	STL	AL	-	-	-	Y	60	-	PANIC HARDWARE
127.1	A	3'-0"	7'-0"	1-3/4"	WD	CLR	Y	1	STL	-	-	-	-	Y	-	-	
128.1	A	3'-0"	7'-0"	1-3/4"	WD	CLR	Y	1	STL	-	-	-	-	Y	-	-	
131.1	B	3'-0"	7'-0"	1-3/4"	STL	PTD	Y	1	STL	-	-	-	-	Y	-	-	-
132.1	A	3'-0"	7'-0"	1-3/4"	WD	CLR	Y	1	STL	-	-	-	-	-	-	-	
133.1	A	3'-0"	7'-0"	1-3/4"	WD	CLR	Y	1	STL	-	-	-	-	-	-	-	

HARDWARE KEY
MLS - MORTISE LOCK SET
LS - LOCK SET
PR - PRIVACY SET
PS - PASSAGE SET
LP - LEVER PULL
PH - PEEPHOLE LENSE

NOTE: FOR DOOR HARDWARE SEE DOOR HARDWARE SPECIFICATION SECTION 08710

WINDOW SCHEDULE

1 WINDOW TYPES
1/4" = 1'-0"

WINDOW SCHEDULE LEGEND

T = TEMPERED GLASS
FG = FIBERGLASS
AL = ALUMINUM
DH = DOUBLE HUNG
AW = AWNING
LV = LOUVER
F = FIXED
GL = GLIDER

WINDOW SCHEDULE

KEY	ACTION	ROUGH * OPENING (WxH) VIF	*CALCULATED HEIGHT FROM SUB FLOOR	DETAILS HEAD	JAMB	SILL	MATERIAL	FINISH	REMARKS
A	F	6'-1" X 4'-1"	-	-	-	-	STL	PTD	45 MINUTE FIRE RATED WINDOW AND FRAME, CLEAR FIRE RATED, TEMPERED GLASS

FOR TEMPERED GLASS LOCATIONS SEE WINDOW ELEVATION TYPES
FOR MASONRY OPENING DIMENSIONS COORDINATE COURSING WITH EXTERIOR ELEVATION SHEETS AND PLAN AND SECTION DETAIL SHEETS

WINDOW NOTES:

1.) ALL GLAZING LOCATED WITHIN 18" OF FINISHED FLOOR TO BE TEMPERED GLASS

REGISTERED ARCHITECT
RYAN J. SENATORE
No. 3322
STATE OF MAINE

© 2017 RYAN SENATORE ARCHITECTURE

MAINE CRAFT DISTILLING
123 WASHINGTON STREET
PORTLAND, MAINE

RSA
RYAN SENATORE
ARCHITECTURE
565 CONGRESS STREET
PORTLAND, MAINE 04101
207-650-6414
senatorearchitecture.com

CONSULTANTS:

REVISIONS:
REVISON #1 -05 / 17 / 17

DATE:	FEBRUARY 14, 2017
PROJECT No.	1666
DRAWN BY:	RRT
CHECKED BY:	RJS
SCALE:	AS NOTED

SHEET TITLE:
DOOR AND WINDOW SCHEDULE

A7-0