



© 2017 RYAN SENATORE ARCHITECTURE

93 WASHINGTON AVE.  
PORTLAND, MAINE



RYAN SENATORE  
**ARCHITECTURE**  
565 CONGRESS STREET  
PORTLAND, MAINE 04101  
207-650-6414  
senatorearchitecture.com

CONSULTANTS:

REVISIONS:

DATE: JULY 22, 2017

PROJECT No. 1626

DRAWN BY: RJS / RRT

CHECKED BY: RJS

SCALE: AS NOTED

SHEET TITLE:  
**FINISH SCHEDULE**

**A7-2**

ROOM FINISH SCHEDULE											
ROOM #	ROOM NAME	WALLS					FLOOR	CEILINGS			REMARKS
		NORTH	EAST	SOUTH	WEST	BASE		MATL.	HEIGHT	RATING	
100	CORRIDOR	1	1	1	1	10	20	31	-	-	
101	RETAIL 1	1	1	1	1	10	20	30	-	-	
102	RETAIL 2	1	1	1	1	10	20	30	-	-	
103	RETAIL 3	1	1	1	1	10	20	30	-	-	
104	RETAIL 4	1	1	1	1	10	20	30	-	-	
105	RETAIL 5	1	1	1	1	10	20	30	-	-	
106	UNISEX TOILET	2	2	2	2	10	20	31	-	-	
107	UNISEX ADA TOILET	2	2	2	2	10	20	31	-	-	

FINISH SCHEDULE KEY	
<b>WALLS</b>	
1	GWB - PAINTED
2	MOISTURE RESISTANT GWB - PAINTED
<b>BASE</b>	
10	VINYL BASE
<b>FLOORS</b>	
20	VINYL PLANK FLOORING
<b>CEILINGS</b>	
30	GWB - PAINTED
31	2'X2' ACT CEILING TILES

ROOM FINISH GENERAL NOTES	
1	ALSO SEE INTERIOR ELEVATIONS FOR GRAPHIC DEPICTION'S OF EXTENT OF FINISHES
2	INSTALL MOISTURE RESISTANT (MOLD AND MILDEW RESISTANT) GWB IN ALL AREAS WHERE PLUMBING FIXTURES EXIST (CEILING AND WALLS IN BATHROOMS)
3	CLOSETS SHALL BE FINISHED AS THE ROOMS THEY SERVICE
5	PROVIDE APPROPRIATE BLOCKING IN WALLS OF ALL BATHROOMS BEHIND FIXTURES, PARTITIONS AND ACCESSORIES. PROVIDE BLOCKING FOR GRAB BARS IN WALLS OF BATHROOMS
6	PROVIDE APPROPRIATE BLOCKING IN WALLS FOR DOOR STOPS
8	UNLESS OTHERWISE NOTED IN DRAWINGS THE TYPICAL WALL TYPE IS 'NA'. ALL OTHER PARTITION TYPES WILL BE INDICATED.
9	VERIFY UNDERLAYMENT MEETS MANUFACTURERS SPECIFICATION AT RESILIENT FLOORING
10	GENERAL CONTRACTOR TO INCLUDE A MINIMUM OF 6 (SIX) INTERIOR PAINT COLORS TO BE USED THROUGHOUT THE BUILDING
11	PROVIDE HARDWOOD TRANSITIONS (SILLS) AT DOOR SILLS WHERE FLOORING TRANSITIONS FROM HARDWOOD TO RUBBER FLOORING WITH ACCESSIBLE PROFILE

PAINT SCHEDULE KEY	
TAG	COLOR
P1	XXXXX
P2	XXXXX
P3	XXXXX
P4	XXXXX
P5	XXXXX
P6	XXXXX
P7	XXXXX
P8	XXXXX
P9	XXXXX