

DIVISION: 07 00 00 – THERMAL AND MOISTURE PROTECTION**Section: 07 21 00 – Thermal Insulation****GACO WESTERN, LLC**
1245 CHAPMAN DRIVE
WAUKESHA, WISCONSIN 53186
(262) 542-8072
www.gacowallfoam.com**REPORT SUBJECT:****Gaco F1850 Spray-applied Polyurethane Insulation****1.0 SCOPE OF EVALUATION**

This Research Report addresses compliance with the following Codes:

- 2012[2009] *International Building Code® (IBC)*
- 2012[2009] *International Residential Code® (IRC)*
- 2012[2009] *International Energy Conservation Code® (IECC)*

Gaco F1850 has been evaluated for the following properties:

- Surface-burning characteristics
- Physical properties
- Thermal resistance
- Air permeability
- Air Barrier
- Vapor permeance
- Alternative to thermal barriers
- Alternative to ignition barriers
- Duct insulation

See Table 1 for applicable Code sections related to these properties.

NOTE: This report references 2012 Code sections with [2009] Code sections shown in brackets where they differ.

2.0 USES

Gaco F1850 spray-applied polyurethane foam insulation is used as a nonstructural thermal insulating material on or in interior and exterior walls, floors, ceilings, and roofs. When used in exterior walls of

buildings constructed under the IBC, its use is limited to Type V-B construction.

Under the IRC, the insulation may be used as air-impermeable insulation when installed in accordance with Section 3.2.3. The insulation may also be used as an air barrier in accordance with IECC Section C402.4.1.2.1, when installed as described in Section 3.2.4.

The insulation may be used as vapor retarder as described in Section 3.2.5.

The insulation may be used as duct insulation material when installed as described in Section 4.5.

3.0 DESCRIPTION**3.1 Materials:**

3.1.1 Gaco F1850: Gaco F1850 insulation is a closed cell, medium-density, polyurethane foam plastic. The insulation is a two-component, spray-applied foam plastic with a nominal in-place density of 2.1 pcf. The insulation is produced in the field by combining a polymeric isocyanate (A component) with a resin (B component). The insulation liquid components are supplied in 55-gallon drums and 250-gallon totes, and must be stored at temperatures between 50°F and 100°F. The resin (B component) must be protected from freezing temperatures. Gaco F1850 insulation has a shelf life of 1 year on the polymeric isocyanate (A component) and 6 months on the resin (B component) when stored in factory-sealed containers at these temperatures.

3.1.2 DC 315 Intumescent Coating: DC 315 intumescent coating, manufactured by IFTI, Paint to Protect, is a water-based coating supplied in 5-gallon pails and 55-gallon drums. The coating material has a shelf life of 24 months when stored in factory-sealed containers at a temperature between 41°F to 95°F.

3.2 Performance Characteristics:

3.2.1 Surface Burning Characteristics: The insulation, at a maximum thickness of 4 in. and a nominal density of 2.1 pcf, has a flame-spread index of 25 or less and a smoke-developed index of 450 or less when tested in accordance with ASTM E84. Thicknesses of up to 9-1/2 in. in ceilings and floors and 7-1/2 in. in vertical surfaces are recognized based on full scale fire performance testing in accordance with NFPA 286. When the insulation is separated from the interior living space of the building with minimum 1/2 in. thick gypsum board, the maximum thickness is not limited.

3.2.2 Thermal Resistance: The insulation has thermal resistance (R-value) at a mean temperature of 75°F as shown in Table 2.

3.2.3 Air Permeability: Gaco F1850 insulation, at a minimum thickness of 1 in., is considered air-impermeable insulation in accordance with Section R202 and R806.5 [R806.4] of the IRC, based on testing in accordance with ASTM E2178.

3.2.4 Air Barrier Material: Gaco F1850 insulation, at a minimum thickness of 1 in., is considered air-barrier material in accordance with Section C402.4.1.2.1 of the IECC, based on testing in accordance with ASTM E2178.

3.2.5 Vapor Permeance: Gaco F1850 has a vapor permeance of less than 1 perm (5.7×10^{-11} kg/Pa-s- m^2) at a minimum thickness of 0.44 in. and may be used where a Class II vapor retarder is required by the applicable code.

4.0 INSTALLATION

4.1 General:

Gaco F1850 must be installed in accordance with the manufacturer's published installation instructions, the applicable Code, and this Research Report. The manufacturer's published installation instructions and this Research Report must be strictly adhered to, and a copy of the instructions must be available on the jobsite during installation.

4.2 Application:

Gaco F1850 insulation is spray-applied on the jobsite using a volumetric positive displacement pump as identified in the Gaco Western application

instructions. The insulation must be applied when the ambient temperature is greater than 32°F. The insulation must not be used in areas that have a maximum in-service temperature greater than 200°F. The foam plastic must not be used in electrical outlet or junction boxes or in contact with water, rain or soil. The foam plastic must not be sprayed onto a substrate that is wet, or covered with frost or ice, loose scales, rust, oil, or grease. The insulation must be protected from the weather during and after application. The insulation may be applied to the maximum thickness in a single pass.

4.3 Thermal Barrier:

4.3.1 Application with a Prescriptive Thermal Barrier: Gaco F1850 insulation must be separated from the interior living space of the building by an approved thermal barrier of 1/2 in. thick gypsum board or an equivalent 15-minute thermal barrier complying with, and installed in accordance with, IBC Section 2603.4 or IRC Section R316.4. Exceptions are provided in Sections 4.3.2 and 4.4.

When the insulation is separated from the interior living space of the building with minimum 1/2 in. thick gypsum board, the maximum thickness is not limited.

4.3.2 Application without a Prescriptive Thermal Barrier: Gaco F1850 insulation may be installed without the 15-minute thermal barrier prescribed in IBC Section 2603.4 and IRC Section R316.4, when installed as described in this section. The thickness of the foam plastics insulation applied to the underside of the roofs, ceilings, or floors must not exceed 9-1/2 in. and applied to vertical wall surfaces must not exceed 7-1/2 in. The insulation must be covered on all exposed surfaces with DC 315 intumescent coating at a nominal wet film thickness of 18 mils (dry film thickness of 12 mils). The coating must be applied over the insulation in accordance with the coating manufacturer's instructions and this report. Surfaces to be coated must be dry, clean, and free of dirt, loose debris, and other substances that could interfere with the adhesion of the coating. The coating is applied with low-pressure airless spray equipment.

4.4 Attics and Crawl Spaces:

The insulation may be applied in attics and crawl spaces as described in either Section 4.4.1 or 4.4.2. When foam insulation is installed in an attic or crawl

space in accordance with this section, a thermal barrier, as described in Section 4.3.1, is not required between the foam plastic insulation and the attic or crawl space but is required between the insulation and the interior living space.

4.4.1 Application with a Prescriptive Ignition Barrier: When Gaco F1850 insulation is installed within attics and crawl spaces where entry is made only for service of utilities, the ignition barrier must be installed in accordance with IBC Section 2603.4.1.6 or IRC Section R316.5.3 or R316.5.4, as applicable. The ignition barrier must be consistent with the requirements for the type of construction required by the applicable Code and must be installed in a manner so the foam plastic insulation is not exposed. Gaco F1850 insulation as described in this section may be installed in unvented attics in accordance with IRC Section R806.5 [R806.4] at a minimum thickness of 1.0 inch.

4.4.2 Application without a Prescriptive Ignition Barrier:

4.4.2.1 General: Gaco F1850 insulation may be installed in attics and crawl spaces, without the ignition barrier prescribed in IBC Section 2603.4.1.6 and IRC Sections R316.5.3 and R316.5.4, subject to the following conditions:

- a. Entry to the attic or crawl space is only to service utilities, and no storage is permitted.
- b. There are no interconnected attic or crawl space areas.
- c. Air in the attic or crawl space is not circulated to other parts of the building.
- d. Under-floor (crawl space) ventilation is provided when required by IBC Section 1203.3 or IRC Section R408.1, as applicable.
- e. Attic ventilation is provided when required by IBC Section 1203.2 or IRC Section R806, except when air-impermeable insulation is permitted in unvented attics in accordance with IRC Section R806.5 [R806.4] of the IRC.
- f. Combustion air is provided in accordance with IMC (International Mechanical Code) Section 701 [Sections 701 and 703].

Gaco F1850 is an air impermeable insulation and may be installed in unvented attics, as described in this section, in accordance with IRC Section R806.5 [R806.4], when applied at a minimum thickness of 1 inch (25.4 mm).

4.4.2.2 Application of Insulation: Gaco F1850 insulation may be spray-applied to the underside of the roof sheathing and/or rafters in attics; the underside of wood floors in crawl spaces; and to vertical surfaces in both attics and crawl spaces, as described in this section. The thickness of the foam plastics applied to the underside of the top of the space must not exceed 10 in. and to vertical surfaces must not exceed 8 in. The insulation may be installed without prescriptive ignition barrier required by IBC Section 2603.4.1.6 or IRC Section R316.5.3 and R316.5.4 or a protective coating.

4.4.2.3 Use on Attic Floors: Gaco F1850 insulation may be installed exposed (no coating) at a maximum thickness of 10 in. between and over the joists in attic floors. The insulation must be separated from the interior living space by an approved thermal barrier. The insulation may be installed without the prescriptive ignition barrier required by IBC Section 2603.4 and IRC Section R316.5.3 or protective coating.

4.5 Duct Insulation:

Gaco F1850 may be applied to residential ducts in attics and crawl spaces in compliance with IRC Section M1601.3. The insulation must be protected in accordance with the ignition barrier requirements of either Section 4.4.1 or 4.4.2.

5.0 CONDITIONS OF USE

The Gaco F1850 described in this Research Report complies with, or is a suitable alternative to, what is specified in those Codes listed in Sections 1.0 and 2.0 of this report, subject to the following conditions:

5.1 Installation must comply with this Research Report, the manufacturer's published installation instructions, and the applicable Code. In the event of a conflict between the manufacturer's instructions and this report, this report governs.

5.2 The insulation must be separated from the interior living space of the building by a thermal barrier as described in Section 4.3, except as described in Sections 4.3.2 and 4.4.

5.3 The insulation must not exceed the thicknesses noted in Sections 3.2, 4.3, and 4.4, as applicable.

5.4 Use of the insulation in areas where the probability of termite infestation is "very heavy" must be in accordance with IRC Section R318.4 or IBC Section 2603.9 [2603.8], as applicable.

5.5 Jobsite certification and labeling of the insulation must comply with IRC Section N1101.12 [N1101.4 and N1101.4.1] and IECC Sections R303.1 [102.1.1 and 102.2.11], as applicable.

5.6 The insulation is produced at the Gaco Western LLC, manufacturing facility in Waukesha, Wisconsin, under a quality control program with inspections by Intertek Testing Services NA, Inc. (AA-647).

6.0 SUPPORTING EVIDENCE

6.1 Reports of tests in accordance with: ASTM C518, ASTM E84, ASTM E2178, ASTM E96 and ASTM C411.

6.2 Data in accordance with the ICC-ES Acceptance Criteria for Spray-applied Foam Plastic Insulation (AC 377), dated November 2012 (editorially corrected April 2013).

6.3 Intertek Listing Report "Gaco F1850 Spray-Applied Polyurethane Foam Insulation".

7.0 IDENTIFICATION

The A and B components of the insulation are identified with the manufacturer's name (Gaco Western, LLC), address and telephone number, the product name (Gaco F1850); use instructions; the flame spread and smoke-development indices; the lot number; the Intertek Mark; and the Research Report number (CCRR-1043).

8.0 OTHER CODES

This section does not apply.

9.0 CODE COMPLIANCE RESEARCH REPORT USE

9.1 Approval of building products and/or materials can only be granted by a building official having legal authority in the specific jurisdiction where approval is sought.

9.2 Code Compliance Research Reports shall not be used in any manner that implies an endorsement of the product by Intertek.

9.3 Reference to the Intertek website address at <https://whdirectory.intertek.com> is recommended to ascertain the current version and status of this report.

This Code Compliance Research Report ("Report") is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this Report. Only the Client is authorized to permit copying or distribution of this Report and then only in its entirety, and the Client shall not use the Report in a misleading manner. Client further agrees and understands that reliance upon the Report is limited to the representations made therein. The Report is not an endorsement or recommendation for use of the subject and/or product described herein. This Report is not the Intertek Listing Report covering the subject product and utilized for Intertek Certification and this Report does not represent authorization for the use of any Intertek certification marks. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek.

TABLE 1 – PROPERTIES EVALUATED

PROPERTY	IBC SECTION ¹	IRC SECTION ¹	IECC SECTION ¹
Physical properties	Not required	Not required	Not required
Surface-burning characteristics	2603.3	R316.3	Not applicable
Thermal barrier/ignition barrier	2603.4	R316.4	Not applicable
Air permeability	1301	R806.5 [R806.4]	C402.4 R402.4
Air Barrier	Not applicable	Not applicable	C402.4.1.2.1
Vapor retarder	1405.3.1	R702.7.1 [R601.3]	Not applicable
Thermal resistance	1301	N1101.12 N1102 [N1101.1]	C303.1.1 C303.1.4 R303.1.1 R30301.4 [102.1.1 102.2.11]
Duct Insulation	Not applicable	N1103.2.1 M1601.3	R403.2.1

¹Section numbers in parentheses refer to the 2009 codes.

TABLE 2 – THERMAL RESISTANCE (R Values)^{1,2,3}

THICKNESSES (inches)	R-VALUE (°F.ft ² .h/Btu)
1	6.5
2	14
3	21
3.5	25
4	29
5.5	40
6	43
7.25	52
8	58
9.25	67
10	72
11.25	81

For SI: 1 inch= 25.4 mm; 1 °F.ft².h/Btu = 0.176 110°K.m²/W

¹ R-values are calculated based on tested K-values at 1 inch and 3.5 inch thicknesses.

² R-values greater than 10 are rounded to the nearest whole number.

³ To determine R values for thickness not listed:

- a. between 1 inch and 3.5 inch can be determined through linear interpolation; or,
- b. greater than 3.5 inches can be calculated based on R 7.2/inch