Reviewed for Code Compliance
Inspection Division
Portland, Maine

Date: 02/28/18

ROOM FINISH SCHEDULE

ROOM #	ROOM NAME	WALLS					FLOOR	CEILINGS			REMARKS
		NORTH	EAST	SOUTH	WEST	BASE		MATL.	HEIGHT	RATING	
100	CORRIDOR	1	1	1	1	10	20	31	-	-	
101	RETAIL 1	1	1	1	1	10	20	30	-	-	
102	RETAIL 2	1	1	1	1	10	20	30	-	-	
103	RETAIL 3	1	1	1	1	10	20	30	-	-	
104	RETAIL 4	1	1	1	1	10	20	30	-	-	
105	RETAIL 5	1	1	1	1	10	20	30	-	-	
106	UNISEX TOILET	2	2	2	2	10	20	31	-	-	
107	UNISEX ADA TOILET	2	2	2	2	10	20	31	-	-	

FINISH SCHEDULE KEY

WALLS	
1	GWB - PAINTED
2	MOISTURE RESISTANT GWB - PAINTED
BASE	
10	VINYL BASE
FLOORS	
20	VINYL PLANK FLOORING
CEILINGS	
30	GWB - PAINTED
31	2'X2' ACT CEILING TILES

ROOM FINISH GENERAL NOTES

1. ALSO SEE INTERIOR ELEVATIONS FOR GRAPHIC DEPICTION'S OF EXTENT OF FINISHES
2. INSTALL MOISTURE RESISTANT (MOLD AND MILDEW RESISTANT) GWB IN ALL AREAS WHERE PLUMBING FIXTURES EXIST (CEILING AND WALLS IN BATHROOMS)
3. CLOSETS SHALL BE FINISHED AS THE ROOMS THEY SERVICE
5. PROVIDE APPROPRIATE BLOCKING IN WALLS OF ALL BATHROOMS BEHIND FIXTURES, PARTITIONS AND ACCESSORIES. PROVIDE BLOCKING FOR GRAB BARS IN WALLS OF BATHROOMS
6. PROVIDE APPROPRIATE BLOCKING IN WALLS FOR DOOR STOPS
8. UNLESS OTHERWISE NOTED IN DRAWINGS THE TYPICALWALL TYPE IS 'NA'. ALL OTHER PARTITION TYPES WILL BE INDICATED.
9. VERIFY UNDERLAYMENT MEETS MANUFACTURERS SPECIFICATION AT RESILIENT FLOORING
10. GENERAL CONTRACTOR TO INCLUDE A MINIMUM OF 6 (SIX) INTERIOR PAINT COLORS TO BE USED THROUGHOUT THE BUILDING
11. PROVIDE HARDWOOD TRANSITIONS (SILLS) AT DOOR SILLS WHERE FLOORING TRANSITIONS FROM HARDWOOD TO RUBBER FLOORING WITH ACCESSIBLE PROFILE

PAINT SCHEDULE KEY

TAG	COLOR
P1	XXXXX
P2	XXXXX
P3	XXXXX
P4	XXXXX
P5	XXXXX
P6	XXXXX
P7	XXXXX
P8	XXXXX
P9	XXXXX

REGISTERED ARCHITECT
RYAN J. SENATORE
No. 3322
STATE OF MAINE

© 2017 RYAN SENATORE ARCHITECTURE

93 WASHINGTON AVE.
PORTLAND, MAINE

RSA
RYAN SENATORE
ARCHITECTURE
565 CONGRESS STREET
PORTLAND, MAINE 04101
207-650-6414
senatorearchitecture.com

CONSULTANTS:

REVISIONS:

DATE:	JULY 22, 2017
PROJECT No.	1626
DRAWN BY:	RJS / RRT
CHECKED BY:	RJS
SCALE:	AS NOTED

SHEET TITLE:
FINISH SCHEDULE

A7-2