Reviewed for Code Compliance
Inspection Division
Portland, Maine
Date: 02/28/18

1 WINDOW TYPES
1/4" = 1'-0"

WINDOW SCHEDULE LEGEND

T = TEMPERED GLASS
FG = FIBERGLASS
AL = ALUMINUM
DH = DOUBLE HUNG
AW = AWNING
LV = LOUVER
F = FIXED
GL = GLIDER
OC = OPERABLE CASEMENT
O/F S = OPERABLE / FIXED STOREFRONT

WINDOW SCHEDULE

KEY	ACTION	ROUGH * OPENING (WxH) VIF	R.O. HEIND HEIGHT FROM SUB FLOOR	DETAILS HEAD	DETAILS JAMB	DETAILS SILL	MATERIAL	FINISH	FOR TEMPERED GLASS LOCATIONS SEE WINDOW ELEVATION TYPES FOR MASONRY OPENING DIMENSIONS COORDINATE COURSING WITH EXTERIOR ELEVATION SHEETS AND PLAN AND SECTION DETAIL SHEETS REMARKS
A	F	4'-0" X 5'-0"	-	-	-	-	-	-	FIXED THERMALLY BROKEN STOREFRONT
B	F	8'-0" X 5'-0"	-	-	-	-	-	-	FIXED THERMALLY BROKEN STOREFRONT

WINDOW NOTES:

1.) COORDINATE AND ADJUST ROUGH OPENING DIMENSIONS TO ACCOMMODATE SILL PAN FLASHING SYSTEM

2.) ALL WINDOW UNITS AND MULTI-WINDOW UNIT COMBINATIONS TO MEET OR EXCEED DP-50 RATINGS FOR BOTH STRUCTURAL AND WATER

3.) ALL GLAZING LOCATED WITHIN 18" OF FINISHED FLOOR TO BE TEMPERED GLASS

4.) ALL EXTERIOR GLAZING TO BE INSULATED

5.) FRAME ALL OPENINGS WITH ELEVATIONS

6.) SEAL WINDOW TO ROUGH OPENING WITH LOW EXPANDING FOAMINSULATION - SEE DETAILS

7.) MINIMUM VISIBLE TRANSMITTANCE "VT" OF ALL GALLS TO BE 0.7 OR GREATER

STOREFRONT INFORMATION

1.) ALL STOREFRONT TO BE THERMALLY BROKEN WITH INSULATED GLAZING UNITS WITH LOW-E COATING ARGON FILLED UNITS

2.) TEMPER ALL GLASS AS REQUIRED BY BUILDING CODE

3.) PROVIDE SUB SILLS WITH DRAINED PANS WITH END AND BACK DAMS

4.) FOR STOREFRONT FRAME GEOMETRY AND ARRANGEMENTS SEE EXTERIOR BUILDING ELEVATIONS

5.) G.C. TO FIELD MEASURE ALL STOREFRONT UNITS PRIOR TO ORDER

REGISTERED ARCHITECT
RYAN J. SENATORE
No. 3322
STATE OF MAINE

© 2017 RYAN SENATORE ARCHITECTURE

93 WASHINGTON AVE.
PORTLAND, MAINE

RSA
RYAN SENATORE
ARCHITECTURE
565 CONGRESS STREET
PORTLAND, MAINE 04101
207-650-6414
senatorearchitecture.com

CONSULTANTS:

REVISIONS:

DATE:	JULY 22, 2017
PROJECT No.	1626
DRAWN BY:	RJS / RRT
CHECKED BY:	RJS
SCALE:	AS NOTED

SHEET TITLE:
WINDOW SCHEDULE

A7-1