

## Framing Members

- a. Pressure treated 6" x 6"  
14' span, 1 post on both ends, one post in middle,  
5.5' apart.
- b. Pressure treated 2x12x14'
- c. 2  $\frac{3}{4}$ " galvanized lags every foot.
- d. First Floor deck = 2x12x11', span is 11', #  
2nd Floor deck = 2x12x14', span is 11' to 4x12x14'  
carring beam, with a 3' cantilever.
- e. Pressure treated 2x12x11 (first floor deck), 16" on center,  
11' span  
2nd floor deck 2x12x14, 16" on center, 11' span  
to carring beam, 3' cantilever.
- f. 2x12 joist hangers