

NFPA 101 2009 & 220 2006: CODE DATA

USE GROUP CLASSIFICATION	SEPERATED MIXED USE (B/R-3)	
TYPE OF CONSTRUCTION	5(0,0,0) (SEE NOTE #1)	
EXISTING BUILDING AREA	EXISTING TO REMAIN	
PROPOSED BUILDING AREA	EXISTING TO REMAIN	
TOTAL AREA	2,591 sqft	
BUILDING HEIGHT (STORIES/ FEET)	3	
BUILDING AREA LIMITATION - SQ FT	EXISTING TO REMAIN	
BUILDING HEIGHT LIMITATION - STORIES	EXISTING TO REMAIN	
TRAVEL: COMMON PATH LIMIT (ALLOWABLE/ ACTUAL)	100'/ NONE	
TRAVEL: DEAD-END LIMIT (ALLOWABLE/ ACTUAL)	50'/ NONE	
TRAVEL: EXIT ACCESS TRAVEL DISTANCE LIMIT (ALLOWABLE/ ACTUAL)	300'/ 56' (RESIDENTIAL)	
FIRE SUPPRESSION SYSTEM	NONE	
NUMBER OF REQUIRED EXITS	BUSINESS - ONE	
	RESIDENTIAL - ONE PRIMARY & ONE SECONDARY	
EXIT ACCESS FIRE RATINGS		
FIRE WALLS/ BARRIERS		
OCCUPANCY SEPARATION	2 HR	
PARTY WALLS	ETR	
STAIR ENCLOSURES	2 HR	
SHAFTS	ETR	
EXIT ACCESS CORRIDORS	ETR	
FIRE PROTECTION OF STRUCTURE		
COLUMNS	ETR	
BEAMS, GIRDERS, TRUSSES & ARCHES	ETR	
LOAD BEARING WALLS - EXTERIOR	ETR	
LOAD BEARING WALLS - INTERIOR	ETR	
NON-LOAD BEARING WALLS - EXTERIOR	ETR	
NON-LOAD BEARING WALLS - INTERIOR	ETR	
FLOOR CONSTRUCTION	ETR	
ROOF CONSTRUCTION	ETR	
OCCUPANT LOAD	2,591 People	20
BUSINESS -BASEMENT	430 SF	100 SF/ PERSON = 4
BUSINESS - 1st FLOOR	894 SF	100 SF/ PERSON = 9
RESIDENTIAL (R-2)		
2nd FLOOR (NO WORK IN THIS AREA)	726 SF	200 SF/ PERSON = 4
3rd FLOOR (NO WORK IN THIS AREA)	541 SF	200 SF/ PERSON = 3

GENERAL NOTES:

Area of work is at tenant entry point & a reconfiguration of doors; no addition of space.