

1. Construction of dog house as follow
2. Dog house is to be 5 ½ feet wide 10 ft. to peak and 4 ft. deep
3. Wall construction to be 2 by 4 construction 16 inches on center
4. Floor to be 2 by 8 construction 16 on center with joist hangers
5. Dog house to be anchored to building
6. Front of dog house to be supported by 2 12 inch sona tubes 4 feet below grade
7. Roof rafters to be built with ¾ inch plywood gluing 2 together and placing 16 on center
8. Roof to be 3 layers of ¼ inch wacky board to it can be bent to make the crown in roof
9. Shingles to be 3 tab asphalt
10. All building materials ether meet our exceeds building codes