FAN PERFORMANCE SCHEDULE

TAG	AIRFLOW (CFM)	T.S.P (IN.W.G)	NOISE (SONES)	RPM	DRIVE	ELECTRICAL REQUIREMENTS					BASIS OF DESIGN = (G) GREENHECK (P) PANASONIC		
						HP	BHP	WATTS	AMPS	V/PH/HZ	SERVICE	ARRANGEMENT	MODEL
EF-1	PROVIDED BY KITCHEN EQUIPMENT SUPPLIER, INSTALLED BY MECHANICAL CONTRACTOR												
EF-2	PROVIDED BY KITCHEN EQUIPMENT SUPPLIER, INSTALLED BY MECHANICAL CONTRACTOR												
EF-3	50	0.25	0.7	1072	DIRECT	-	-	65	-	120/1/60	TOILET EXHAUST	CEILING-WALL	(P) FV-05-11VK51
EF-4	75	0.25	0.7	1072	DIRECT	-	-	65	-	120/1/60	STORAGE VENTILATION	CEILING-WALL	(P) FV-05-11VK51
EF-5	50	0.25	0.7	1072	DIRECT	-	-	65	-	120/1/60	OFFICE VENTILATION	CEILING-WALL	(P) FV-05-11VK51

EF-3 SHALL OPERATE FROM A WALL MOUNTED SWITCH
EF-4 AND EF-5 SHALL OPERATE DURING THE OCCUPIED PERIOD AS DETERMINED BY A GRASS-LIN 7-DAY PROGRAMMABLE TIMECLOCK.

TEMPERATURE MIXING VALVE PERFORMANCE SCHEDULE

TAG	FLOW RATE (GPM)	INLET CONNECTION (INCHES)	OUTLET CONNECTION (INCHES)	W.P.D (PSIG)	SET POINT (DEGREES F)	PROVIDE SPARE CARTRIDGE (Y) OR (N)	BASIS OF DESIGN = SYMMONS		
							SERVICE	ARRANGEMENT	MODEL
TMV-1	4.0	1/2"	1/2"	12.0	110°F	Y	DOM HW	WALL	7-102-W

EXPANSION TANK PERFORMANCE SCHEDULE

TAG	TANK VOLUME (GAL)	ACCEPTANCE VOLUME (GAL)	MIN. REQ'D. ACCEPT.VOL. (GAL)	MAX. WORK'G. TEMPERATURE (DEG F)	MAX. WORK'G. PRESSURE (PSI)	WEIGHT (LBS)	BASIS OF DESIGN = AMTROL		
							MOUNTING	SERVICE	MODEL
ET-1	4.4	4.4	4.4	240	125	90	INLINE	DOM HW	ST-12

ELECTRIC UNIT HEATER PERFORMANCE SCHEDULE

TAG	OUTPUT (MBH)	AIRFLOW (CFM)	MTG.HT. AFF (IN)	ELECTRICAL REQUIREMENTS		BASIS OF DESIGN = BERKO	
				KW	V/PH/HZ	SERVICE	MODEL
EUH-1	17	350	*	5.0	208/3/60	BACK ROOM	HUHAA520

* - 12" BELOW CEILING

ELECTRIC WALL HEATER PERFORMANCE SCHEDULE

TAG	OUTPUT (MBH)	AIRFLOW (CFM)	MTG.HT. AFF (IN)	ELECTRICAL REQUIREMENTS		BASIS OF DESIGN = BERKO	
				KW	V/PH/HZ	SERVICE	MODEL
EWH-1	6.1	100	12"	1.8	120/1/60	MULTIPLE	FRA1812F TEST

GAS WATER HEATER PERFORMANCE SCHEDULE

TAG	STORAGE (GALS)	GPM @ 100°F RISE	HEATING INPUT BTU/Hr	ELEC V/PH/HZ	BASIS OF DESIGN - RINNAI	
					SERVICE	MODEL
GWH-1	0	3.8	199,000	120/1/60	DOM HW	C199I

PLUMBING FIXTURE CONNECTION SCHEDULE

TAG	DESCRIPTION	SAN	VENT	CW	HW
P-1	ADA TANK TYPE WATER CLOSET	3"	2"	3/4"	-
P-2	ADA WALL HUNG LAVATORY	1-1/2"	1-1/2"	1/2"	1/2"
FD-1	FLOOR DRAIN	3"	2"	1/2" *	-
FS-1	FLOOR SINK	3"	2"	1/2" *	-

MINIMUM SIZE OF BELOW SLAB SANITARY & VENT PIPING SHALL BE 2".
* - FLOOR DRAINS SHALL HAVE TRAP PRIMER CONNECTION SERVED FROM NEAREST FIXTURE.

EQUIPMENT UTILITY SCHEDULE

CustomColumn4	ITEM NO.	QTY	ITEM DESCRIPTION	MFR	MODEL	ELECTRICAL							PLUMBING							
						VOLTS	PH	AMPS	KW	HP	CONN.	NEMA	CW (IN)	HW (IN)	IW	DW	GAS SIZE	MBTU	REMARKS	ITEM NO.
	1	6	FRYERS	NIC	BY OTHERS	X	X	X			X						X	X	ALL TRADES SHALL VERIFY DIMENSIONS AND UTILITY REQUIREMENTS PRIOR TO ROUGH-INS.	1
	2	1	ICE CUBER	HOSHIZAKI	KM-515MAH	115	1	11.7			DR	5-15P	1/2"		3/4"					2
	2A	1	ICE BIN FOR ICE MACHINES	HOSHIZAKI	B-300PF										3/4"					2A
	2B	1	WATER FILTRATION SYSTEM	EVERPURE	EV932422								3/4"						G.C. SHALL PROVIDE WALL BLOCKING AS REQUIRED.	2B
	3	1	GRIDDLE, GAS	NIC	BY OTHERS												X	X	ALL TRADES SHALL VERIFY DIMENSIONS AND UTILITY REQUIREMENTS PRIOR TO ROUGH-INS.	3
	4	1	REFRIGERATED EQUIPMENT STAND	NIC	BY OTHERS	X	X	X			X	X							ALL TRADES SHALL VERIFY DIMENSIONS AND UTILITY REQUIREMENTS PRIOR TO ROUGH-INS.	4
	5	1	TWO BURNER HOT PLATE, GAS	NIC	BY OTHERS												X	X	ALL TRADES SHALL VERIFY DIMENSIONS AND UTILITY REQUIREMENTS PRIOR TO ROUGH-INS.	5
	6	1	STORAGE SHELVING	CENTAUR	EPOXY														TO CONSIST OF FOUR (4) TIERS ON 74" HIGH POSTS.	6
	7	1	WORK TABLE, STAINLESS STEEL TOP	ADVANCE TABCO	AG-364															7
	8	1	DOUBLE OVERSHELF	TRIMARK	FABIRCATE														ALL S/S CONSTRUCTION 13" X 16", 4" SECTION W/ THREE (3) SHELVES, PROVISIONS FOR #9 HEAT LAMP.	8
	9	1	HEAT LAMP	MARSHALL AIR	500794	120		1.3	1.75		JBH									9
	10	1	COOK AND HOLD OVEN	NIC	BY OTHERS	X	X	X			X	X							ALL TRADES SHALL VERIFY DIMENSIONS AND UTILITY REQUIREMENTS PRIOR TO ROUGH-INS.	10
	11	1	MEGA TOP SANDWICH / SALAD PREPARATION REFRIGERATOR	HOSHIZAKI	CRMR48-18M	115	1	15.0		1/6	DR	5-15P								11
	12	1	THREE (3) COMPARTMENT SINK	ADVANCE TABCO	93-63-54-18R											(3) 1-1/2"				12
	12A	1	PRE-RINSE FAUCET ASSEMBLY	T&S BRASS	B-0133-BJ								1/2"	1/2"					G.C. SHALL PROVIDE WALL BLOCKING AS REQUIRED.	12A
	12B	1	ADD ON FAUCET, FOR PRE RINSE FAUCET	T&S BRASS	B-0156															12B
	12C	3	DRAIN, LEVER / TWIST WASTE	T&S BRASS	B-3952										2"				NOT SHOWN ON PLAN.	12C
	13	1	WORK TABLE, STAINLESS STEEL TOP	ADVANCE TABCO	AG-365															13
	14	1	MOP SINK CABINET	ADVANCE TABCO	9-OPC-84											2"				14
	14A	1	SERVICE FAUCET	T&S BRASS	B-0665-BSTR								1/2"	1/2"					G.C. SHALL PROVIDE WALL BLOCKING AS REQUIRED.	14A
	15	1	EXHAUST HOOD	NIC	BY OTHERS	X	X	X			X	X							ALL TRADES SHALL VERIFY DIMENSIONS AND UTILITY REQUIREMENTS PRIOR TO ROUGH-INS.	15
	15A	1	EXHAUST FAN	NIC	BY OTHERS	X	X	X			X	X							ALL TRADES SHALL VERIFY DIMENSIONS AND UTILITY REQUIREMENTS PRIOR TO ROUGH-INS.	15A
	15B	1	MAKE UP AIR FAN	NIC	BY OTHERS	X	X	X			X	X							ALL TRADES SHALL VERIFY DIMENSIONS AND UTILITY REQUIREMENTS PRIOR TO ROUGH-INS.	15B
	15C	1	FIRE PRETECTION SYSTEM	NIC	BY OTHERS	X	X	X			X	X							ALL TRADES SHALL VERIFY DIMENSIONS AND UTILITY REQUIREMENTS PRIOR TO ROUGH-INS.	15C
	16	1	MIXER, DRINK / BAR	WARING	DMC201DCA	120	1	1.56			DR	5-15P								16
	17	1	SPARE NUMBER	CUSTOM																17
	18	2	INDUCTION FOOD PAN WARMER, DROP-IN	VOLLRATH	741101DW	120	1	2.1	.25		DR	5-15P							W/ INSERT FOR INDUCTION RETHERMALIZER, VEGETABLE INSET COVER, AND DECORATIVE RING.	18
	19	1	DRAFT BEER COOLER	NIC	BY OTHERS	X	X	X			X	X							ALL TRADES SHALL VERIFY DIMENSIONS AND UTILITY REQUIREMENTS PRIOR TO ROUGH-INS.	19
	20	1	SODA DISPENSER	NIC	BY OTHERS	X	X	X			X	X	X						ALL TRADES SHALL VERIFY DIMENSIONS AND UTILITY REQUIREMENTS PRIOR TO ROUGH-INS.	20
	21	1	HAND SINK	ADVANCE TABCO	7-PS-22								1/2"	1/2"		1-1/2"				21
	22	1	WALK IN COOLER	NORLAKE	WIC-810	120	1	15.0			JBH								6'-0" X 6'-0", W/ ONE (1) 30" DOOR, NO FLOOR, LED LIGHT(S), GRAY GALVALUME INTERIOR/EXTERIOR, 36" HIGH DIAMOND TREADPLATE WAINSCOTING WHERE EXPOSED AND ON INTERIOR/EXTERIOR OF DOOR, TRIM STRIPS AND ENCLOSURE PANELS.	22
	22A	1	WALK IN COOLER EVAPORATOR	NORLAKE	CUSTOM	X	X	X			JBH				3/4"				VERIFY AND COORDINATE UTILITIES WITH MANUFACTURER'S FINAL APPROVED SHOP DRAWINGS.	22A
	22B	1	WALK IN COOLER CONDENSER	NORLAKE	CUSTOM	X	X	X			JBH								VERIFY AND COORDINATE UTILITIES WITH MANUFACTURER'S FINAL APPROVED SHOP DRAWINGS.	22B
	23	5	STORAGE SHELVING	CENTAUR	EPOXY														TO BE FOUR (4) AND THREE (3) TIER HIGH ON 74" AND 63" POSTS.	23
	24	2	STORAGE SHELVING	CENTAUR	EPOXY														TO BE FOUR (4) TIER HIGH ON 74" POSTS.	24
	25	1	HAND SINK	CENTAUR	SSHAND-2SSNO											1-1/2"				25
	25A	1	WALL / SPLASH MOUNT FAUCET	T&S BRASS	B-1146-01								1/2"	1/2"						25A
	26	1	PREP SINK	NIC	BY OTHERS								X	X	X				VERIFY AND COORDINATE UTILITIES WITH MANUFACTURER'S FINAL APPROVED SHOP DRAWINGS.	26
	27	1	WORK TABLE, STAINLESS STEEL TOP	ADVANCE TABCO	SS-304															27
	28	1	ICE CREAM DIPPING CABINET	MASTER-BILT	DC-25	115	1	5.7		1/4	DR	5-15P							W/ DIPPER WELL.	28
	29	1	"L" SHAPED COUNTER	TRIMARK	FABIRCATE														ALL S/S CONSTRUCTION "L" SHAPED 3'-7" X 5'-8" W/ 6" X 42" TRAY REST.	29
	30	1	SOUP COUNTER	TRIMARK	FABIRCATE														ALL S/S CONSTRUCTION 6'-6" X 15" WIDE W/ 10" X 10" X 10" X 5" DEEP SINK BOWL W/ APRON. PROVISIONS FOR DROP-IN SOUP WARMERS ON RIGHT.	30
	30A	1	DECK MOUNT FAUCET	T&S BRASS	B-0325								1/2"	1/2"						30A
	31	2	SHELVING, WALL-MOUNTED	ADVANCE TABCO	WS-18-36														G.C. SHALL PROVIDE WALL BLOCKING AS REQUIRED.	31
	32	1	WALK IN FREEZER	NORLAKE	CUSTOM	208-230	1	15.0		1	JBH								6'-6" X 6'-7", W/ ONE (1) 30" DOOR, WITH FLOOR, LED LIGHT(S), 26 GAUGE EMBOSSED COATED STEEL INTERIOR/EXTERIOR, 36" HIGH DIAMOND TREADPLATE WAINSCOTING WHERE EXPOSED AND ON INTERIOR/EXTERIOR OF DOOR, TRIM STRIPS AND ENCLOSURE PANELS.	32
	32A	1	WALK IN COOLER EVAPORATOR	NORLAKE	CUSTOM	X	X	X			JBH								VERIFY AND COORDINATE UTILITIES WITH MANUFACTURER'S FINAL APPROVED SHOP DRAWINGS.	32A
	32B	1	WALK IN COOLER CONDENSER	NORLAKE	CUSTOM	X	X	X			JBH				3/4"				VERIFY AND COORDINATE UTILITIES WITH MANUFACTURER'S FINAL APPROVED SHOP DRAWINGS.	32B

NOTE - SEE FOOD SERVICE EQUIPMENT PLAN K101 FOR FINAL EQUIPMENT SELECTIONS AND LOCATIONS

MECHANICAL AND PLUMBING SYMBOLS AND ABBREVIATIONS LEGEND

NOTE - USE SYMBOLS AND ABBREVIATIONS AS APPLICABLE FOR THIS MECHANICAL DRAWING SET.
SOME SYMBOLS AND ABBREVIATIONS IN THIS LEGEND MAY NOT APPLY.

SYMBOL	DESCRIPTION
—CA—	COMPRESSED AIR PIPING (CA)
—C—	CONDENSATE DRAIN PIPING (C)
—CTR—	COOLING TOWER RETURN PIPING (CTR)
—CTS—	COOLING TOWER SUPPLY PIPING (CTS)
—CWR—	CHILLED WATER RETURN PIPING (CWR)
—CWS—	CHILLED WATER SUPPLY PIPING (CWS)
—FOR—	FUEL OIL RETURN PIPING (FOR)
—FOS—	FUEL OIL SUPPLY PIPING (FOS)
—G—	GAS PIPING (G)
—HWR—	HOT WATER RETURN PIPING (HWR)
—HWS—	HOT WATER SUPPLY PIPING (HWS)
—RL—	REFRIGERANT LIQUID PIPING (RL)
—RG—	REFRIGERANT GAS PIPING (RG)
- - - - - -	SANITARY PIPING BELOW FLOOR (SAN)
————	SANITARY PIPING ABOVE FLOOR (SAN)
— — — —	SANITARY VENT PIPING
—RWL—	RAINWATER LEADER ABOVE SLAB (RWL)
—·—·—·—	COLD WATER PIPING (CW)
—·—·—·—	HOT WATER PIPING (HW)
—·—·—·—	RECIRCULATED HOT WATER PIPING (RHW)
	PIPE CAP
	DIRECTION OF FLUID FLOW
	ELBOW UP
	ELBOW DOWN
	PIPE TEE UP
	PIPE TEE DOWN
	PIPE REDUCER
	PIPE WITH GUIDE
	PIPE WITH ANCHOR
	BUTTERFLY VALVE
	GS & Y GATE VALVE

SYMBOL	DESCRIPTION
	BACKFLOW PREVENTER (BFP)
	CHECK VALVE
	BALANCING VALVE (ADJUSTABLE)
	AUTOMATIC FLOW CONTROL VALVE
	RELIEF VALVE (RV)
	BALL VALVE
	BALL VALVE
	3/4" BALL VALVE WITH 3/4" HOSE END
	GATE VALVE
	PRESSURE REDUCING VALVE
	FUSIBLE VALVE
	STRAINER W/BLOWDOWN BALL VALVE
	2-WAY CONTROL VALVE
	SOLENOID VALVE
	3-WAY CONTROL VALVE
	3-WAY CONTROL VALVE (TOP VIEW)
	4-WAY CONTROL VALVE (TOP VIEW)
	2 BUTTERFLY VALVES W/SINGLE ACTUATOR
	BUTTERFLY VALVE W/ACTUATOR
	TRIPLE-DUTY VALVE
	UNION
	PIPE FLANGE
	PUMP WITH FLANGES
	BASE MOUNTED PUMP
	CARTRIDGE TYPE INLINE PUMP
	VERTICAL INLINE PUMP
FC	FLEXIBLE PIPE CONNECTION (FC)
	PITCH DOWN
	PETCOCK

SYMBOL	DESCRIPTION
	PRESSURE GAGE WITH GAGE COCK
	THERMOMETER IN WELL
	WATER FLOW SWITCH
	PRESSURE SWITCH OR SENSOR
	EMURSION TEMPERATURE SENSOR
	DUCT MOUNTED SMOKE DETECTOR
	ROOM TEMPERATURE SENSOR
	THERMOSTAT OR SENSOR ON WALL
	TSTAT OR SENSOR W/ TAMPERPROOF GUARD
	MANUAL AIR VENT
	NOTE TAG (NUMBER)
250	AIR DEVICE TAG (LETTER) WITH CFM
	ROOM NUMBER
	TURNING VANES
	DUCT W/MANUAL DAMPER
	DUCT W/FLEXIBLE CONNECTION (FC)
	LAGGED DUCT
	DUCT W/ACOUSTIC LINING
	DUCT W/SQUARE-TO-ROUND TRANSITION
	FLEXIBLE DUCT
MOD	MOTOR OPERATED DAMPER
	AIRFLOW OUT
	AIRFLOW IN
	DIAMETER OR FLAT OVAL
	FIRE DAMPER
	ROUND OR FLAT OVAL DUCT DOWN
	ROUND OR FLAT OVAL DUCT UP
	SUPPLY DIFFUSER
	RETURN GRILLE
	STEAM TRAP
	WATER HAMMER ARRESTOR

ABBREVIATION	DESCRIPTION
AAV	AUTOMATIC AIR VENT
AD	ACCESS DOOR
AFF	ABOVE FINISHED FLOOR
AHU-*	AIR HANDLING UNIT TAG
AMS	AIRFLOW MONITORING STATION
AMPS	AMPERES
AP	ACCESS PANEL
APD	AIR PRESSURE DROP
AS-*	AIR SEPARATOR TAG
ATC	AUTOMATIC TEMPERATURE CONTROL
BD-*	BYPASS DAMPER TAG
BFP-*	BACKFLOW PREVENTER TAG
BHP	BRAKE HORSEPOWER
BTUH	BRITISH THERMAL UNITS PER HOUR
CC-*	COOLING COIL TAG
CFM	CUBIC FEET PER MINUTE
CO	CLEANOUT
CP-*	CIRCULATING PUMP TAG
Cv	VALVE COEFFICIENT
CW	COLD WATER
DB	DRY BULB
dB RE	DECIBELS RELATIVE TO
DC	DOUBLE CHECK
DCA	DOUBLE CHECK ATMOSPHERIC
DEG F	DEGREES FAHRENHEIT
DIA	DIAMETER
DIW	DOWN IN WALL
DN	DOWN
EA	EXHAUST AIR
EAT	ENTERING AIR TEMPERATURE

ABBREVIATION	DESCRIPTION
EDB	ENTERING DRY BULB
EDC-*	ELECTRIC DUCT COIL TAG
EER	ENERGY EFFICIENCY RATIO
EF-*	EXHAUST FAN TAG
EFF	EFFICIENCY
ESP	EXTERNAL STATIC PRESSURE
ET-*	EXPANSION TANK TAG
EWB	ENTERING WET BULB
EWH-*	ELECTRIC WATER HEATER TAG
EWT	ENTERING WATER TEMPERATURE
EXG	EXISTING
EXH	EXHAUST
FC	FLEXIBLE CONNECTION
FCO	FLOOR CLEANOUT
FD	FIRE DAMPER
FD-*	FLOOR DRAIN TAG
FLA	FULL LOAD AMPS
FPHB	FROST PROOF HOSE BIBB
FPM	FEET PER MINUTE
FSD	COMBINATION FIRE & SMOKE DAMPER
FT	FEET
GA.	GAGE
GAL	GALLONS
GPH	GALLONS PER HOUR
GPM	GALLONS PER MINUTE
HC-*	HEATING COIL TAG
HP	HORSEPOWER
HRV-*	HEAT RECOVERY VENTILATOR TAG
HW	HOT WATER
HWS/R	HOT WATER SUPPLY AND RETURN

ABBREVIATION	DESCRIPTION
I=B=R	INSTITUTE OF BOILER AND RADIATOR MANUFACTURERS
IN.	INCHES
L-*	LOUVER TAG
LAT	LEAVING AIR TEMPERATURE
LB	POUNDS
LWS/R	LOOP WATER SUPPLY/RETURN
LRA	LOCKED ROTOR AMPS
LWCO	LOW WATER CUTOUT
LWT	LEAVING WATER TEMPERATURE
MAX	MAXIMUM
MBH	THOUSANDS OF BTU PER HOUR
MCA	MINIMUM CIRCUIT AMPACITY
MIN	MINIMUM
NC	NOISE CRITERION
NIC	NOT IN CONTRACT
NTS	NOT TO SCALE
OA	OUTSIDE AIR
OBD	OPPOSED BLADE DAMPER
O.D.	OUTSIDE DIAMETER
OED	OPEN ENDED DUCT
OPD	OVERCURRENT PROTECTIVE DEVICE
P-*	PLUMBING FIXTURE TAG
PENETN	PENETRATION
PF-*	PADDLE FAN TAG
PSIA	POUNDS PER SQUARE INCH ABSOLUTE
PSIG	POUNDS PER SQUARE INCH GAGE
PVC	POLYVINYL CHLORIDE (PIPE)
RA	RETURN AIR
RD	ROOF DRAIN
RDE	RECOMMENDED DUAL ELEMENT FUSE AMPS
RHW	RECIRCULATED HOT WATER

ABBREVIATION	DESCRIPTION
RLA	RUNNING LOAD AMPS
RPM	REVOLUTIONS PER MINUTE
RPS	REVOLUTIONS PER SECOND
RPZ	REDUCED PRESSURE ZONE
RTU	ROOM TEMPERATURE SENSOR
RV	RELIEF VALVE
RWL	RAINWATER LEADER
SA	SUPPLY AIR
SAN	SANITARY (DRAIN & WASTE)
SD	SMOKE DAMPER
SEER	SEASONAL ENERGY EFFICIENCY RATIO
SF	SUPPLY FAN
SP	STATIC PRESSURE
SQFT	SQUARE FEET
ΔT	TEMPERATURE DIFFERENTIAL
TEMP.	TEMPERATURE
TCP	TEMPERATURE CONTROL PANEL
TMV-*	THERMOSTATIC MIXING VALVE TAG
TSP	TOTAL STATIC PRESSURE
TYP	TYPICAL
UH-*	UNIT HEATER TAG
VB	VACUUM BREAKER
VFD	VARIABLE FREQUENCY INVERTER DRIVE
VTR	VENT THRU ROOF
V/PH/HZ	VOLTS/PHASES/HERTZ
WB	WET BULB
WCO	WALL CLEANOUT
WG	WATER GAGE
WPD	WATER PRESSURE DROP
WSA	WIRE SIZING AMPS
WTD	WATER TEMPERATURE DROP
W/	WITH

ISSUED FOR PERMIT

Bob's Clam Hut
109 Cumberland Avenue
Portland, Maine

OWNER
Bob's Clam Hut
315 U.S. Route 1
Kittery, Maine
Telephone: (207) 439-4233
Contact: Michael Landgarten

DESIGNER
Paul Bennett Architect PC
25 West 31st Street, Floor 7
New York, New York 10001
Telephone: (212) 209-1177
Contact: Lisa Wright

DESIGNER
Bennett Engineering, Inc.
7 Bennett Road, P.O. Box 297
Freeport, ME 04032
Telephone: (207) 865-9475
Contact: William Bennett

KITCHEN CONSULTANT
TriMark
505 Collins Street
South Attelboro, MA 02703-8039
Telephone: (508) 399-6000
Contact: Ed Dresser

REV. NO.	DATE	COMMENTS

PROJECT
Bob's Clam Hut
109 Cumberland Avenue
Portland, Maine

TITLE
MECHANICAL SCHEDULES, LEGEND AND DETAILS

DWG NO.
M-2.01

SEAL & SIGNATURE
STATE OF MAINE
STEPHEN D. DORE
No. 5607
LICENSED
PROFESSIONAL ENGINEER

PAGE

SCALE

ISSUED
29-DECEMBER-2017

REVISION
13-FEBRUARY-2018

DESIGNER
PAUL BENNETT ARCHITECT PC
25 WEST 31ST STREET, NEW YORK, NEW YORK 10014
TEL (212) 209-1177