

EXISTING ROOF ACCESS HATCH ?

REPAIR EXISTING CEILING SUPPORT
GRID OF 1X2 FURRING ON 2X3 CEILING JOISTS

WALL ASSEMBLIES

- 1
- 2HR FIRE RESISTIVE STAIR ENCLOSURE
STC 45
(1) LAYER 5/8" TYPE-X GYP BD ON RESILIENT CHANNEL APARTMENT SIDE
(2) LAYERS 5/8 GYP BD STAIR SIDE.
6D COATED NAILS 24" O.C.BASE LAYER
8D COATED NAILS 8"O.C. FACE LAYER
STAGGER JOINTS 24" EACH LAYER
90MIN DOOR ASSEMBLIES - SEE FLOOR PLANS

- 2
- 2HR FIRE RESISTIVE STAIR ENCLOSURE
(2) LAYER 5/8" TYPE-X GYP BD BASEMENT SIDE
(1) LAYER 5/8 GYP BD STAIR SIDE.
6D COATED NAILS 24" O.C.BASE LAYER
8D COATED NAILS 8"O.C. FACE LAYER
STAGGER JOINTS 24" EACH LAYER

FLOOR-CEILING ASSEMBLIES

- 3
- 1HR FLOOR-CEILING SEPARATION
STC 45
(1) LAYER 5/8" TYPE-X GYP BD ON RESILIENT CHANNEL

- 4
- (2) AYERS 5/8" TYPE X GYP BD
2HR FLOOR-CEILING SEPARATION UNDER STAIR SIDE HALLWAY

